

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	(22)N & TS-3	MARSHALL	21	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	SODDING SALT TOLERANT	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	TEMP EROSION CONTROL SEEDING	SUPPLEMENTAL WATERING
	SQ YD	POUND	POUND	POUND	POUND	UNITS
NE QUADRANTS	110	1.2	1.2	1.2	6	1.65
NW QUADRANTS	53	0.6	0.6	0.6	3	0.795
SE QUADRANTS	107	1.2	1.2	1.2	6	1.605
SW QUADRANTS	59	0.6	0.6	0.6	3	0.885
TOTAL	329	4	4	4	18	5

STATION	INLET REMOVAL	INLET TY A TY 20 F & G	SS CLASS A TY1-12"	TRENCH BACKFILL
	EACH	EACH	FOOT	CU YD
IL 17 & 1L 26			10	2
STA. 87+21.60, 36.02' RT		1		
STA. 87+26.67, 26.33' RT	1			
STA. 87+83.96, 25.10' RT	1			
STA. 87+92.61, 38.27' RT		1	16	2
TOTAL	2	2	26	4

LOCATION	BIT SURF REM 2 1/2"	BIT MATL PR CT	AGG PR CT	LEVELING BINDER (MM)	BIT CONC SURF CSE MIX D	CCC & G B-6.24	CCC & G B-6.24 REMOVAL	BIT BASE CSE 10"	EARTH EX
	SQ YD	GALLON	TONS	TONS	TONS	FOOT	FOOT	SQ YD	CU YD
IL 17	2173	174	5	122	182				
IL 26	1926	154	4	109	164				
NE QUAD						171	190	131	36.4
SE QUAD						198	202	30	8.3
NW QUAD						145	155	58	16.1
SW QUAD						184	181	13	3.6
TOTALS	4099	328	9	231	346	698	728	232	64

LOCATION	SIDEWALK REMOVAL	PCC SIDEWALK 4"	DETECTABLE WARNINGS
	SQ FT	SQ FT	SQ FT
NE QUADRANT	804	544	20
NW QUADRANT	495	415	20
SE QUADRANT	600	530	20
SW QUADRANT	478	435	20
TOTALS	2377	1924	80

LOCATION	DRIVEWAY PAVEMENT 8"	DRIVEWAY PAVEMENT REMOVAL
STATION	SQ YD	SQ YD
23+93.4		12
25+30	36	36
86+17	79	79
86+79	65	65
TOTAL	180	192

LOCATION	TEMP PVMT MKS 4" WHITE	TEMP PVMT MKS 4" YELLOW	TEMP PVMT MKS 6" WHITE	TEMP PVMT MKS 12" WHITE	TEMP PVMT MKS 24" WHITE	THERM PVMT MKS 4" YELLOW	THERM PVMT MKS 4" WHITE	THERM PVMT MKS 6" WHITE	THERM PVMT MKS 12' WHITE	THERM PVMT MKS 24' WHITE	RAISED REF PVMT MRK	RAISED REF PVMT MRK	SHORT TERM PVT MRK	WRK ZN PVMT MRK REM
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	SQ FT
	IL 17 WEST LEG	83	346	123	236	23	346	83.0	123.0	236.0	23.0	5.0	5.0	75
IL 17 EAST LEG	90	384	122	248	26	384	90.0	122.0	248.0	26.0	5.0	5.0	81	9
IL 26 NORTH LEG		392	132	204	24	392		132.0	204.0	24.0	5.0		81	9
IL 26 SOUTH LEG	67	368	97	188	18	368	67.0	97.0	188.0	18.0	5.0		78	9
TOTALS	240	1490	474	876	91	1490	240	474.0	876	91.0	20	10	315	36

LOCATION	SIGN STANDARD NUMBER	LEGEND	SIZE	QUANTITY	SIGN PANEL TYPE 1	METAL POST TYPE A
			IN.X IN.		SQ FT	FEET
NO PARKING HERE TO CORNER						
NW QUAD	R7-1C	NO PARKING HERE TO CORNER	12 X 18	1	1.5	12.5
SW QUAD	R7-1C	NO PARKING HERE TO CORNER	12 X 18	1	1.5	12.5
NE QUAD	R7-1C	NO PARKING HERE TO CORNER	12 X 18	1	1.5	12.5
TOTALS				4.5	4.5	37.5

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____