RECONSTRUCTION OF RUNWAY END 2

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	1,457	
AR108558	2/C #8 600 V UG CABLE IN UD	L.F.	251	
AR110014	4" DIRECTIONAL BORE	L.F.	560	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	56	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	280	
AR110714	ELECTRICAL MANHOLE 4'	EACH	3	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	2	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	2	
AR125950	ADJUST PLASI	EACH	1	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EACH	22	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	2	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EACH	1	
AR125967	RELOCATE REILS	PAIR	1	
AR125968	RELOCATE PAPI	EACH	1	
AR151450	CLEARING AND GRUBBING	ACRE	0.2	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	44,355	
AR152441	ON-SITE BORROW	C.Y.	1,126	
AR156513	SEPARATION FABRIC	S.Y.	5,948	
AR161616	CLASS C GATE - 16'	EACH	1	
AR201610	BITUMINOUS BASE COURSE	TON	704	
AR208540	OVERSIZED AGGREGATE	TON	802	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	2,718	
AR401610	BITUMINOUS SURFACE COURSE	TON	242	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	5,730	
AR602510	BITUMINOUS PRIME COAT	GAL.	761	
AR603510	BITUMINOUS TACK COAT	GAL.	613	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	41,018	
AR705410	POROUS BACKFILL	C.Y.	32	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	876	
AR705530	UNDERDRAIN INSPECTION HOLE	EACH	4	
AR705900	REMOVE UNDERDRAIN	L.F.	1,587	
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EACH	5	
AR901510	SEEDING	ACRE	28.2	
AR908510	MULCHING	ACRE	28.1	
AR908520	EXCELSIOR BLANKET	S.Y.	947	

DATE	REVISION	BY

DITMAR
DEKALB TAYLOR MUNICIPAL AIRPORT
IL. PROJ.: DKB-3448 AIP PROJ.: 3-17-0139-B42

HPS Project No. 8030STXYAD 0800
Filename R-003FLP.DWG
Scale N/A
Date 01/06/04

LAYOUT	MDR	01/06/04
DRAWN	MDR	01/06/04
REVIEWED	CAH	03/06/06

HANSON
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

REMOVE AND REGRADE RUNWAY END 2

SUMMARY OF QUANTITIES FOR RECONSTRUCTION OF RUNWAY END 2

APR 04, 2006 7:48 AM BAK
I:\AIRPORTS\DEKALB\B03-05TXYA\AIRPORT\SHEETS\RWY -2\R-003FLP.DWG