PROPOSED TAXIWAY "A" EXTENSION

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR108158	1\C #8 5KV UG CABLE IN UD	L.F.	6,092	
AR108554	2\C #4 600 V UG CABLE IN UD	L.F.	1,091	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	153	
AR110900	REMOVE DUCT	L.F.	82	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EA	1	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EA	1	
AR125470	MODIFY EXISTING SIGN PANEL	EA	1	
AR125565	SPLICE CAN	EA	3	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA	2	
AR125902	REMOVE BASE MOUNTED LIGHT	EA	1	
AR125904	REMOVE TAXI GUIDANCE SIGN	EA	2	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EA	34	
AR125962	RELOCATE BASE MOUNTED LIGHT	EA	2	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EA	2	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	34,621	
AR152441	ON-SITE BORROW EXCAVATION	C.Y.	2,976	
AR156513	SEPARATION FABRIC	S.Y.	6,078	
AR156530	TEMPORARY SEEDING	ACRE	16.0	
AR156544	RIPRAP-GRADATION NO. 4	S.Y.	192	
AR201610	BITUMINOUS BASE COURSE	TON	2,017	
AR208540	OVERSIZED AGGREGATE	TON	2,311	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	2,871	
AR401610	BITUMINOUS SURFACE COURSE	TON	667	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	4,165	
AR602510	BITUMIONOUS PRIME COAT	GAL	2,119	
AR603510	BITUMINOUS TACK COAT	GAL	1,754	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	3,875	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	46	
AR701524	24" RCP CLASS IV	L.F.	402	
AR701530	30" RCP CLASS IV	L.F.	303	
AR701536	36" RCP CLASS IV	L.F.	136	
AR701548	48" RCP CLASS IV	L.F.	116	
AR701612	12" RCP CLASS V	L.F.	1,418	
AR701900	REMOVE PIPE	L.F.	180	
AR705410	POROUS BACKFILL	C.Y.	167	
AR705524	4" PERFORATED UNDERDRAIN W/ SOCK	L.F.	2,644	
AR705630	UNDERDRAIN INSPECTION HOLE	EA	11	
AR705903	REMOVE UNDERDRAIN INSPECTION HOLE	EA	9	
AR751411	INLET-TYPE B	EA	1	
AR751540	MANHOLE 4'	EA	1	
AR751944	ADJUST MANHOLE - PAVEMENT	EA	2	
AR751945	ADJUST MANHOLE - NON PAVEMENT	EA	5	
AR752430	PRECAST REINFORCED CONC. FES 30"	EA	1	
AR752436	PRECAST REINFORCED CONC. FES 36"	EA	4	
AR752648	CONCRETE HEADWALL 48"	EA	1	
AR752903	REMOVE HEADWALL	EA	2	
AR770516	16" DUCTILE IRON SANITARY SEWER	L.F.	410	
AR770704	SANITARY MANHOLE 4'	EA	1	
AR770905	REMOVE SANITARY MANHOLE	EA	1	
AR770945	ADJUST SANITARY MANHOLE	EA	1	
AR800429	FIELD TILE TRACING	EACH	6	
AR800463	FIELD TILE REPAIR	EACH	6	
AR901510	SEEDING	ACRE	15.6	
AR901550	LIME AND FERTILIZER	ACRE	3.8	
AR908510	MULCHING	ACRE	15.2	
AR908520	EXCELSIOR BLANKET	S.Y.	2,149	

DATE	REVISION	BY

DITMAR

DEKALB TAYLOR MUNICIPAL AIRPORT

IL PROJ.: DKB-3448 AIP PROJ.: 3-17-0139-B42

HPS Project No. 80305TXYAD 0800
Filename R-003FLP.DWG
Scale N/A
Date 01/06/04

LAYOUT	MDR	01/06/04
DRAWN	MDR	01/06/04
REVIEWED	CAH	03/16/06

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

EXTEND TAXIWAY "A"

SUMMARY OF QUANTITIES FOR TAXIWAY "A" EXTENSION

APR 13, 2006 8:53 AM CAH
I:\AIRPORTS\DEKALB\803-05TXYA\AIRPORT\SHEETS\TWY-A EXT\R-003FLP.DWG