

WIDEN TAXIWAYS "A" & "C" FROM 35' TO 50'

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR108158	1\C #8 5KV UG CABLE IN UD	L.F.	7,014	
AR110552	EXTEND 2-WAY DUCT	L.F.	66	
AR110554	EXTEND 4-WAY DUCT	L.F.	30	
AR125447	TAXI GUIDANCE SIGN, 7 CHARACTER	EA	1	
AR125902	REMOVE BASE MOUNTED LIGHT	EA	1	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EA	55	
AR125962	RELOCATE BASE MOUNTED LIGHT	EA	7	
AR125964	RELOCATE TAXI-GUIDANCE SIGN	EA	3	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	6,812	
AR156513	SEPARATION FABRIC	S.Y.	9,833	
AR156544	RIPRAP-GRADATION NO. 4	S.Y.	45	
AR201610	BITUMINOUS BASE COURSE	TON	3,126	
AR201630	BITUMINOUS BASE TEST SECTION	EA	1	
AR208540	OVERSIZED AGGREGATE	TON	3,604	
AR208510	CRUSHED AGGREGATE BASE COURSE	TON	3,219	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,007	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	42	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	5,568	
AR602510	BITUMINOUS PRIME COAT	GAL	4,682	
AR603510	BITUMINOUS TACK COAT	GAL	2,719	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	8,712	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	8,029	
AR701518	18" RCP CLASS IV	L.F.	53	
AR701530	30" RCP CLASS IV	L.F.	26	
AR701536	36" RCP CLASS IV	L.F.	67	
AR705410	POROUS BACKFILL	C.Y.	197	
AR705524	4" PERFORATED UNDERDRAIN W/ SOCK	L.F.	5,307	
AR705630	UNDERDRAIN INSPECTION HOLE	EA	14	
AR705900	REMOVE UNDERDRAIN	L.F.	5,395	
AR705903	REMOVE UNDERDRAIN INSPECTION HOLE	EA	10	
AR752618	CONCRETE HEADWALL 18"	EA	2	
AR752630	CONCRETE HEADWALL 30"	EA	1	
AR752636	CONCRETE HEADWALL 36"	EA	2	
AR752903	REMOVE HEADWALL	EA	5	
AR901510	SEEDING	ACRE	7.5	
AR908510	MULCHING	ACRE	6.6	
AR908520	EXCELSIOR BLANKET	S.Y.	4,771	

DATE	REVISION	BY



AIP PROJ.: 3-17-0139-B42
IL PROJ.: DK8-3448

HPS Project No. 80305TXAD_0800		Date 01/06/04	
Drawings	R-005FLP.DWG	MDR	01/06/04
Scale	N/A	MDR	01/06/04
		CAH	02/22/06
LAYOUT			
DRAWN			
REVIEWED			



Hanson Professional Services, Inc.
1425 S. Main Street
Springfield, Illinois 62703-2686
Offices Nationwide

WIDEN TAXIWAYS A & C
FROM 35' TO 50'
SUMMARY OF QUANTITIES
FOR WIDENING OF TAXIWAYS
"A" & "C" FROM 35' TO 50'