

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				CONTRACT MAINTENANCE 100% STATE	CONTRACT MAINTENANCE 100% STATE
				BOX CULVERT	BOX CULVERT
				0004	0004
				S.N. 050-2542	S.N. 050-2543
20400800	FURNISHED EXCAVATION	CU YD	56	26	30
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	73	42	31
42000060	WELDED WIRE REINFORCEMENT	SQ YD	273	220	53
44004250	PAVED SHOULDER REMOVAL	SQ YD	58	58	
44201069	CLASS B PATCHES, TYPE IV, 18 INCH	SQ YD	53		53
44201106	CLASS B PATCHES, TYPE IV, 20 INCH	SQ YD	220	220	
44201299	DOWEL BARS 1 1/2"	EACH	66	44	22
44213200	SAWCUTS	FOOT	461	342	119
44213204	TIE BARS 3/4"	EACH	35	22	13
48101200	AGGREGATE SHOULDERS, TYPE B	TON	24	20	4
50102400	CONCRETE REMOVAL	CU YD	51	30	21
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12520	6770	5750
50800530	MECHANICAL SPLICERS	EACH	94	56	38
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2320	1470	850
54002060	EXPANSION BOLTS 3/4 INCH X 12 INCH	EACH	55	25	30



MODEL: D:\info\...
 FILE NAME: ...
 PROJECT: ...
 USER: ...
 DATE: ...

USER NAME = ronald.woodshank	DESIGNED - RW	REVISED -
DRAWN - RW	CHECKED - YP	REVISED -
PLOT SCALE = 100,000' / 1"	DATE - 9/26/2022	REVISED -
PLOT DATE = 3/24/2023		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: 50	SHEET 1	OF 3 SHEETS	STA. TO STA.

F.A.P. RTE. 786	SECTION (111)CLV, CLV-1	COUNTY LASALLE	TOTAL SHEETS 28	SHEET NO. 3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66M76	