



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2023

SUBJECT: D4 Traffic Maintenance Yard  
Section D4 Parking Lot Resurf 2023-1  
Peoria County  
Contract No. 68H67  
Item No. 39, June 16, 2023 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page 2 of the Special Provisions.
3. Revised sheets 3 and 7 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## **LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES**

Effective: August 3, 2007    Revised: July 31, 2009

The Contractor shall be responsible for locating existing and proposed IDOT electrical facilities (traffic signal, overhead lighting, Intelligent Transportation System, etc.) prior to performing any work at his/her own expense if required. The Contractor shall also be liable for any damage to IDOT facilities resulting from inaccurate locating.

The Contractor may obtain, on request, plans for existing electrical facilities from the Department.

The Contractor shall also be responsible for locating and providing protection for IDOT facilities during all phases of construction. If at any time the facilities are damaged, the Contractor shall immediately notify the Department and make all necessary arrangements for repair to the satisfaction of the Engineer. This work will not be paid for separately, but shall be included in the contract bid price.

## **PAVEMENT REMOVAL**

Any earth excavation required for aggregate, pavement or curb placement shall be included in the PAVEMENT REMOVAL pay item.

## **PCC PAVEMENT**

The Contractor shall adjust affected building downspouts as required during construction. Any damage to the downspouts shall be restored by the Contractor.

The Contractor shall construct the parking lot in two separate stages, East and West. Access to parking and access to overhead doors on east and west sides cannot be obstructed at the same time.

All edges of pavement to be removed adjacent to pavement to remain shall be full-depth sawcut.

## **BOLLARDS**

This work consists of furnishing and installing 8" diameter precast concrete bollards at the location as shown on the plans, Section 634 of the Standard Specifications, and this special provision. The bollards shall be painted Safety Yellow. The concrete bollard shall be a minimum of **6.0** feet in length, with a minimum of 2.5 feet embedded in the ground.

This work shall be paid at the contract unit price of Each for BOLLARDS.

Revised June 1, 2023