

FAP 801 (ILL 10)  
 FED 80%  
 STATE 20%  
 CHAMPAIGN COUNTY  
 URBAN  
 BOX CULVERT  
 0010  
 010-2038

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	FOOT	325	325
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2
* 78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS	SQ FT	62	62
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	325	325
* 78011000	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	62	62
* 78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	325	325
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6
A2000216	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2
X0323265	REMOVE EXISTING RIPRAP	SQ YD	114	114
A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2
X0900064	MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	296	296
B2010042	TREE, CHIONANTHUS VIRGINICUS (WHITE FRINGETREE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2
X2840105	GABION REMOVAL	CU YD	36	36
X2500002	POWDER COATING OF PARAPET RAILING AND BRIDGE FENCE RAILING	L SUM	1	1
X5427602	REMOVE EXISTING FLARED END SECTION	EACH	2	2
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1



\* SPECIALTY ITEM

MODEL: SDC.dwg (Sheet) FILE NAME: P:\EIT\m\2025 - IDOT FTB 194-40 DS V4 Kuhn Trello\Work Order\_1028-TransCAD\Project Drawings\05270581-cad10-shc-SDC.dwg

USER NAME = kulrich	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 0.16666633 / in.	CHECKED -	REVISED -
PLOT DATE = 3/20/2023	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: 1" = 1'-0" | SHEET 5 OF 6 SHEETS | STA. + TO STA. +

SECTION	4BR	COUNTY	CHAMPAIGN	CONTRACT NO.	70581
	so		7		