

1

Tree Removal and Seeding Schedule						
lane	station	offset	length ft	avg. width ft	Tree Removal acre	Seeding acre
WB	449+63	32 ft to 50 ft				
	to		516.0	18.0	0.21	0.21
	444+47	32 ft to 50 ft				
	442+90	32 ft to 50 ft				
	to		2652.0	18.0	1.10	1.10
	416+38	32 ft to 50 ft				
	378+70	32 ft to 50 ft				
	to		2562.0	18.0	1.06	1.06
	353+08	32 ft to 50 ft				
	352+27	32 ft to 50 ft				
	to		2251.0	18.0	0.93	0.93
	329+76	32 ft to 50 ft				
	323+43	32 ft to 50 ft				
	to		2320.0	18.0	0.96	0.96
	300+23	32 ft to 50 ft				
	296+22	32 ft to 50 ft				
	to		561.0	18.0	0.23	0.23
	290+61	32 ft to 50 ft				
	285+98	32 ft to 50 ft				
	to		958.0	18.0	0.40	0.40
	276+40	32 ft to 50 ft				
Subtotal Acre					4.9	4.9

Tree Removal and Seeding Schedule						
lane	station	offset	length ft	avg. width ft	Tree Removal acre	Seeding acre
WB	248+08	32 ft to 50 ft				
	to		1681.0	18.0	0.69	0.69
	231+27	32 ft to 50 ft				
	207+74	32 ft to 50 ft				
	to		1136.0	18.0	0.47	0.47
	196+38	32 ft to 50 ft				
	187+63	32 ft to 50 ft				
	to		387.0	18.0	0.16	0.16
	183+76	32 ft to 50 ft				
	180+86	32 ft to 50 ft				
	to		965.0	18.0	0.40	0.40
	171+21	32 ft to 50 ft				
	168+72	32 ft to 50 ft				
	to		1547.0	18.0	0.64	0.64
	153+25	32 ft to 50 ft				
	148+82	32 ft to 50 ft				
	to		2526.0	18.0	1.04	1.04
	123+56	32 ft to 50 ft				
	121+41	32 ft to 50 ft				
	to		281.0	18.0	0.12	0.12
	118+60	32 ft to 50 ft				
Subtotal Acre					3.5	3.5

Tree Removal and Seeding Schedule						
lane	station	offset	length ft	avg. width ft	Tree Removal acre	Seeding acre
WB	118+15	32 ft to 50 ft				
	to		2531.0	18.0	1.05	1.05
	92+84	32 ft to 50 ft				
	89+32	32 ft to 50 ft				
	to		68.0	18.0	0.03	0.03
	88+64	32 ft to 50 ft				
	76+12	32 ft to 50 ft				
	to		1594.0	18.0	0.66	0.66
	60+18	32 ft to 50 ft				
	54+38	32 ft to 50 ft				
	to		574.0	18.0	0.24	0.24
	48+64	32 ft to 50 ft				
	45+25	32 ft to 50 ft				
	to		436.3	18.0	0.18	0.18
	40+89	32 ft to 50 ft				
Sta. Eq. 265+05+65bk = 40+88.70ah						
	265+05.65	32 ft to 50 ft				
	to		2160.7	18.0	0.89	0.89
	243+45	32 ft to 50 ft				
	237+05	32 ft to 50 ft				
	to		1030.0	18.0	0.43	0.43
	226+75	32 ft to 50 ft				
	225+35	32 ft to 50 ft				
	to		980.0	18.0	0.40	0.40
	215+55	32 ft to 50 ft				
Subtotal Acre					3.9	3.9
Total Acre					12.3	12.3

1 REVISED 6-7-2023

REV. - MS

FILE NAME = S:\CONTRMAINT_CAD\72710 - IL 54 - TREE	USER NAME = Timothy.Sharp	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	REMOVAL (6-16-2023)\PLANS\72129-sh-5-schedule	DRAWN - DMS	REVISED - _____			71	(11-2+ 31-5)TR-1	SANGAMON	5	5	
	PLOT SCALE = 40.0000' / in.	CHECKED - _____	REVISED - _____			CONTRACT NO. 72710					
	PLOT DATE = 3/28/2023	DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT					