STRUCTURE GEOTECHNICAL REPORT

068-0509

Existing SN: 068-0017

IL 16 over Sangamon Creek **FAP 325 Section 18(B-2,B-3) Montgomery County**

> D-96-522-05 Contract 72984

Prepared By: Brian Laningham

IDOT Region 4 District 6

Geotechnical Unit 217-782-6709

Approved By: 3

Brian Laningham, P.E.

D-6 Geotechnical Engr.

Lic. #062-053757

Date: August 14, 2019

Date: 8 -14 - 19

Checked By:

Prepared For: Fehr-Graham

Consultans

Attachments: Preliminary TSL

Subsurface Profile

Boring Logs

Special Provisions

This Report has been prepared based on a 'Approved" preliminary General Plan Sheet dated April 2012. Contact the author if there are any questions regarding this Report or if there are modifications to structure location, size, geometry, or vertical alignment.

Electronic copies of boring logs are available upon request for inclusion in the plans. Calculations are also available upon request.

This Report has been prepared according to AASHTO Standard Specifications for Highway Bridges 7th Edition 2014 and the 2009 IDOT BBS Bridge Manual

Project Description and Proposed Structure Information

This project consists of the removal of the existing single span, closed abutment bridge and replacing it with a triple barrel box culvert. Work will be performed under stage construction.

The proposed structure consists of a triple 10' x 10' cast in place box culvert. Wingwalls are 16± ft long with a retained height from bottom of footing of 15.5± ft. There is approximately 3 ft of fill above the culvert.

Existing Structure and Site Investigation

The existing structure is a 32± ft span, 32± ft wide closed abutment bridge built in 1923. The abutments are founded on spread footings.

The existing structure is in level terrain. The existing approaches are at or near grade. Land use is a mix of pasture and rural residential. The creek has rip rap lined banks. Existing slopes are approximately 1.5H:1V or flatter. No slope stability or settlement problems have been observed. The channel banks are steeply sloped and are approximately 5 ft high.

New borings were advanced on the existing roadway at the northwest and southeast corners. Borings were advanced to a minimum of 27± ft below streambed by the District 6 drill crew according to AASHTO T 206 and the IDOT Geotechnical Manual.

Boring data indicates approximately 10 ft of silty clay and clay loam over clay loam till. Borings on roadways are filled to prevent a hazard immediately after drilling. As a result, no 24-hour water elevation observations were made. The boring data indicates groundwater was encountered at 670.2 ft.

Geotechnical Evaluation

Settlement. The proposed box culvert produces a net increase in loading. Empirical settlement calculations indicate less than 1.5 in of settlement at the upstream end of the box. At the downstream end the box culvert is founded on clay loam till with a high unconfined compressive strength. Settlement problems are not anticipated.

Slope Stability. The stability of a 1:1 temporary construction slope has been analyzed including excavation to elevation 662.5 ft. The resulting factor-of-safety is 2.3. No problems are anticipated.

Seismic Considerations. Seismic events are not a significant design consideration for culverts. No analysis is required.

Scour. A 100 year scour estimate has not been calculated for the proposed culvert. The design scour elevation should correspond to the bottom of wingwall footing elevation. Based on available information, the upstream design scour elevation is 662.7 ft, and the downstream design scour elevation is 662.5 ft. These elevations may be adjusted during final design.

Mining Activity. ISGS records indicate no mining beneath the proposed structure.

Foundation Evaluation

Culvert Barrel. A pre-cast culvert is feasible at this site. If the pre-cast alternative is selected, cast-in-place headwalls should be included. No ground improvement is required.

Wingwalls. Proposed wingwalls are approximately 16 ft long and have a design height of 15.5 ft. Based on the wingwall geometry and soil conditions a T-Type vertical cantilever design is recommended. Soil conditions provide adequate bearing capacity with less than one inch of settlement. A preliminary has been evaluated to assess spread footing feasibility. The details of the preliminary design are summarized in the following table. It is assumed the structure designer will perform a more detailed footing design. The T-type wall should be designed with no soil above the bottom of footing in the front to accommodate the design scour elevation. Contact the author if a new analysis is needed during final design.

| Bottom of Footing Elev. | 662.5 ft | | | | |
|-----------------------------|----------|--|--|--|--|
| Design Height | 15.5 ft | | | | |
| Fill Above Stem | 3.0ft | | | | |
| Equivalent Fluid Pressure | 45 pcf | | | | |
| Footing Width | 9.5 ft | | | | |
| Soil Cohesion Below Footing | 1.6 ksf | | | | |
| Soil Unit Weight | 120 pcf | | | | |

| Equivalent Uniform | 2.3 ksf | | | | |
|------------------------|---------|--|--|--|--|
| Bearing Pressure | | | | | |
| Q _{max} | 2.9 ksf | | | | |
| Q _{allowable} | 37 ksf | | | | |

Footing sliding resistance may be determined using undrained conditions in cohesive soil because it is unlikely drained conditions will occur. The preliminary footing width of 9.5 ft has adequate resistance to sliding. Factor of safety against sliding is 1.2, factor of safety against overturning is 2.3.

The following note should be included on the plans, "Contact the District Geotechnical Engineer to verify foundation conditions meet plan requirements."

Construction Considerations

Stage Construction. This project will be constructed under stage construction.

Temporary Soil Retention. Hard Till has been identified directly below the bottom of the proposed box culvert which does not permit adequate sheet pile embedment. Therefore, a Temporary Soil Retention System is required. A 1:1 temporary excavation slope is adequate. For Stage II if there is insufficient room for a 1:1 slope above Stage I construction, the area above the box should be included in the temporary retention system.

Excavation. Existing abutments should be removed to 2 ft below the proposed culvert barrel and should be backfilled with Rockfill - Foundation. The special provision is attached.

Backfill. Backfill should consist of <u>Granular Culvert Backfill</u>. The special provision is attached. A detail showing pay limits should be included. Pay limits include the temporary excavation limits in a section along the roadway and from edge of shoulder to edge of shoulder in a section along the culvert.


Ground Improvement. Minor ground improvement may be required beneath a portion of the culvert barrel. If required, additional <u>Rockfill – Foundation</u> may be used.














NOT TO HORIZONTAL SCALE

Illinois Department of Transportation Division of Highways IDOT

VARIATIONS IN SUBSURFACE CONDITIONS MAY EXIST BETWEEN BORINGS

▼ Completion
▼ after (refer to log) hours

WOH - Sampler Advanced by Weight of Hammer, WOP - Weight of Pipe B.S. - Before Seating

SUBSURFACE DATA PROFILE

Route: FAP 325

Section: 18(B-2,B-3)

County: Montgomery

SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date 10/27/10

| ROUTE FAP 325 | DESCRIPTIO | N | Cul | vert ca | ırrying | IL 16 over Sangamon Creek | _ LOGGE | LOGGED BY | | | oan |
|---|-------------------|---------------------------|-------------|-------------------|-----------------------|--|---------------|-----------------------|-----------------------|-------------|-----------------------|
| SECTION 18(B-2,B-3) LOCATION NE 1/4, SEC. 5, TWP. 10N, RNG. 1W, 3 PM | | | | | | | | | | | |
| COUNTY Montgomer | y DRILLING | HSA HAMMER TYPE 140# Auto | | | | | | | | | |
| STRUCT. NO. 068 Station 43 BORING NO. 1- Station 42 | +23.5 SE | D E P T H | B L O W S | U C S Qu | M O I S T | Surface Water Elev. 668 Stream Bed Elev. 667 Groundwater Elev.: ▽ First Encounter 670 | . <u>5</u> ft | D E P T H | B L O W S | U C S Qu | M O I S T |
| Station 42 Offset 8.0 Ground Surface Elev. | ft LT 679.2 ft | (ft) | /6" | (tsf) | (%) | ▼Upon Completion Plugge ▼After Hrs. Plugge | | (ft) | /6" | (tsf) | (%) |
| V Dark Gray Moist SILTY LOAM | | | | | | Gray Dry SANDY CLAY LOAM (Till) | 658.70 | | 5 30 | 10.0 E | 6 |
| | | | 0 | | | | , | | 39 7 | | |
| | | -5 | 2 2 | 1.1 B | 25 | | | -25 | 27 47 | 10.0 E | 8 |
| | | | 0 | 0.7 | 25 | | | _ | | | |
| | | | 2 | 0.7 S-12 | | Olive Brown Moist CLAY LOAM (Till) | 651.70 | | | | |
| Brown and Gray Moist CL LOAM FREE WATER | 670.70 .AY ∑ | | 1 1 2 | 0.6 B | 21 | | | -30 | 4 9 10 | 4.9 B | 16 |
| Gray and Brown Moist CL LOAM (Till) | 668.70 .AY | - | 0 | | | | | | | | |
| | | ***** | 1 2 | 0.8 B | 19 | | | | | | |
| Brown and Gray V. Moist | | -15 | 0 0 1 | 0.4 B | 21 | Brown Moist Clay Loam Till | | -35 | 2 18 23 | 7.1 S-12 | 10 |
| Moist | | | 1 5 | 1.6 | 11 | | | | | | |
| Minist | | | 7 | В | 1 1 | | | | | | |
| Gray | | | 9 14 | 4.0 S-12 | 8 | Olive Brown | 020.55 | | 5 15 24 | 8.7 S-14 | 11 |



SOIL BORING LOG

Page <u>1</u> of <u>2</u>

Date 10/29/10 ROUTE FAP 325 DESCRIPTION Culvert carrying IL 16 over Sangamon Creek LOGGED BY M. Tappan SECTION 18(B-2,B-3) LOCATION NE 1/4, SEC. 5, TWP. 10N, RNG. 1W, 3 PM 140# Auto COUNTY Montgomery DRILLING METHOD HAMMER TYPE М STRUCT. NO. 068-0509 Station 43+23.5 В U U М Surface Water Elev. ___ 668.7 ft Ε E L C 0 L С 0 Stream Bed Elev. Р O S 1 P 0 S Т Т W S T W S BORING NO. 2-NW Groundwater Elev.: Т S Н S Qu Qu Т **Station** ______ 43+65 662<u>.3</u> ft ⊽First Encounter Offset 23.0ft RT ▼Upon Completion 651.3 ft /6" /6" (ft) (%) (ft) (tsf) (%) ▼After ____ Hrs. (tsf) 678.8 Cuttings ft Ground Surface Elev. Dk Gray Moist SILTY CLAY (Fill) 658.30 Gray Dirty Med SANDY GRAVEL 2 1 2 8 1.1 16 Gray Dry CLAY LOAM (Till) 17 3 S-10 19 1 Gray Moist Silty Clay Fill 0.9 25 42 12.2 2 58/5" S-10 2 В Gray Moist SILTY CLAY (Till) 1 2 17 1.3 2 В V 14 w/Gray Wet Med Sandy Gravel at 1 0.9 21 11 4.4 17 S-12 2 В Gray and Brown Wet CLAY LOAM (Till) 0 0 0.3 1 В 1 2.9 20 8.7 12 Gray and Brown Moist 5 10 Brown 9 В 44 S-10 1 Gray Moist Clay Loam Till 4 1.9 10 FREE WATER 5 В 6 2 8 3.2 8 Gray and Brown 18 10.3 11 S-11 29 11

SOIL BORING LOG

Page $\underline{2}$ of $\underline{2}$

Date 10/29/10

| ROUTE | FAP 325 | DESCRIP | TIO1 | ١ | Cul | vert ca | arrying | IL 16 over Sangamon C | reek | LOGGE | ED BY | <u> </u> | 1. Tapı | oan | | |
|-------------|--|---------|-----------------|----------------------|------------------|-------------|------------------|---|----------------|--------------|------------------|------------------|--|--|--|--|
| SECTION _ | SECTION 18(B-2,B-3) LOCATION NE 1/4, SEC. 5, TWP. 10N, RNG. 1W, 3 PM | | | | | | | | | | | | | | | |
| COUNTY _ | Montgomery | DRIL | LING METHOD HSA | | | | | HSA | HAMMER TYPE _ | | | 140# Auto | | | | |
| Station | 0. 068-43+2 0. 2-N | 23.5 | | D E P T | B L O W | U C S | M O I S | Surface Water Elev Stream Bed Elev Groundwater Elev.: | 668.7 667.5 | _ ft _ ft | D E P T | B L O W | U C s | M O I S | | |
| Station | 43+ | 65 | | н | S | Qu | Т | | 662.3 | _ ft | Н | s | Qu | T | | |
| Offset | 23.01 | IKI | | (54) | /6" | (tof) | 10/ | ▼Upon Completion _ | 651.3 | | (ft) | /6" | (te4) | (9/.) | | |
| | rface Elev. | | ft | (ft) | 10 | (tsf) | (%) | ▼After Hrs | Cuttings | ft | (11) | /0 | (tsf) | (%) | | |
| (continued) | AY LOAM (Till |) | | | 9 26 | 12.0 | 12 | Boring Complete | | | | | | To the second se | | |
| | | | | -45 | 39 | S-13 | | | | | <u>-65</u> | | | | | |
| Olive Brown | Moist Clay Loa | am Till | | -450 -550 -555 | 10 25 38 | 1.9 S-12 | 12 | | | | | | THE CONTRACT OF THE CONTRACT O | | | |
| | | | - | | | | | | | | | | | | | |

ROCKFILL - FOUNDATION 6M10 6/15/17

This work consists of constructing a layer of rockfill below culverts or spread footings having unstable or unsuitable soil conditions. When shown on the plans, the rockfill limits and thickness shall be confirmed by the Engineer prior to excavating below the theoretical top of rockfill line.

Rockfill materials shall meet the requirements of Article 1005.01 of the Standard Specifications. The gradation of rockfill shall be primary crusher run. The maximum dimension shall be 8 inches. Rockfill may contain broken pavement or rock excavation as defined in Article 205.04 and with the approval of the Engineer.

Materials shall meet the requirements of the following Articles of the Standard Specifications:

Bedding or Capping Material 1003.04 or 1004.05

The method of rockfill placement shall be approved by the Engineer. Rockfill shall be capped according to application as shown below:

Spread Footing 4 to 6 inches CA-6

Cast-In-Place Box Culverts 4 to 6 inches CA-7 or CA-11

Pre-Cast Box Culverts Porous Granular Bedding Material (Article 540.02)

Pre-Cast Pipe Culverts Coarse or Fine Aggregate Bedding (Article 542.04)

Excavation shall be performed according to Section 202 of the Standard Specifications.

In spread footing applications, the CA-6 cap shall be compacted to the satisfaction of the Engineer. No compaction of rockfill is required for culvert applications.

This work will be measured and paid for at the contract unit price per ton for ROCKFILL - FOUNDATION. The contract price for ROCKFILL-FOUNDATION shall include excavation, aggregate materials, aggregate material placement, and placement of excavated materials within right-of-way or disposal off right-of-way. *Excavation will not be measured or paid for separately or as part of EARTH EXCAVATION.* For precast concrete box culverts, porous granular bedding material and the excavation volume required for bedding will be paid for according to Article 540.08. For pipe culverts, the aggregate bedding material and excavation volume required for the aggregate bedding material will be paid for according to Article 542.11.

GRANULAR CULVERT BACKFILL 6M6 10/15/13

This work consists of backfilling box culverts or three-sided structures with granular materials. This work shall be performed at locations shown on the plans or as directed by the Engineer.

Backfilling shall be performed according to Article 502.10. The backfill material shall meet the requirements of Article 1004.05, except the gradation shall be CA-06 or CA-10. This work satisfies select granular backfill (porous granular material) requirements of ASTM C 1577.

Granular Culvert Backfill will be measured for payment in cubic yards compacted in place. Additional material required to backfill excavation outside the limits shown on the plans will not be measured for payment. This work shall be paid for at the contract unit price per cubic yard for GRANULAR CULVERT BACKFILL.

Existing Structure Plans

