

### SIDEWALK REMOVAL

DESCRIPTION	FROM			TO			APPROX. LENGTH (METERS)	AVERAGE WIDTH (METERS)	SIDEWALK REMOVAL (SQ M) M4402050
	ALIGNMENT	STATION	OFFSET	ALIGNMENT	STATION	OFFSET			
IL 22 / OAK GROVE DRIVE	IL 22	101+259	RT	IL 22	101+311	RT	52	1.1	56
IL 22 / ACACIA TERRACE	IL 22	101+259	LT	IL 22	101+276	LT	17	2.5	42
IL 22 / BUFFALO GROVE RD	IL 22	101+466	RT	BUFFALO	10+163	LT	153	1.5	235
IL 22 / BUFFALO GROVE RD	IL 22	101+555	LT	BUFFALO	10+315	LT	142	2.3	328
BUFFALO GROVE RD/ IL 22	BUFFALO	10+262	RT	IL 22	101+642	LT	57	2.2	127
BUFFALO GROVE RD/ IL 22	BUFFALO	10+125	RT	IL 22	101+665	RT	86	2.6	220
BUFFALO GROVE RD	BUFFALO	10+285	RT	BUFFALO	10+290	RT	5	2.2	11
BUFFALO GROVE RD	BUFFALO	10+298	RT	BUFFALO	10+303	RT	5	2.2	11
IL 22 / ARBORETUM (NW)	IL 22	101+850	LT	IL 22	101+860	LT	10	2.4	24
IL 22 / ARBORETUM (SW)	IL 22	101+849	RT	IL 22	101+857	RT	8	2.9	23
IL 22 / ARBORETUM (NE)	IL 22	101+879	LT	IL 22	101+888	LT	9	1.4	13
IL 22 / ARBORETUM (SE)	IL 22	101+868	RT	IL 22	101+873	RT	5	2.4	12
IL 22 / WILLOW PKWY (NW)	IL 22	102+068	LT	IL 22	102+071	LT	3	1.0	3
IL 22 / WILLOW PKWY (SW)	IL 22	102+078	RT	IL 22	102+083	RT	5	4.4	22
IL 22 / WILLOW PKWY (NE)	IL 22	102+103	LT	IL 22	102+108	LT	5	1.0	5
IL 22 / WILLOW PKWY (SE)	IL 22	102+098	RT	IL 22	102+104	RT	6	3.7	22
IL 22 / FIRE STATION (NW)	IL 22	102+365	LT	IL 22	102+367	LT	2	2.0	4
IL 22 / FIRE STATION (NE)	IL 22	102+378	LT	IL 22	102+380	LT	2	1.5	3
IL 22 / EASTON AVE (NW)	IL 22	102+440	LT	IL 22	102+444	LT	4	1.5	6
IL 22 / PRAIRIE RD (NW)	PRAIRIE	10+008	LT	PRAIRIE	10+040	LT	32	1.8	59
IL 22 / PRAIRIE RD (SW)	IL 22	102+831	RT	PRAIRIE	9+966	LT	28	2.5	70
IL 22 / PRAIRIE RD (NE)	PRAIRIE	10+064	RT	IL 22	102+904	LT	90	1.7	149
ILLINOIS 22	IL 22	102+921	LT	IL 22	102+951	LT	30	1.6	47
ILLINOIS 22	IL 22	102+960	LT	IL 22	103+117	LT	157	1.7	271
ILLINOIS 22	IL 22	103+120	LT	IL 22	103+210	LT	90	1.5	132
ILLINOIS 22	IL 22	103+217	LT	IL 22	103+223	LT	6	1.5	9
ILLINOIS 22	IL 22	103+258	RT	IL 22	103+276	RT	18	2.3	42
IL 22 / APPLE HILL LANE (NW)	IL 22	103+342	LT	IL 22	103+347	LT	5	1.0	5
IL 22 / APPLE HILL LANE (SW)	IL 22	103+345	RT	IL 22	103+349	RT	4	2.0	8
IL 22 / APPLE HILL LANE (NE)	IL 22	103+362	LT	IL 22	103+364	LT	2	1.5	3
IL 22 / APPLE HILL LANE (SE)	IL 22	103+362	RT	IL 22	103+376	RT	14	3.0	42
ILLINOIS 22	IL 22	103+634	LT	IL 22	103+636	LT	2	1.5	3
IL 22 / STEVENSON DRIVE (NW)	IL 22	103+650	LT	IL 22	103+657	LT	7	4.3	30
IL 22 / PALLAZO DR (SW)	IL 22	103+633	RT	IL 22	103+641	RT	8	4.8	38
IL 22 / PALLAZO DR (SE)	IL 22	103+659	RT	IL 22	103+729	RT	70	2.6	179
ILLINOIS 22	IL 22	103+736	RT	IL 22	103+860	RT	124	2.6	328
ILLINOIS 22	IL 22	103+880	RT	IL 22	103+900	RT	20	2.2	43
IL 22 / SCHELTER ROAD (NW)	IL 22	104+153	LT	IL 22	104+160	LT	7	2.1	15
IL 22 / SCHELTER ROAD (NE)	IL 22	104+175	RT	IL 22	104+178	RT	3	2.3	7
TOTAL									2,647

### DRIVEWAY PAVEMENT REMOVAL

DESCRIPTION	ALIGNMENT	STATION	LT/RT	DRIVEWAY PAVEMENT REMOVAL (SQ M) M4402010
PRIVATE ENTRANCE	IL 22	100+512	RT	34
PRIVATE ENTRANCE	IL 22	100+612	RT	155
PRIVATE ENTRANCE	IL 22	100+816	RT	107
COMMERCIAL ENTRANCE	BUFFALO GRV	10+294	RT	60
COMMERCIAL ENTRANCE	IL 22	102+258	LT	66
FIRE STATION ENTRANCE	IL 22	102+373	LT	216
COMMERCIAL ENTRANCE	IL 22	102+594	LT	83
COMMERCIAL ENTRANCE	IL 22	102+680	LT	137
COMMERCIAL ENTRANCE	IL 22	102+731	LT	108
COMMERCIAL ENTRANCE	IL 22	102+801	LT	338
FIELD ENTRANCE	PRAIRIE RD	9+898	RT	47
PRIVATE ENTRANCE	PRAIRIE RD	9+963	RT	29
COMMERCIAL ENTRANCE	MAIN ST	10+109	LT	38
COMMERCIAL ENTRANCE	MAIN ST	10+112	RT	85
COMMERCIAL ENTRANCE	MAIN ST	10+131	LT	45
COMMERCIAL ENTRANCE	IL 22	103+091	RT	107
COMMERCIAL ENTRANCE	IL 22	103+106	LT	269
COMMERCIAL ENTRANCE	IL 22	103+186	RT	157
COMMERCIAL ENTRANCE	IL 22	103+250	RT	164
PRIVATE ENTRANCE	APPLE HILL	103+355	LT	22
COMMERCIAL ENTRANCE	IL 22	103+489	LT	144
COMMERCIAL ENTRANCE	IL 22	103+732	RT	136
COMMERCIAL ENTRANCE	IL 22	103+965	LT	46
COMMERCIAL ENTRANCE	SCHELTER RD	104+167	RT	48
COMMERCIAL ENTRANCE	SCHELTER RD	104+167	RT	100
COMMERCIAL ENTRANCE	SCHELTER RD	104+167	RT	42
COMMERCIAL ENTRANCE	HALF DAY RD	10+070	LT	119
COMMERCIAL ENTRANCE	HALF DAY RD	10+148	LT	79
PRIVATE ENTRANCE	HALF DAY RD	10+123	RT	76
COMMERCIAL ENTRANCE	HALF DAY RD	10+150	RT	115
TOTAL				3172

DATE	
BY	
FINAL SURVEYED	
SURVEY PLOTTED	
NOTE BOOK TEMPLATE	
AREAS CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEYED	
SURVEY PLOTTED	
NOTE BOOK TEMPLATE	
AREAS CHECKED	
NO.	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
IL RTE 22 (FAP 337)  
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

SCHEDULE OF QUANTITIES

SHEET 3 OF 14

SCALE: NONE      DRAWN BY: JSM  
DATE: 03-22-2004      CHECKED BY: JNR