F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-5	LAKE	562	31
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

D-91-552-99 60881

PROPOSED PAVEMENT

DESCRIPTION	FROM			TO			PCC PVT 250 JOINTED (SQ M) M4202255	AGG SUBGRADE 300 (SQ M) MZ001050	BC SC SUPER "C" N50 (M TON) MX406012	BC BC SUPER "D" N70 (M TON) MX406024	BC BC SUPER IL-19.0 N70 (SQ M) MX406216	BIT BC SUPER 250 (SQ M) MX355250	BC BC WIDE SUPER 250 (SQ M) M3560250	PAVEMENT FABRIC (SQ M) M4205100
	ALIGNMENT	STATION	OFFSET	ALIGNMENT	STATION	OFFSET								
WESTBOUND ILLINOIS 22 (MEDIAN)	IL 22	99+815	LT	IL 22	99+892	LT	213	241						
ILLINOIS 22 MEDIAN	IL 22	99+852	-	IL 22	99+973	-		275						
EASTBOUND ILLINOIS 22 (MEDIAN)	IL 22	99+815	RT	IL 22	99+976	RT	521	548						
ILLINOIS 83 (RADII RETURNS)	IL 22	99+968	RT	IL 83	9+942	LT	132	169						
ILLINOIS 83 (RADII RETURNS)	IL 83	10+054	RT	IL 22	100+031	LT	174	210						
EASTBOUND IL 22 W/IL 83 RADII RETURN	IL 83	9+966	RT	IL 22	100+159	RT	1077	1249						
WESTBOUND ILLINOIS 22	IL 22	100+025	LT	IL 22	100+159	LT	2209	2360						
ILLINOIS 22 MEDIAN	IL 22	100+028	-	IL 22	100+106	-		152						
WESTBOUND ILLINOIS 22	IL 22	100+159	LT	IL 22	100+397	LT	1941	2276						
EASTBOUND ILLINOIS 22	IL 22	100+159	RT	IL 22	100+397	RT	2078	2430						
ILLINOIS 22 MEDIAN	IL 22	100+314	-	IL 22	100+384	-		95						
TALL OAKS DRIVE	IL 22	100+379	LT	IL 22	100+415	LT	196	324	10		10			
WESTBOUND ILLINOIS 22	IL 22	100+397	LT	IL 22	100+734	LT	2481	2880						
EASTBOUND ILLINOIS 22	IL 22	100+397	RT	IL 22	100+734	RT	2822	3283						
ILLINOIS 22 MEDIAN	IL 22	100+648	-	IL 22	100+719	-		95						
HAMPTON DRIVE	IL 22	100+673	LT	IL 22	100+749	LT	215	701	26		27		64	
WESTBOUND ILLINOIS 22	IL 22	100+734	LT	IL 22	101+255	LT	3793	4486						
EASTBOUND ILLINOIS 22	IL 22	100+734	RT	IL 22	101+255	RT	4144	4880						
ILLINOIS 22 MEDIAN	IL 22	101+169	-	IL 22	101+240	-		95						
ACACIA TERRACE	IL 22	101+198	LT	IL 22	101+269	LT	277	536						
OAK GROVE DRIVE	IL 22	101+240	RT	IL 22	101+269	RT	133	412	24		24		53	
WESTBOUND ILLINOIS 22	IL 22	101+255	LT	IL 22	101+614	LT	3063	3418						
EASTBOUND ILLINOIS 22	IL 22	101+255	RT	IL 22	101+614	RT	4279	4664						
ILLINOIS 22 MEDIAN	IL 22	101+269	-	IL 22	101+340	-		95						
WESTBOUND ILLINOIS 22	IL 22	101+400	-	IL 22	101+585	-								1394
EASTBOUND ILLINOIS 22	IL 22	101+400	-	IL 22	101+585	-								2700
ILLINOIS 22 MEDIAN	IL 22	101+490	-	IL 22	101+593	-		219						
SB BUFFALO GROVE RD (NORTH OF IL 22)	BUFFALO	10+212	LT	BUFFALO	10+332	LT	1666	1791						
NB BUFFALO GROVE RD (NORTH OF IL 22)	BUFFALO	10+212	RT	BUFFALO	10+332	RT	1134	1232						
BUFFALO GROVE RD MEDIAN (NO OF IL 22	BUFFALO	10+014	-	BUFFALO	10+175	-		311						
SB BUFFALO GROVE RD (SOUTH OF IL 22)	BUFFALO	10+133	LT	BUFFALO	10+184	LT	529	574						
NB BUFFALO GROVE RD (SOUTH OF IL 22)	BUFFALO	10+014	RT	BUFFALO	10+184	RT	1894	2033						
BUFFALO GROVE RD MEDIAN (SO OF IL 22	BUFFALO	10+225	-	BUFFALO	10+332	-		144						
WESTBOUND ILLINOIS 22	IL 22	101+614	LT	IL 22	101+870	LT	3080	3338						
EASTBOUND ILLINOIS 22	IL 22	101+614	RT	IL 22	101+863	RT	2356	2549						
ILLINOIS 22 MEDIAN	IL 22	101+634	-	IL 22	101+751	-		238						
ARBORETUM WAY (NORTH OF IL 22)	IL 22	101+851	LT	IL 22	101+888	LT	202	232						
ARBORETUM WAY (SOUTH OF IL 22)	IL 22	101+843	RT	IL 22	101+885	RT	375	426						
WESTBOUND ILLINOIS 22	IL 22	101+870	LT	IL 22	102+088	LT	2088	2270						
EASTBOUND ILLINOIS 22	IL 22	101+863	RT	IL 22	102+088	RT	2198	2451						
WILLOW PARKWAY (NORTH OF IL 22)	IL 22	102+065	LT	IL 22	102+113	LT	406	463						
WILLOW PARKWAY (SOUTH OF IL 22)	IL 22	102+070	RT	IL 22	102+111	RT	309	346						
FIRE STATION (NORTH OF IL 22)	IL 22	102+360	LT	IL 22	102+385	LT	112	130						
WESTBOUND ILLINOIS 22	IL 22	102+088	LT	IL 22	102+448	LT	3049	3427						
EASTBOUND ILLINOIS 22	IL 22	102+088	RT	IL 22	102+448	RT	3022	3437						

FINAL SURVEY — SURVEYED ___ BY ___ DATE ___; PLOTTED ___; TEMPLATE ___; AREAS ___; AREAS CHECKED ___; NOTE BOOK NO. ___

ORIGINAL SURVEY — SURVEYED ___ BY ___ DATE ___; PLOTTED ___; TEMPLATE ___; AREAS ___; AREAS CHECKED ___; NOTE BOOK NO. ___

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL RTE 22 (FAP 337)
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

SCHEDULE OF QUANTITIES

SHEET 7 OF 14

SCALE: NONE DRAWN BY: JSM

DATE: 03-22-2004 CHECKED BY: JNR