F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-5	LAKE	562	33
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

D-91-552-99 60881

PROPOSED PAVEMENT, CONT'D.

DESCRIPTION	FROM			TO			PCC PVT 250 JOINTED (SQ M) M4202255	AGG SUBGRADE 300 (SQ M) MZ001050	BC SC SUPER "C" N50 (M TON) MX406012	BC BC SUPER "D" N70 (M TON) MX406024	BC BC SUPER IL-19.0 N70 (SQ M) MX406216	BIT BC SUPER 250 (SQ M) MX355250	BC BC WIDE SUPER 250 (SQ M) M3560250	PAVEMENT FABRIC (SQ M) M4205100	POLY BC SC SUPER "F" N90 (M TON)
	ALIGNMENT	STATION	OFFSET	ALIGNMENT	STATION	OFFSET									
ILLINOIS 22 MEDIAN	IL 22	104+390	-	IL 22	104+493	-		162							
OLD HALF DAY ROAD	HALFDAY	10+012	LT/RT	HALFDAY	10+237	LT/RT	2598	2700							
BARCLAY ROAD	IL 22	104+353	RT	IL 22	104+394	RT	436	486							
ILLINOIS 22 EB	IL 22	104+518	-	IL 22	104+600	-		305				591			88
ILLINOIS 22 (TO TIE INTO EXISTING) WB	IL 22	104+600	LT	IL 22	104+665	LT		155					126		78
IL 22 (TO TIE INTO EXISTING) EB	IL 22	104+600	RT	IL22	104+695	RT							171		102
BITUMINOUS SIDEPATH	IL 22	103+890	RT	IL 22	104+600	RT			314		643				
TOTAL															268

PROPOSED SIDEWALK

DESCRIPTION	FROM STATION	TO STATION	PC CONC SIDEWALK 125 (SQ M) M4240125
ILLINOIS 22 (LT)	100+740	100+805	187
ILLINOIS 22 (LT)	100+805	101+247	1191
IL 22/ ACACIA (NE)	101+261	101+276	38
ILLINOIS 22 (RT)	102+259	101+539	720
IL 22 / BUFFALO GROVE (SW)	101+466	10+163	312
IL 22 / BUFFALO GROVE (NW)	101+555	10+315	325
IL 22 / BUFFALO GROVE (NE)	10+262	101+642	136
BUFFALO GROVE DRIVEWAY (RT)	10+285	10+304	21
IL 22 / BUFFALO GROVE (SE)	10+125	101+665	208
IL 22 / ARBORETEUM (NW)	101+849	101+859	29
IL 22 / ARBORETEUM (NE)	101+880	101+888	22
IL 22 / ARBORETEUM (SW)	101+849	101+857	37
IL 22 / ARBORETEUM (SE)	101+874	101+878	20
IL 22 / WILLOW (NW)	102+068	102+075	16
IL 22 / WILLOW (NE)	102+102	102+108	15
IL 22 / WILLOW (SW)	102+078	102+082	27
IL 22 / WILLOW (SE)	102+098	102+104	29
IL 22 / FIRESTATION (LT)	102+365	102+380	6
IL 22 / EASTON (LT)	102+440	102+443	3
IL 22 / PRAIRIE (SW)	102+831	9+966	68
IL 22 / PRAIRIE (SE)	102+863	102+922	151
IL 22 / MAIN (NW)	102+828	102+838	21
IL 22 / MAIN (NE)	10+064	102+911	218
ILLINOIS 22 (RT)	102+932	103+085	369
ILLINOIS 22 (LT)	102+921	102+946	53
ILLINOIS 22 (LT)	102+966	102+997	47
ILLINOIS 22 (LT)	103+001	103+117	174
ILLINOIS 22 (RT)	103+096	103+118	250
ILLINOIS 22 (LT)	103+121	103+202	122
ILLINOIS 22 (RT)	103+222	103+245	67

PROPOSED SIDEWALK, CONT'D

DESCRIPTION	FROM STATION	TO STATION	PC CONC SIDEWALK 125 (SQ M) M4240125
IL 22 / PRAIRIE LN (NE)	103+221	103+223	3
ILLINOIS 22 (RT)	103+254	103+276	56
IL 22 / APPLE HILL (NW)	103+342	103+347	5
IL 22 / APPLE HILL (NE)	103+362	103+364	3
IL 22 / APPLE HILL (SW)	103+345	103+349	8
IL 22 / APPLE HILL (SE)	103+364	103+376	39
IL 22 / STEVENSON (NW)	103+634	103+657	63
IL 22 / PALLAZO (SW)	103+633	103+641	43
IL 22 / STEVENSON (NE)	103+672	103+677	6
ILLINOIS 22 (RT)	103+657	103+728	179
ILLINOIS 22 (RT)	103+736	103+857	309
IL 22 / HOTZ (NW)	103+868	103+872	7
IL 22 / HOTZ (NE)	103+885	103+889	9
IL 22 / SCHELTER (NW)	104+153	104+157	8
IL 22 / SCHELTER (SW)	104+134	103+138	6
IL 22 / SCHELTER (NE)	104+176	104+179	5
IL 22 / SCHELTER (SE)	104+167	104+171	8
IL 22 / OLD HALF DAY (NW)	10+015	10+076	182
IL 22 / OLD HALF DAY (SW)	104+355	104+364	14
IL 22 / OLD HALF DAY (SE)	104+385	104+393	15
TOTAL			5849

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK NO.		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL RTE 22 (FAP 337)
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

SCHEDULE OF QUANTITIES

SHEET 9 OF 14

SCALE: NONE DRAWN BY: JSM

DATE: 03-22-2004 CHECKED BY: JNR