

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 305	1518 PCC-PC-2	COOK	17	9

**WESTBOUND WILLOW ROAD.
W. OF PFINGSTEN RD. TO E. OF IL 43 (WAUKEGAN RD.)**

CONTRACT 62457

PATCH LOCATION NUMBER	STATION	LANE 1			TYPE	LANE 2		
		SIZE (W X L)	AREA (SQ. YD.)	TYPE		SIZE (W X L)	AREA (SQ. YD.)	TYPE
114	47+00	12 x 6	8.0	II	12 x 6	8.0	II	
115	48+10	12 x 6	8.0	II	12 x 6	8.0	II	
116	50+25	12 x 6	8.0	II	12 x 6	8.0	II	
117	53+35	12 x 6	8.0	II	12 x 6	8.0	II	
118	55+00	12 x 6	8.0	II	12 x 6	8.0	II	
119	57+80	12 x 6	8.0	II				
120	58+00	12 x 6	8.0	II				
121	58+50	12 x 6	8.0	II	12 x 6	8.0	II	
122	60+10	12 x 6	8.0	II	12 x 6	8.0	II	
123	61+60	12 x 10	14.0	II	12 x 10	14.0	II	
124	62+20	12 x 6	8.0	II	12 x 6	8.0	II	
125	62+75	12 x 6	8.0	II	12 x 6	8.0	II	
126	64+50	12 x 6	8.0	II	12 x 6	8.0	II	
127	67+60				12 x 6	8.0	II	
128	70+15	12 x 6	8.0	II				
129	70+80	12 x 6	8.0	II	12 x 6	8.0	II	
130	73+00	12 x 12	16.0	III	12 x 15	20.0	III	
131	78+55	12 x 6	8.0	II	12 x 6	8.0	II	
132	79+60				12 x 8	11.0	II	
133	80+25	12 x 10	14.0	II	12 x 10	14.0	II	
134	82+05	12 x 6	8.0	II	12 x 6	8.0	II	
135	82+95	12 x 6	8.0	II	12 x 6	8.0	II	
136	83+93	12 x 6	8.0	II	12 x 6	8.0	II	
137	84+65	12 x 6	8.0	II	12 x 6	8.0	II	
138	85+65				12 x 6	8.0	II	
139	87+40	12 x 6	8.0	II				

NOTE: PHINGSTEN RD. CENTERLINE = STA. 56+47

PATCH LOCATION NUMBER	STATION	LANE 1			TYPE	LANE 2		
		SIZE (W X L)	AREA (SQ. YD.)	TYPE		SIZE (W X L)	AREA (SQ. YD.)	TYPE
140	94+05	12 x 6	8.0	II	12 x 6	8.0	II	
141	95+25	12 x 12	16.0	III	12 x 12	16.0	III	
142	96+10	12 x 6	8.0	II	12 x 6	8.0	II	
143	98+53	12 x 6	8.0	II	12 x 6	8.0	II	
144	99+85	12 x 6	8.0	II	12 x 6	8.0	II	
145	100+70	12 x 6	8.0	II	12 x 6	8.0	II	
146	104+05	12 x 6	8.0	II	12 x 6	8.0	II	
147	105+10	12 x 6	8.0	II	12 x 6	8.0	II	
148	107+05	12 x 8	11.0	II	12 x 8	11.0	II	
149	108+30	12 x 10	14.0	II	12 x 10	14.0	II	
150	110+73	12 x 6	8.0	II	12 x 6	8.0	II	
151	111+85	12 x 6	8.0	II	12 x 6	8.0	II	
152	113+11	12 x 6	8.0	II	12 x 6	8.0	II	
153	113+78	12 x 6	8.0	II	12 x 6	8.0	II	
154	114+30	12 x 15	20.0	III				
155	114+40				12 x 22	30.0	IV	
156	140+10	12 x 6	8.0	II	12 x 6	8.0	II	
157	141+02	12 x 6	8.0	II	12 x 6	8.0	II	
158	141+80	12 x 6	8.0	II	12 x 6	8.0	II	
159	143+70	12 x 6	8.0	II	12 x 6	8.0	II	

**NOTE: BRIDGE OMISSION – SN: 016-0533 FROM + STA. 136+05 TO STA. 139+95
SHERMER RD. CENTERLINE = STA. 109+81
LEHIGH RD. CENTERLINE = STA. 137+30**

ILLINOIS DEPARTMENT OF TRANSPORTATION

WILLOW RD.
PAVEMENT PATCHING SCHEDULE