F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	19
STA. 1200+00.00		TO STA. 1365+00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-9

62695

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	H01 URBAN - 90% FEDERAL, 10% STATE							H05 100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
	X0325030	TRENCH AND BACKFILL FOR 2 OR 4 DUCTS	FOOT	448						448			
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	1304	1304								
*	K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	13	13								
	X0300057	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3	3								
*	X0301295	ELECTRICAL MANHOLE REMOVAL	EACH	8			4		4				
*	X0301898	ELECTRICAL MANHOLES 3' x 4' x 4' WITH 24" FRAME AND LID	EACH	8			2		6				
	X0320001	PVC CONDUIT IN TRENCH 2" (SCHEDULE #40)	FOOT	219			219 △1						
*	X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	610					610				
	X0320815	SLEEPER SLAB	SQ YD	206	206								
	X0321072	BRIDGE FENCE RAILING	FOOT	694								694	
*	X0321519	CONDUIT SUPPORT SYSTEM	L SUM	1					1				
*	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	144		144							
*	X0322425	CIRCUIT BREAKER, 1-POLE, 70 AMPERE, 480 VOLT IN EXISTING STREET LIGHT CONTROLLER	EACH	2					2				
	X0322679	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER	EACH	2					2				
*	X0322706	ELECTRIC CABLE IN CONDUIT NO. 12 10/C	FOOT	512					512				
*	X0322741	LIGHT POLE, STEEL, 34.5 FT. M.H., 12 FT. MAST ARM, 3 GAUGE 12 1/2" DIA., 16.5" BOLT CIRCLE, 1 1/2" ANCHOR RODS	EACH	1					1				
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	20	20								
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	30		30							
	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18			18						
	X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	760			760						
	X0323830	DRAINAGE SCUPPERS DS-11	EACH	10								10	
*	X0323907	COMMUNICATIONS VAULT, TYPE C1	EACH	6				6					
	X0324112	BARRIER BASE	FOOT	1039	939	100							
*	X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	795			795						
*	X0324210	CONDUIT ENCASED, REINFORCED CONCRETE, 4-4" DIA. CNC, 2 WIDE X 2 HIGH	FOOT	160			160 △1						
*	X0324212	CONDUIT ENCASED, REINFORCED CONCRETE, 6-4" DIA. CNC 2 WIDE X 3 HIGH	FOOT	40			40						
*	X0325052	CONDUIT ENCASED, REINFORCED CONCRETE, 5-4" DIA. CNC AND 1-2" DIA. CNC, 2 WIDE X 3 HIGH	FOOT	34			34						
△1 *	X0325053	CONDUIT ENCASED, REINFORCED CONCRETE, 6-4" DIA. CNC AND 2-2" DIA. CNC, 2 WIDE X 4 HIGH	FOOT	35			35						
*	X0325054	CONDUIT ENCASED, REINFORCED CONCRETE, 5-4" DIA. CNC AND 3-2" DIA. CNC, 2 WIDE X 4 HIGH	FOOT	431			431						
	X0324225	CONTROLLER, TRAFFIC, 16 LOAD BAY, P CABINET	EACH	2					2				
*	X0324414	CONDUIT ENCASED, REINFORCED CONCRETE, 1-3" DIA. CNC	FOOT	48			48						
	X0324420	PVC CONDUIT IN TRENCH 4" (SCHEDULE #40)	FOOT	68					68				

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

△1 Rev. 6-1-05

TY·LIN INTERNATIONAL

REVISIONS NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 10 OF 13

SCALE: NONE DRAWN BY: JPA

DATE: MARCH 25, 2005 CHECKED BY: MPG