CONTRACT NO. 62695
F.A.I. ROUTE 94 (DAN RYAN EXPRESSWAY)
71ST STREET TO I-57 (SB RAMPS, C-D'S, AND RETAINING WALLS)
COOK COUNTY

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	10
STA. 1200+00.00	TO STA. 1365+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-9

62695

H01 — H05

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE								100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	3369	3357	12							
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	915	881	34							
	20101000	TEMPORARY FENCE	FOOT	11361	11361								
	20200100	EARTH EXCAVATION	CU YD	83380	83380								
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12238	12238								
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	3479							651	2828	
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	809	809								
	20800150	TRENCH BACKFILL	CU YD	15209	15150	59							
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	25432	25432								
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	69172	68557	615							
	21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	16364	16364								
	21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	16364	16364								
*	25000210	SEEDING, CLASS 2A	ACRE	17.25	17.00	0.25							
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1541	1530	11							
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1541	1530	11							
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1541	1530	11							
* ⊙	25000750	MOWING	ACRE	27.25	27.25								
*	25100630	EROSION CONTROL BLANKET	SQ YD	82729	82169	560							
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	870	870								
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3380	3380								
	28000300	TEMPORARY DITCH CHECKS	EACH	37	37								
*	28000400	PERIMETER EROSION BARRIER	FOOT	19148	19148								
*	28000510	INLET FILTERS	EACH	159	61	98							
	28001000	AGGREGATE (EROSION CONTROL)	TONS	12	12								
	31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	12210		12210							
	31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2319	2319								
	31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	23113	23113								
	31200100	STABILIZED SUB-BASE 4"	SQ YD	21434	21434								
	35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	4681		4681							
	35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	5913		5913							
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30.5		30.5							
	40600300	AGGREGATE (PRIME COAT)	TON	65		65							

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESWAY)

SUMMARY OF QUANTITIES
SHEET 1 OF 13

SCALE: NONE — DRAWN BY: JPA

DATE: MARCH 25, 2005 — CHECKED BY: MPG

P:\0237\5\cook\cir\Dsgn\ts\ts013c.dgn

05/09/2005 04:39:56 PM