F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	•	COOK	907	17

STA. 1200+00.00 TO STA. 1365+00

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

• (1516.1, 1717 & 1818) R-9

62695

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	H01						H05		
					URBAN - 90% FEDERAL, 10% STATE								100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	20	20								
*	78201000	TERMINAL MARKERS, DIRECT APPLIED	EACH	5	5								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	12061	8603	3458							
*	80700140	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	68			68						
*	80800525	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	6			6						
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2542			2542						
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	227			227						
*	81023750	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	343				343					
*	81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	15			15						
*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	525			525						
*	81301010	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 10" X 8" X 4"	EACH	2				2					
*	81400200	HEAVY-DUTY HANDHOLE	EACH	24				24					
*	81400205	HEAVY-DUTY HANDHOLE, SPECIAL	EACH	2				2					
*	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4192			4192						
*	81800700	AERIAL CABLE, 3-1/C NO. 2 AWG, ALUMINUM, WITH MESSENGER WIRE	FOOT	890			890						
*	82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	6			6						
*	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	60			60						
*	83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	180	90		90						
*	84200700	LIGHTING FOUNDATION REMOVAL	EACH	9					9				
*	84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	36			36						
*	87301155	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 7C	FOOT	662					662				
*	87301185	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 19C	FOOT	792					792				
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	426					426				
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12				12					
*	87900200	DRILL EXISTING HANDHOLE	EACH	1				1					
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					2				
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2261			795		1466				
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2					2				
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	19				17	2				
*	X0325015	ADJUST FRAME AND LID	EACH	6					6				
	X0320868	BRACED EXCAVATION SPECIAL	CU YD	216								216	
	X0324872	CAST IN PLACE TACTILE / DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	156		156							

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 8 OF 13

SCALE: NONE | DRAWN BY: JPA

DATE: MARCH 25, 2005 | CHECKED BY: MPG

P:\02375\road\cf7\dsg\7dsn08.3d.dgn

05/06/2005 04:40:01 PM