

SUMMARY OF QUANTITIES

H01

H05

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94		COOK	907	18
STA. 1200+00.00		TO STA. 1365+00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(1516.1, 1717 & 1818) R-9		62695		

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE							100% CITY	
				DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-IE	L.T.S. Y032-IF	SIGNALS Y031-IF	SIGNING Y002-1C	RETAINING WALLS Y007		76TH ST. BRIDGE X771-2A
X6643300	CHAIN LINK FENCE REMOVAL (CTA)	FOOT	270	270								
X6643310	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED (CTA)	FOOT	100	100								
44201351	CLASS C PATCHES, TYPE I, 10.5 INCH	SQ YD	150		150							
44201355	CLASS C PATCHES, TYPE II, 10.5 INCH	SQ YD	290		290							
44201360	CLASS C PATCHES, TYPE IV, 10.5 INCH	SQ YD	412		297						115	
⊙ X0325016	CLEAN EXISTING MANHOLE AND HANDHOLE	EACH	4					4				
60608530	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.48	FOOT	155.5	155.5								
X6060015	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	207.0	20.0	187.0							
X0325017	COMBINED SEWER, TYPE 2, 8"	FOOT	56		56							
60619390	CONCRETE MEDIAN SURFACE (CORRUGATED)	SQ FT	444		444							
81200100	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	15			15						
* X0325018	CONDUIT ENCASED, REINFORCED CONCRETE, 3-2" DIA., CNC, 2 WIDE X 2 HIGH	FOOT	20			20						
* X0325019	CONDUIT ENCASED, REINFORCED CONCRETE, 4-4" DIA. CNC AND 2-2" DIA. RGC, 2 WIDE X 3 HIGH	FOOT	394			394						
* X0325020	CONDUIT ENCASED, REINFORCED CONCRETE, 6-4" DIA. CNC AND 2-3" DIA. RGC, 2 WIDE X 4 HIGH	FOOT	31			31						
* 81012805	CONDUIT IN TRENCH, 3" DIA., PVC, ENCASED IN CONCRETE	FOOT	1016					1016				
* X8170400	ELECTRIC CABLE IN CONDUIT, 600V, (EPR/HYP), 1C NO. 6	FOOT	2240			2240						
* X8170405	ELECTRIC CABLE IN CONDUIT, 600V, (EPR/HYP), 1C NO. 8	FOOT	1120			1120						
* X0325021	INTERCONNECT, 7 WIRE LOCAL	EACH	1					1				
* X0325022	INTERCONNECT, 7 WIRE MASTER	EACH	1					1				
* X0325023	LIGHT POLE, STEEL, 32.5 FT. M.H., 12 FT. MAST ARM, 7 GAUGE 8 1/2" DIA., 11 1/2" BOLT CIRCLE, 1" ANCHOR RODS, INSTALL ONLY	EACH	6			6						
* X0325024	LIGHT POLE, STEEL, 34.5 FT. M.H., 12 FT. MAST ARM, 3 GAUGE 10" DIA., 15" BOLT CIRCLE, 1 1/4" ANCHOR RODS	EACH	3					3				
* X0325025	LIGHT POLE, STEEL, 34.5 FT. M.H., 12 FT. MAST ARM, 3 GAUGE 11" DIA., 17 1/4" BOLT CIRCLE, 1 1/4" ANCHOR RODS	EACH	2					2				
* X0325026	LIGHT POLE, STEEL, 34.5 FT. M.H., 12 FT. MAST ARM, 7 GAUGE 10" DIA., 15" BOLT CIRCLE, 1 1/4" ANCHOR RODS	EACH	3					3				
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7		7							
X6022120	MANHOLES, DROP TYPE, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1								
X0325027	MEDIAN AND PAVEMENT REMOVAL (SPECIAL)	SY YD	560		560							
* X0322122	METALLIZING STRUCTURAL STEEL	L SUM	1							1		
44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	250	250								
* X0325028	POLE, CITY STEEL, ANCHOR BASE, 32'-6", 7 GAUGE, WITH 11-1/2" BOLT CIRCLE, INSTALL ONLY	EACH	6			6						
* X0325029	PVC CONDUIT IN DUCT, 2 - 3 INCH	FOOT	194					194				
* X0324697	SOIL STABILIZERS	POUND	528845	528845								

⊙ - NON-PARTICIPATING
 * - SPECIALTY ITEM
 □ - IDOT PAY CODE SFTY-3N
 Δ - IDOT PAY CODE Y080

TYLINT INTERNATIONAL

REVISIONS	
NAME	DATE
REVISOR	05/06/05
REVISOR	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)
 SUMMARY OF QUANTITIES
 SHEET 9 OF 13
 SCALE: NONE
 DATE: MARCH 25, 2005
 DRAWN BY: JPA
 CHECKED BY: MPG

04/09/2005 04:02 PM