

SUMMARY OF QUANTITIES

← H01 → H05 →

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE								100% CITY
				DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	
* X0324433	LIGHT TOWER SERVICE PAD, 6"	SQ FT	411			411						
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	152							152		
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	185131							185131		
* X0324478	PVC CONDUIT IN TRENCH 3" (SCHEDULE #40)	FOOT	150					150				
* X0324486	CONCRETE FOUNDATION, 30" DIAMETER, 1.25" ANCHOR RODS, 15" BOLT CIRCLE, 9' DEEP	FOOT	54					54				
* X0324487	CONCRETE FOUNDATION, 30" DIAMETER, 1.50" ANCHOR RODS, 16.5" BOLT CIRCLE	FOOT	11					11				
X0324491	CONCRETE MEDIAN WALL, 18 INCH WIDE	FOOT	435		435							
X0324493	CONCRETE MEDIAN SURFACE (SPECIAL)	SQ FT	527		527							
* X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1			1						
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	196	196								
X0324706	CONCRETE FOUNDATION, 30" DIAMETER, 1.25" ANCHOR RODS, 17.25" BOLT CIRCLE, 9' DEEP	FOOT	18					18				
X0324864	DRAIN CONNECTIONS	FOOT	212		212							
* X0329888	REMOVE EXISTING STREET LIGHTING EQUIPMENT	L SUM	1			1						
X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	74		74							
X0712400	TEMPORARY PAVEMENT	SQ YD	11045	11045								
* X0933900	PVC CONDUIT IN TRENCH 3" (SCHEDULE #80)	FOOT	295			295						
* X0934000	PVC CONDUIT IN TRENCH 4" (SCHEDULE #80)	FOOT	405			405						
* X0934800	MAST ARM, STEEL, MONOTUBE 20 FT.	EACH	1					1				
* X0934900	MAST ARM, STEEL, MONOTUBE 26 FT.	EACH	2					2				
* X0935000	MAST ARM, STEEL, MONOTUBE 30 FT.	EACH	2					2				
* X0935100	MAST ARM, STEEL, MONOTUBE 35 FT.	EACH	1					1				
* X0966500	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, MAST ARM MOUNTED	EACH	3					3				
* X0966600	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, BRACKET MOUNTED	EACH	5					5				
* X0966700	JUNCTION BOX, POLE OR POST MOUNTED	EACH	9					9				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5		5							
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5		5							
X4023000	TEMPORARY ACCESS (ROAD)	EACH	5		5							
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1721		1721							
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	710		710							
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50, 1 1/2"	TON	533		533							
X6022130	MANHOLES, DROP TYPE, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1								
X6061001	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48	FOOT	6448.5	5106.5	1342.0							

- \* - SPECIALTY ITEM
- - IDOT PAY CODE SFTY-3N
- △ - IDOT PAY CODE Y080

**TYLIN** INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**F.A.I. 94 (DAN RYAN EXPRESSWAY)**

**SUMMARY OF QUANTITIES  
 SHEET 11 OF 13**

SCALE: NONE      DRAWN BY: JPA  
 DATE: MARCH 25, 2005      CHECKED BY: MPG

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94		COOK	907	20
STA. 1200+00.00		TO STA. 1365+00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (1516.1, 1717 & 1818) R-9				<b>62695</b>

05/09/2005 09:49:03 PM