

EARTHWORK SCHEDULE

RAMP/WALL	FROM		TO		EARTH EXCAVATION (CU YD)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)
	ALIGNMENT	STATION	ALIGNMENT	STATION			
HALSTED EXIT	SB I-57	97+00	SB I-57	106+50	2190	530	375
WALL 67	SB I-57	107+50	SB I-57	116+00	1400	395	130
WENTWORTH EXIT	SB I-57	132+00	SB I-57	156+00	3230	1075	1305
95TH EXIT	SB I-94	1210+13	SB I-94	1236+00	19615	2447	345
87TH ENTRANCE	SB I-94	1241+00	SB I-94	1258+00	9940	1164	230
87TH EXIT	SB I-94	1260+50	SB I-94	1283+50	7895	1165	90
76TH -79TH C-D	SB I-94	1312+50	SB I-94	1339+00	21525	2405	1320
71ST-75TH C-D	SB I-94	1342+15	SB I-94	1363+50	17585	3055	255
TOTAL					83380	12236	4050

FOR TOPSOIL QUANTITIES, SEE LANDSCAPING PLANS

POROUS GRANULAR EMBANKMENT, SUBGRADE

ALIGNMENT	DESCRIPTION	STATION		LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	VOLUME (CU YD)
		FROM	TO				
95TH EXIT	PIPES #1017, 1022	-	-	475	5	12	88.0
95TH EXIT	PIPES #1118	-	-	156	5	12	28.9
87TH ENT	87TH STREET ENTRANCE RAMP	7197+24.0	7201+47.0	AREA=1212 SQ YD ; DEPTH=18"			605.8
87TH ENT	PIPES #167,1615,166,1610	-	-	233	5	12	43.1
	STRUCTURES #167, 166, 1610	-	-	-	4 DIA. (EA.)	24	12.0
87TH ENT	PIPES #168, 1611	-	-	146	5	12	27.0
	STRUCTURE #1611	-	-	-	4 DIA. (EA.)	24	4.0
TOTAL (CU YD)							809



NOTES:
"ALIGNMENT" REFERS TO PROPOSED ALIGNMENTS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

**SCHEDULE OF QUANTITIES
EARTHWORK QUANTITIES - SHEET 1**

SCALE: NONE DRAWN BY: JPA
DATE: MARCH 25, 2005 CHECKED BY: MPG