F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	44
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-9

62695

PCC SIDEWALK 5 INCH

LOCATION	ALIGNMENT	FROM		TO		PC CONC SIDEWALK 5 (SQ FT)	PROTECTIVE COAT (SQ YD)
		STATION	OFFSET	STATION	OFFSET		
76th STREET	76TH ST.	70+00.0	LT	70+91.5	LT	644	143
76th STREET	76TH ST.	70+50	RT	70+95	RT	270	60
76th STREET	76TH ST.	71+72.9	LT	71+80.6	LT	56	12
76th STREET	76TH ST.	71+70.9	RT	71+77.2	RT	44	10
76th STREET	76TH ST.	75+17.1	LT	75+30.6	LT	93	21
76th STREET	76TH ST.	75+13.7	RT	75+23.2	RT	67	15
					TOTAL	1174	261

PCC SIDEWALK 8 INCH

LOCATION	ALIGNMENT	FROM		TO		PC CONC SIDEWALK 8 (SQ FT)	PROTECTIVE COAT (SQ YD)
		STATION	OFFSET	STATION	OFFSET		
76th STREET	76TH ST.	70+92	LT	71+14.3	LT	129	29
76th STREET	76TH ST.	70+94.7	RT	71+09.4	RT	109	24
76th STREET	76TH ST.	71+59.8	LT	71+72.9	LT	68	15
76th STREET	76TH ST.	71+54.5	RT	71+70.9	RT	90	20
76th STREET	76TH ST.	75+30.6	LT	75+42.7	LT	61	14
76th STREET	76TH ST.	75+23.2	RT	75+37.3	RT	75	17
76th STREET	76TH ST.	76+08	RT	76+23.1	RT	117	26
					TOTAL	649	144

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12

LOCATION	ALIGNMENT	FROM		TO		COMB CC&G TBV.12 (FOOT)	SUB GRAN MAT B 6 (SQ YD)	PROTECTIVE COAT (SQ YD)
		STATION	OFFSET	STATION	OFFSET			
76th STREET	76TH ST.	69+70	30.6 LT	70+91	38.9 LT	122	34	25
LAFAYETTE AVE.	LAFAYETTE	104+50	18.2 LT	104+90	18.0 LT	40	11	7
76th STREET	76TH ST.	69+70	24.0 RT	70+93	23.5 RT	125	35	25
LAFAYETTE AVE.	LAFAYETTE	101+70	18.5 LT	102+25	18.2 LT	55	15	11
STATE ST.	STATE	136+56	31.5 RT	137+19.4	61.9 RT	85	24	17
STATE ST.	STATE	137+79.8	61.5 RT	138+10	31.4 RT	54	15	11
					TOTAL	481	134	96

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24

LOCATION	ALIGNMENT	FROM		TO		COMB CC&G TB6.24 (FOOT)	SUB GRAN MAT B 6 (SQ YD)	PROTECTIVE COAT (SQ YD)
		STATION	OFFSET	STATION	OFFSET			
LAFAYETTE AVE.	LAFAYETTE	101+70	29.2 RT	102+40	19.5 RT	70	27	42
					TOTAL	70	27	42

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

LOCATION	ALIGNMENT	FROM		TO		COMB CC&G TB6.12 (FOOT)	SUB GRAN MAT B 6 (SQ YD)	PROTECTIVE COAT (SQ YD)
		STATION	OFFSET	STATION	OFFSET			
LAFAYETTE AVE	LAFAYETTE	102+25	18.2 LT	103+04	43.0 LT	94	26	42
LAFAYETTE AVE.	LAFAYETTE	103+67	43.3 LT	104+50	18.2 LT	97	27	43
LAFAYETTE AVE.	LAFAYETTE	102+40	18.0 RT	103+05.8	27.8 RT	70	19	31
LAFAYETTE AVE.	LAFAYETTE	103+72.4	25.8 RT	104+90	18.0 RT	121	34	54
STATE ST.	STATE	136+56	32.1 LT	137+12.4	41.0 LT	60	17	27
STATE ST.	STATE	137+81.1	36.8 LT	138+10	31.5 LT	31	9	14
					TOTAL	473	132	211

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12

LOCATION	ALIGNMENT	FROM		TO		COMB CC&G TB9.12 (FOOT)	SUB GRAN MAT B 6 (SQ YD)	PROTECTIVE COAT (SQ YD)
		STATION	OFFSET	STATION	OFFSET			
76TH STREET	76TH ST.	71+64	42.1 LT	71+74.6	40.3 LT	11	3	6
76TH STREET	76TH ST.	71+61.8	24.8 RT	71+71.3	24.1 RT	10	3	5
76TH STREET	76TH ST.	75+23	40.0 LT	75+40	42.7 LT	17	5	9
76TH STREET	76TH ST.	75+19.8	24.1 RT	75+32	25.7 RT	13	4	6
					TOTAL	51	15	25

PAVEMENT WIDENING

LOCATION	FROM		TO		BC SC SUPER "D" N70 (TON)	SUB GRAN MAT B 6 (SQ YD)	PCC BSE CSE 10 1/2 (SQ YD)
	ALIGN	STATION	ALIGN	STATION			
LAFAYETTE AVE.	LAFAYETTE	101+70	LAFAYETTE	102+90	3.3	38	38
				TOTAL	3.3	38	38

BRIDGE APPROACH PAVEMENT

LOCATION	FROM		TO		BR APPR PVT CON (PCC) (SQ YD)	BR APPR PAVT (SPL) (SQ YD)	PROTECTIVE COAT (SQ YD)
	ALIGN	STATION	ALIGN	STATION			
76TH STREET	76TH ST.	71+72.5	76TH ST.	71+78.5	44	-	88
76TH STREET	76TH ST.	71+78.5	76TH ST.	72+08.5	-	270	540
76TH STREET	76TH ST.	74+85	76TH ST.	75+15	-	270	540
76TH STREET	76TH ST.	75+15	76TH ST.	75+21	44	-	88
				TOTAL	88	540	1256

KNIGHT
Engineers & Architects

REVISIONS	
NAME	DATE
REVISED	05/06/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SCHEDULE OF QUANTITIES
76TH STREET BRIDGE - SHEET 2

SCALE: NONE DRAWN BY: RTM
DATE: MARCH 25, 2005 CHECKED BY: JPA

FILE: L:\6592.02\Cad\Sheets\Revised ITb\ 05-06-05\6592.02sch02 Rev050605.dgn