



- NOTES:**
- The geocomposite wall drain shall be constructed according to section 591 of the standard specifications.
 - The Contractor is responsible for the design and performance of the lagging using no less than 3" nominal rough-sawn thickness and the minimum tabulated unit stress in bending (f_b), used in the design of timber lagging shall be 1000 psi.
 - Stud shear connectors shall be 3/4" x 6" granular or solid flux filled headed studs, automatically end welded to the front flange of the soldier piles.

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Structure Excavation	CU YD	712
Stud Shear Connectors	EACH	1,042
Untreated Timber Lagging	SQ FT	4,757
Geocomposite Wall Drain	SQ YD	567
Pipe Underdrains for Structures, 6"	FOOT	690

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)
 RETAINING WALL ALONG LAFAYETTE AVE.
 77TH PL. TO 78TH ST.
 WALL 73A
 WALL CROSS SECTIONS & DETAILS (2 OF 2)
 S.N. 016-W972
 SCALE: N.T.S.
 DATE: MARCH 25, 2005

DESIGNED BY: MI, DJR
 DRAWN BY: DJR, MAF
 CHECKED BY: TD, MI

TYLIN INTERNATIONAL