

FAP. NTL.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	6717RS-2 & I	MARSHALL	74	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
D-93-065-03				

SUMMARY OF QUANTITIES				CONSTR. TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000- ROADWAY 20% STATE 80% FED	Y007 100% CITY	Y025 100% CITY
* 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	652	652		
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	549	549		
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	68	68		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	566	566		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25281	25281		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1860	1860		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	549	549		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	68	68		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	203	203		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	153	153		
K1005863	TREE ROOT PRUNING	EACH	12	12		
X0301828	ENGINEERED BARRIER	SQ YD	728	728		
* X0321907	STORM SEWERS, TYPE 2, WATERMAIN QUALITY PIPE, 12"	FOOT	137	137		
* X0321909	STORM SEWERS, TYPE 2, WATERMAIN QUALITY PIPE, 24"	FOOT	392	392		
X0324160	CATCH BASIN WITH HALF TRAP, 4' DIAMETER (INCLUDING FRAME AND LID)	EACH	1	1		
X0914300	PRECAST CONCRETE BOX CULVERT END SECTION 4'X2'	EACH	2	2		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	3322	3133		189
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	19	19		
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	1195	1195		
XX001391	REMOVAL AND REPLACEMENT OF BITUMINOUS DRIVEWAY	SQ YD	469	469		
XX001018	REMOVAL AND REPLACEMENT OF CONCRETE DRIVEWAY	SQ YD	46	46		
XX004827	REMOVE EXISTING PIPE CULVERTS, SPECIAL	FOOT	46	46		
* XX005432	STORM SEWERS, TYPE 2, WATERMAIN QUALITY PIPE, 18"	FOOT	34	34		
XX146400	STORM SEWER REMOVAL	FOOT	472	472		
* X0321912	STORM SEWERS, TYPE 2, WATERMAIN QUALITY PIPE, 30"	FOOT	872	872		
* X0321919	STORM SEWERS, TYPE 2, WATERMAIN QUALITY PIPE, 42"	FOOT	408	375.8	32.2	

* INDICATES SPECIALTY ITEM

SUMMARY