

# SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-TR-1, 82-7B-1, 2	ST. CLAIR	89	4
STA. TO STA.				
CONTRACT NO.: 76813				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90/FED/10/STATE					
				I-64 MAINLINE I000	GREENMOUNT RD SN 082-0344 SFTY-2A	S. LINCOLN AVE (FAS 843) SN 082-0181 X771-2A	N. MAIN STREET (FAS 844) SN 082-0182 X771-2A	IL RTE 158 (SB) (FAP 674) SN 082-0183 SFTY-2A	IL RTE 158 (NB) (FAP 674) SN 082-0184 SFTY-2A
50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")	SQ FT	20			5	5	10	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3120			1560	1560		
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	36			18	18		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	11910			3190	3320	2700	2700
58700200	BRIDGE SEAT SEALER	SQ FT	441			193	248		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	150	150					
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	70,588	70,588					
60107600	PIPE UNDERDRAINS 4"	FOOT	75388	75388					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	3000	3000					
60260100	INLETS TO BE ADJUSTED	EACH	2	2					
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1875	187.5		462.5	575	325	325
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2					
*63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	12			4	4	2	2
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	10			4	4	1	1
*63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	7	5				1	1
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	2750	425		725	900	350	350
63500105	DELINEATORS	EACH	313	313					
63500120	DELINEATOR REMOVAL	EACH	313	313					
64200105	SHOULDER RUMBLE STRIP	FOOT	80688	80688					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	0.5	0.1	0.1	0.1	0.1	0.1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	2			1	1		
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1					0.5	0.5
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1					0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	14				1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1			0.5	0.5		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1					
70102670	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601, SPECIAL	L SUM	1		1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10			5	5		

QUANTITY  
DATE-TIME  
QUANTITY  
DATE-TIME  
QUANTITY  
DATE-TIME

\*SPECIALTY ITEMS

Rev.

PLOT DATE: DATE-TIME