

SUMMARY OF QUANTITIES

Item No.	Description	Unit	As Bid		
			State/Local	Local Only	Total
AR110504	4-Way Concrete Encased Duct	Linear Foot	124.00	0.00	124.00
AR125941	Adjust Stake Mounted Light	Each	4.00	0.00	4.00
AR125961	Relocate Stake Mounted Light	Each	1.00	0.00	1.00
AR151450	Clearing and Grubbing	Acre	0.12	0.00	0.12
AR152410	Unclassified Excavation	Cubic Yard	4,465.00	0.00	4,465.00
AR156510	Silt Fence	Linear Foot	800.00	0.00	800.00
AR156513	Separation Fabric	Square Yard	6,480.00	568.00	7,048.00
AR162506	Class E Fence 6'	Linear Foot	358.00	0.00	358.00
AR162605	Class E Gate-5'	Each	1.00	0.00	1.00
AR162728	Electric Gate-28'	Each	1.00	0.00	1.00
AR201610	Bituminous Base Course	Ton	793.00	70.00	863.00
AR201630	Bituminous Base Test Section	Each	1.00	0.00	1.00
AR209610	Crushed Agg. Base Course - 10"	Square Yard	6,480.00	568.00	7,048.00
AR401610	Bituminous Surface Course	Ton	803.00	70.00	873.00
AR401630	Bituminous Surface Test Section	Each	1.00	0.00	1.00
AR401650	Bituminous Pavement Milling	Square Yard	169.00	0.00	169.00
AR401660	Saw & Seal Bit. Joints	Linear Foot	754.00	0.00	754.00
AR401665	Bituminous Pavement Sawing	Linear Foot	754.00	0.00	754.00
AR401916	Rem & Rep Bit Pavement - Type B	Square Yard	346.00	0.00	346.00
AR501665	PCC Pavement Sawing	Linear Foot	79.00	0.00	79.00
AR501910	Remove & Replace PCC Pavement	Square Yard	65.00	0.00	65.00
AR602510	Bituminous Prime Coat	Gallon	1,970.00	171.00	2,141.00
AR603510	Bituminous Tack Coat	Gallon	998.00	86.00	1,084.00
AR620530	Pavement Marking-Epoxy	Square Foot	1,465.00	0.00	1,465.00
AR701008	8" PVC Storm Sewer	Linear Foot	139.00	0.00	139.00
AR701512	12" RCP, Class IV	Linear Foot	237.00	0.00	237.00
AR701515	15" RCP, Class IV	Linear Foot	237.00	0.00	237.00
AR701518	18" RCP, Class IV	Linear Foot	145.00	0.00	145.00
AR701524	24" RCP, Class IV	Linear Foot	950.00	0.00	950.00
AR701900	Remove Pipe	Linear Foot	41.00	0.00	41.00
AR705412	Porous Backfill No. 2	Cubic Yard	157.00	0.00	157.00
AR705504	4" Perforated Underdrain	Linear Foot	1,514.00	0.00	1,514.00
AR705544	4" Non Perforated Underdrain	Linear Foot	60.00	0.00	60.00
AR705630	Underdrain Inspection Hole	Each	4.00	0.00	4.00
AR705640	Underdrain Cleanout	Each	8.00	0.00	8.00
AR751410	Inlet	Each	1.00	0.00	1.00
AR751540	Manhole 4'	Each	6.00	0.00	6.00
AR751550	Manhole 5'	Each	6.00	0.00	6.00
AR751943	Adjust Manhole	Each	1.00	0.00	1.00
AR800330	Traffic Control	Lump Sum	1.00	0.00	1.00
AR800915	Airfield Cable in Unit Duct	Linear Foot	324.00	0.00	324.00
AR800927	Granular Drainage Subbase - 4"	Square Yard	6,480.00	568.00	7,048.00
AR800937	Conservation Cover	Acre	1.60	0.00	1.60
AR901510	Seeding	Acre	1.10	0.00	1.10
AR905510	Topsoiling (From On Site)	Cubic Yard	365.00	0.00	365.00
AR905520	Topsoiling (From Off Site)	Cubic Yard	227.00	0.00	227.00
AR908510	Mulching	Acre	1.10	0.00	1.10
AR910230	Handicapped Sign	Each	1.00	0.00	1.00



HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200
Oak Brook, Illinois 60523
Telephone: 630.990.3800
Fax: 630.990.3801



Waukegan Regional Airport
Waukegan Regional Port District

3580 North McAree Road
Waukegan, Illinois 60087
Phone: 847.244.0055
Fax: 847.244.3813

REPAIR SELECTED PAVEMENT AREAS, REHABILITATE HANGAR TAXILANES AND SERVICE ROAD, AND CONSTRUCT NEW HANGAR PAVEMENTS

A.I.P. PROJ.: 3-17-0105-B30
IL. PROJ.: UGN-3449

No.	Drawing Issue Description	Date	By

Date
MAY 06, 2005

Sheet Title

SUMMARY OF QUANTITIES

831-04TKYD
Project Number
SJM 02/28/05
Layout By Date
AAP 02/28/05
Designed By Date
RMH/TMM 05/05/05
Reviewed By Date
SJM -
Drawn By Sheet No.

05/06/2005, 03:46 PM 1:04 Job: 03083193104TKYD\Civil\SHHEE118 Summary of Quantities.dgn