

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	SFTY-2A						
CODE NO	ITEM	UNIT		LOCATION 1 MCHENRY COOK COUNTY	LOCATION 2 SHERIDAN COOK COUNTY	LOCATION 3 TOUHY COOK COUNTY	LOCATION 4 IL 56 KANE COUNTY			
20300100	CHANNEL EXCAVATION	CU YD	520				520			
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,530			840	690			
28100109	STONE RIPRAP, CLASS A5	SQ YD	505	112	393					
28200200	FILTER FABRIC	SQ YD	288				288			
28400100	GABIONS	CU YD	30				30			
28401000	SLOPE MATTRESS, 12"	SQ YD	258				258			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	1	1	1			
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.33		0.34	0.33			
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1	1						
X0301853	DEWATERING STRUCTURE NO. 2	EACH	1		1					
X0301854	DEWATERING STRUCTURE NO. 3	EACH	1			1				
X0301855	DEWATERING STRUCTURE NO. 4	EACH	1				1			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	205.6	51.4	51.4	51.4	51.4			

FILE NAME = 0160J08-sht-500.dgn  
PLOT DATE = 5/10/2010

**CR & A**  
CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - K.R.K.  
DRAWN - J.V.  
CHECKED - G.F.L.  
DATE - MARCH, 2010

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
SCOUR COUNTERMEASURES - VARIOUS LOCATIONS

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-108 I	COOK/KANE	23	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J08	