



\* THE EXISTING METAL POST AND R1-1 SIGN AT RT STA 9+57 SHALL BE REMOVED AND RELOCATED TO RT STA 9+47. A W4-4P SHALL BE ADDED. THIS WORK SHALL BE PAID FOR AS "REMOVE AND RELOCATE SIGN NO. 1".

THE EXISTING METAL POST AND R1-1 SIGN AT LT STA 10+71 SHALL BE REMOVED AND RELOCATED TO LT STA 10+62. A W4-4P SHALL BE ADDED. THIS WORK SHALL BE PAID FOR AS "REMOVE AND RELOCATE SIGN NO. 2".

**LEGEND**

- (A) THERMOPLASTIC PAVEMENT MARKING, LINE 5"-YELLOW
- (B) THERMOPLASTIC PAVEMENT MARKING, LINE 5"-WHITE
- (C) THERMOPLASTIC PAVEMENT MARKING, LINE 6"-WHITE
- (D) THERMOPLASTIC PAVEMENT MARKING, LINE 12"-WHITE
- (E) THERMOPLASTIC PAVEMENT MARKING, LINE 24"-WHITE
- (F) THERMOPLASTIC PAVEMENT MARKING, DOUBLE LINE 5"-YELLOW (9" SPACING)
- (G) PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTERS AND SYMBOLS
- (H) THERMOPLASTIC PAVEMENT MARKING, LINE 12"-YELLOW

SHEET TITLE <b>PAVEMENT MARKING PLAN</b> STA 22+00.00 TO STA 35+76.94	
PROJECT FAU RTE. 8046 (MEADOWBROOK ROAD) SECTION 09-00465-00-PV CITY OF SPRINGFIELD SANGAMON COUNTY	PROJECT NO. 09040 SCALE 1"=50' DATE 4/19/10 DRAWN BY CHECKED BY DRAWING NO. 21