

SUMMARY OF QUANTITIES				URBAN 100% STATE					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				URBAN 100% STATE					CONSTRUCTION TYPE CODE																	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000																																				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8																																				
40600300	AGGREGATE (PRIME COAT)	TON	41	41																																				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3																																				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																																				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	99	99																																				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	858	858																																				
42001300	PROTECTIVE COAT	SQ YD	133	133																																				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	10215	10215																																				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400																																				
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	327	327																																				
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	245	245																																				
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	245	245																																				
55039700	STORM SEWERS TO BE CLEANED	FOOT	400	400																																				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	34	34																																				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3																																				
67100100	MOBILIZATION	L SUM	1	1																																				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																																				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																																				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18315	18315																																				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6105	6105																																				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	49	49																																				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	60	60																																				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2035	2035																																				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6105	6105																																				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	49	49																																				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	60	60																																				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	120	120																																				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	90	90																																				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	100	100																																				

\*specialty items

Rev. 7-15-09