

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
CODE NO	ITEM	UNIT	URBAN 100% STATE		I-000						CODE NO	ITEM	UNIT	URBAN 100% STATE		I-000							
			TOTAL QUANTITIES											TOTAL QUANTITIES									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8		8						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4		51.4							
40600300	AGGREGATE (PRIME COAT)	TON	41		41						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	402		402							
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	3		3						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	9		9							
40600895	CONSTRUCTING TEST STRIP	EACH	1		1																		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	99		99																		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	858		858																		
42001300	PROTECTIVE COAT	SQ YD	133		133																		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	10215		10215																		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400		400																		
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	1816		1816																		
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	1440		1440																		
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	700		700																		
55039700	STORM SEWERS TO BE CLEANED	FOOT	400		400																		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	34		34																		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		3																		
67100100	MOBILIZATION	L SUM	1		1																		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1																		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1																		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18315		18315																		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6105		6105																		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	49		49																		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	60		60																		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2035		2035																		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6105		6105																		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	49		49																		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	60		60																		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	120		120																		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	90		90																		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	100		100																		

*specialty items

Rev.