

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	08-00174-00-RS	KANE/COOK	19	3
CONTRACT NO. 63150				

CODE NO.	PAY ITEM	UNIT	CONST. CODE 1000 TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,770
40600300	AGGREGATE (PRIME COAT)	TON	65
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,620
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	215
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	157
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,835
42400800	DETECTABLE WARNINGS	SQ FT	305
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	19,235
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	9,585
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL & REPLACEMENT	FOOT	425
44002223	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 3/4 INCH	SQ YD	20
44002240	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 10 INCH	SQ YD	35
44201317	CLASS C PATCHES, TYPE II, 7 INCH	SQ YD	20
44201321	CLASS C PATCHES, TYPE III, 7 INCH	SQ YD	25
44201323	CLASS C PATCHES, TYPE IV, 7 INCH	SQ YD	75
44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQ YD	35
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	20
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	28,820
60255500	MANHOLES TO BE ADJUSTED	EACH	40
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6
60266600	VALVE BOXES TO BE ADJUSTED	EACH	4
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,080
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16,165
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	696
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,610
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,555
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,000
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	335
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	422
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	2
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,685
XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	1,493
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	100
XX006425	RESTORATION	SQ YD	185
	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 19 INCH	SQ YD	120

* INDICATES SPECIALTY ITEMS

Plotted: March 20, 2009 @ 11:00 AM By: Jim Golis - Tab: 03 Quantities - 22x34

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.



Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeiweb.com

CITY OF ELGIN
KANE COUNTY, ILLINOIS

NO.	DATE	REVISIONS
2	03-20-09	PER IDOT COMMENTS
1	02-13-09	PER IDOT COMMENTS

**SUMMIT STREET
LAPP IMPROVEMENTS**

SUMMARY OF QUANTITIES

DATE:	DECEMBER 2008
PROJECT NO:	EG0810
FILE:	EG0810-CVR
SHEET	3 OF 19

Path: H:\SBSKPROJ\EG0810\DWG\DWG_FINAL\ENCL\EG0810-CVR