


F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
* FAU 6883	09-00093-00-SW	FULTON	6	3
			CONTRACT NO. 89530	

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
SPECIALTY ITEMS	CODE NO.	ITEM	UNIT		SFTY-1B
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	19843	19843
	42400800	DETECTABLE WARNINGS	SQ. FT.	96	96
	44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	150	150
	44000600	SIDEWALK REMOVAL	SQ. FT.	14789	14789
	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
	60604400	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18	FOOT	150	150
	67100100	MOBILIZATION	L SUM	1	1
	70102620	TRAFFIC CONTROL & PROTECTION, STANDARD 701501	L SUM	1	1
	70102640	TRAFFIC CONTROL & PROTECTION, STANDARD 701801	L SUM	1	1
	X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ. YD.	60	60

S:\2470247-0900\CAD\15-Summary of Quantities.dwg

 MAUREN & STUTZ, INC. <small>ENGINEERS SURVEYORS</small>		1670 EAST ASH STREET CANTON, ILLINOIS 61520 PH. (309) 647-7831 FAX (309) 647-6155
SUMMARY OF QUANTITIES		
FOR: CITY OF CANTON, ILLINOIS		
REVISIONS _____ _____ _____ FIELD BK.	DATE <i>04/30/09</i> DESIGNED <i>GBM</i> CHECKED <i>-</i> DRAWN <i>NDP</i> CHECKED <i>GBM</i>	PROJECT NO. 247-09001 DRAWING NO. SHEET 3 OF 6