



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 20, 2020

SUBJECT: FAI Route 57 (I-57)
Project NHPP-Q18X(185)
Section (X1-6,X1-6-3,X1-5,X1-4-1,X1-4)RS-4
Williamson County
Contract No. 78787
Item No. 55, July 31, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Revised page 91 of the Special Provisions.
4. Revised sheets 9, 49, and 50 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

PORTLAND CEMENT CONCRETE PAVEMENT PATCHING (BDE)	57
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE).....	58
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	66
SPEED DISPLAY TRAILER (BDE)	77
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	78
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	78
SURFACE TESTING OF HOT-MIX ASPHALT OVERLAYS (BDE)	79
TEMPORARY PAVEMENT MARKING (BDE).....	79
TRAFFIC CONTROL DEVICES - CONES (BDE).....	82
TRAFFIC SPOTTERS (BDE).....	82
TRAINING SPECIAL PROVISIONS (BDE)	83
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION...	86
WARM MIX ASPHALT (BDE)	88
WEEKLY DBE TRUCKING REPORTS (BDE).....	89
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	90
WORKING DAYS (BDE)	91
GEOTECHNICAL FABRIC FOR GROUND STABILIZATION.....	91
PROJECT LABOR AGREEMENT	92

Category 4 includes portable or trailer-mounted devices such as arrow boards, changeable message signs, temporary traffic signals, and area lighting supports. It is preferable for Category 4 devices manufactured after December 31, 2019 to be MASH-16 compliant; however, there are currently no crash tested devices in this category, so it remains exempt from the NCHRP 350 or MASH compliance requirement.

For each type of device, when no more than one MASH-16 compliant is available, an NCHRP 350 or MASH-2009 compliant device may be used, even if manufactured after December 31, 2019.”

Revise Articles 1106.02(g), 1106.02(k), and 1106.02(l) to read:

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **90** working days.

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION

This work at locations shown in the plans shall be according to Section 210 except Article 210.04 shall be deleted.

Revised July 20, 2020