ITEM 04A

LETTING DATE: JULY 31, 2020

TOTAL SHEETS: 95 CA021

CONSTRUCTION PLANS FOR ABRAHAM LINCOLN CAPITAL AIRPORT

SPRINGFIELD AIRPORT AUTHORITY SPRINGFIELD, IL

IL. PROJ. NO: SPI-4755

AIP PROJ. NO: 3-17-0096-XX

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



COMMON GROUND ALLIANCE www.call811.com or Phone: 811

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES DETAILED INFORMATION AND SASISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE RIGHER SHALL ALS DE BIE MIMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR TO A DUD FOR BY THE CONTRACTOR TO A DUD FOR BY THE CONTRACTOR TO A DOLD THE CONTRACTOR.

CALL 911 IN THE EVENT IN WHICH DAMAGE RESULTS IN THE RELEASE OF NATURAL GAS.

DESIGN INFORMATION

GEOMETRIC CRITERIA

TAXIWAY CONSTRUCTION

APPROACH CATEGORY C


AIRPLANE DESIGN GROUP III

TAXIWAY DESIGN GROUP 3


TAXIWAY SAFETY AREA: 118'
TAXIWAY OBJECT FREE AREA: 186'
TAXIWAY WIDTH: 50'

ABRAHAM LINCOLN CAPITAL AIRPORT

TOWNSHIP: 16 NORTH RANGE: 5 WEST OF THE 4TH P.M. SECTION: 8, 9, 16 & 17 COUNTY: SANGAMON CIVIL TOWNSHIP: CAPITAL **JUNE 29, 2020**



LOCATION MAP



SITE PLAN





		Sheet List Table
Sheet No.	Sheet Index	Sheet Title
1	Gl001	COVER SHEET
2	GI002	INDEX TO SHEETS & SUMMARY OF QUANTITIES
3	GI101	AIRPORT SITE PLAN
4	GI102	CONTRACT OVERVIEW & CONST. ACCESS
5	GC001	CONSTRUCTION ACTIVITY PLAN NOTES 1
6	GC002	CONSTRUCTION ACTIVITY PLAN NOTES 2
7	GC003	CONSTRUCTION ACTIVITY PLAN DETAILS
8	GC101	CONSTRUCTION ACTIVITY PLAN - PHASE 1A
9	GC102	CONSTRUCTION ACTIVITY PLAN - PHASE 1B
10	GC103	CONSTRUCTION ACTIVITY PLAN - PHASE 2
11	GC104	CONSTRUCTION ACTIVITY PLAN - PHASE 3
12	GC105	CONSTRUCTION ACTIVITY PLAN - PHASE 4
13	CD001	EXISTING PAVEMENT STRUCTURES
14	CD002	EXISTING UTILITIES 1
15	CD003	EXISTING UTILITIES 2
16	CD100	RUNWAY 18-36 CLOSURE 1
17	CD101	RUNWAY 18-36 CLOSURE 2
18	CD102	EXISTING CONDITIONS AND REMOVALS 1
19	CD102	EXISTING CONDITIONS AND REMOVALS 2
20	CD104	EXISTING CONDITIONS AND REMOVALS 3
21	CD105	EXISTING CONDITIONS AND REMOVALS 4
22	CD103	EXISTING CONDITIONS AND REMOVALS 5
23	CD100	EXISTING CONDITIONS AND REMOVALS 6
24	CD107	EXISTING CONDITIONS AND REMOVALS 7
25	CP100	HORIZONTAL CONTROL
26	CP101	PROPOSED GEOMETRY
27	CP101	RUNWAY 4 THRESHOLD IMPROVEMENTS
28	CP201	PLAN & PROFILE - TAXIWAY A
29	CP202	PLAN & PROFILE - TAXIWAY H
30	CP202	PLAN & PROFILE - TAXIWAY Y
31	CP301	TYPICAL SECTION
32	CP302	PAVEMENT TRANSITION DETAILS
33	CJ101	JOINTING PLAN 1
34	CJ102	JOINTING PLAN 2
35	CS102	STAKING PLAN
36	CJ501	PAVING DETAILS 1
37	CJ501	PAVING DETAILS 1
38	CG101	GRADING & DRAINAGE PLAN 1
		GRADING & DRAINAGE PLAN 2
39 40	CG102 CG103	GRADING & DRAINAGE PLAN 3
41	CG104	GRADING & DRAINAGE PLAN 4 GRADING & DRAINAGE PLAN 5
42 43	CG105 CG301	GRADING & DRAINAGE FLAN S
		STORM SEWER AND UNDERDRAIN PLAN 1
44	CU101	STORM SEWER AND UNDERDRAIN PLAN 1
45	CU102	STORM SEWER SCHEDULES
46	CU103	UNDERDRAIN SCHEDULES
47	CU104	STORM SEWER PROFILES
48	CU201	OTONIVI DEWEN FROFILED

Chast	Sheet	Sheet List Table	
Sheet No.	Index	Sheet Title	
49	CU501	UNDERDRAIN DETAILS	
50	CU502	STORM SEWER DETAILS 1	
51	CU503	STORM SEWER DETAILS 2	
52	EL101	LIGHTING & SIGNAGE PLAN 1	
53	EL102	LIGHTING & SIGNAGE PLAN 2	
54	EL103	LIGHTING & SIGNAGE PLAN 3	
55	EL201	CABLING PLAN 1	
56	EL202	CABLING PLAN 2	
57	EL203	CABLING PLAN 3	
58	EL 401	LIGHTING SCHEDULE	
59	EL402	SIGNAGE SCHEDULE	
60	EL501	ELECTRICAL DETAILS 1	
61	EL502	ELECTRICAL DETAILS 2	
62	EL503	ELECTRICAL DETAILS 3	
63	EL504	ELECTRICAL DETAILS 4	
64	CM101	PAVEMENT MARKING PLAN 1	
65	CM102	PAVEMENT MARKING PLAN 2	
66	CM501	PAVEMENT MARKING DETAILS 1	
67	CM502	PAVEMENT MARKING & SIGNAGE DETAILS	
68	LG101	EROSION CONTROL & TURFING PLANS 1	
69	LG102	EROSION CONTROL & TURFING PLANS 2	
70	LG103	EROSION CONTROL & TURFING PLANS 3	
71	LG104	EROSION CONTROL & TURFING PLANS 4	
72	LG501	EROSION CONTROL DETAILS	
73	CG700	CROSS SECTION INDEX - REMOVALS	
74	CG701	CROSS SECTIONS - RWY 18-36 REMOVALS 1	
75	CG702	CROSS SECTIONS - RWY 18-36 REMOVALS 2	
76	CG703	CROSS SECTIONS - RWY 18-36 REMOVALS 3	
77	CG704	CROSS SECTIONS - RWY 18-36 REMOVALS 4	
78	CG705	CROSS SECTIONS - RWY 18-36 REMOVALS 5	
79	CG706	CROSS SECTIONS - RWY 18-36 REMOVALS 6	
80	CG707	CROSS SECTIONS - RWY 18-36 REMOVALS 7	
81	CG708	CROSS SECTIONS - RWY 18-36 REMOVALS 8	
82	CG709	CROSS SECTIONS - RWY 18-36 REMOVALS 9	
83	CG710	CROSS SECTIONS - RWY 18-36 REMOVALS 10	
84	CG711	CROSS SECTIONS - RWY 18-36 REMOVALS 11	
85	CG712	CROSS SECTIONS - RWY 18-36 REMOVALS 12	
86	CG713	CROSS SECTIONS - RWY 18-36 REMOVALS 13	
87	CG714	CROSS SECTIONS - TXY E REMOVALS 1	
88	CG715	CROSS SECTIONS - TXY E REMOVALS 2	
89	CG716	CROSS SECTIONS - TXY E REMOVALS 3	
90	CG717	CROSS SECTIONS - TXY E REMOVALS 4	
91	CG800	CROSS SECTION INDEX - NEW TAXIWAYS	
92	CG801	CROSS SECTIONS - TAXIWAY A 1	
93	CG802	CROSS SECTIONS - TAXIWAY A 2	
94	CG803	CROSS SECTIONS - TAXIWAY H	
95	CG804	CROSS SECTIONS - TAXIWAY Y	

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTI
AR 106910	REMOVE LIGHT FIXTURE	EA	27
AR 106930	REPLACE LIGHT FIXTURE	EA	27
AR 108108	1/C #8 5 KV UG CABLE	LF	280
AR 108158	1/C #8 5 KV UG CABLE IN UD	LF	6,400
AR 108258	2/C #8 5 KV UG CABLE IN UD	LF	1,135
AR 108706	1/C #6 COUNTERPOISE	LF	7,815
AR 110504	4-WAY CONCRETE ENCASED DUCT	LF	100
AR 125100	ELEVATED RETROREFLECTIVE MARKER	EA	15
AR 125416	MITL - BASE MOUNTED - LED	EA	74
AR 125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EA	2
AR 125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EA	2
AR 125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EA	5
AR 125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EA	1
AR 125470	MODIFY SIGN PANEL	EA	4
AR 125525	HIRL, IN-PAVEMENT	EA	1
AR 125565	SPLICE CAN	EA	3
AR 125901	REMOVE STAKE MOUNTED LIGHT	EA	49
AR 125902	REMOVE BASE MOUNTED LIGHT	EA	135
AR 125904	REMOVE TAXI GUIDANCE SIGN	EA	30
AR 125905	REMOVE RWY DISTANCE REMAIN SIGN	EA	4
AR 125906	REMOVE SPLICE CAN	EA	1
AR 150510	ENGINEER'S FIELD OFFICE	LS	1
AR 152410	UNCLASSIFIED EXCAVATION	CY	7,530
AR 152512	SUBGRADE REPAIR	CY	290
AR 154506	GRANULAR SUBBASE - 6"	SY	9,920
AR 156510	SILT FENCE	LF	3,360
AR 156520	INLET PROTECTION	EA	8
AR 156530	TEMPORARY SEEDING	AC	0.6
AR 209600	GEOTEXTILE FABRIC	SY	9,920
AR 401610	BITUMINOUS SURFACE COURSE	TON	105
AR 401650	BITUMINOUS PAVEMENT MILLING	SY	870
AR 501527	17.5" PCC PAVEMENT	SY	8,850
AR 501905	REMOVE PAVEMENT	SY	30,515
AR 603510	BITUMINOUS TACK COAT	GAL	6,210
AR 620520	PAVEMENT MARKING - WATERBORNE	SF	16,000
AR 620525	PAVEMENT MARKING - BLACK BORDER	SF	4,375
AR 620900	PAVEMENT MARKING REMOVAL	SF	17,200
AR 701512	12" RCP, CLASS IV	LF	1,225
AR 701900	REMOVE PIPE	LF	25
AR 705524	4" PERFORATED UNDERDRAIN W/SOCK	LF	2,720
AR 705635	UNDERDRAIN COLLECTION STRUCTURE	EA	7
AR 705640	UNDERDRAIN CLEANOUT	EA	9
AR 705645	UNDERDRAIN CONNECTION	EA	4
AR 751410	INLET	EA	6
AR 751530	MANHOLE	EA	1
AR 751900	REMOVE INLET	EA	1
AR 800308	EXPLORATORY EXCAVATION	EA	4
AR 901510	SEEDING	AC	6.0
AR 904510	SODDING	SY	1,640
AR 908515	HEAVY-DUTY HYDRAULIC MULCH	AC	6.0

	ALTERNATE 1				
	ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	
	AS 125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EA	2	
	AS 125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EA	2	
	AS 125515	HIRL, BASE MOUNTED	EA	2	
	AS 152410	UNCLASSIFIED EXCAVATION	CY	4,410	
	AS 156510	SILT FENCE	LF	1,220	
1	AS 156520	INLET PROTECTION	EA	3	
1	AS 156530	TEMPORARY SEEDING	AC	0.4	
	AS 501905	REMOVE PAVEMENT	SY	10,145	
1	AS 701512	12" RCP, CLASS IV	LF	155	
	AS 701515	15" RCP, CLASS IV	LF	225	
1	AS 701524	24" RCP, CLASS IV	LF	190	
	AS 751410	INLET	EA	3	
1	AS 751940	ADJUST INLET	EA	1	
	AS 800308	EXPLORATORY EXCAVATION	EA	2	
	AS 901510	SEEDING	AC	3.6	
	AS 904510	SODDING	SY	660	
1	AS 908515	HEAVY-DUTY HYDRAULIC MULCH	AC	3.6	

713 300313	TILAVI-DOTT TITDINAGLIC MOLCIT	7	5.0		
	ALTERNATE 2				
ITEM NO. ITEM DESCRIPTION UNIT QUANTI					
AT 110900	REMOVE DUCT	LF	125		
AT 125462	TAXI GUIDANCE SIGN, UNLIT	EA	1		
AT 125901	REMOVE STAKE MOUNTED LIGHT	EA	16		
AT 125902	REMOVE BASE MOUNTED LIGHT	EA	2		
AT 125904	REMOVE TAXI GUIDANCE SIGN	EA	1		
AT 152410	UNCLASSIFIED EXCAVATION	CY	7,790		
AT 152621	REMOVE CONCRETE	CY	155		
AT 156510	SILT FENCE	LF	1,120		
AT 156520	INLET PROTECTION	EA	6		
AT 156530	TEMPORARY SEEDING	AC	0.4		
AT 501120	RUBBLIZE PAVEMENT	SY	4,880		
AT 800308	EXPLORATORY EXCAVATION	EA	2		
AT 800331	PAVEMENT MILLING, 6"	SY	4,880		
AT 901510	SEEDING	AC	3.7		
AT 908515	HEAVY-DUTY HYDRAULIC MULCH	AC	3.7		

	ALTERNATE 3			
ITEM NO. ITEM DESCRIPTION UNIT QUANTITY				
AU 152410	UNCLASSIFIED EXCAVATION	CY	670	
AU 156510	SILT FENCE	LF	2,535	
AU 156520	INLET PROTECTION	EA	3	
AU 156530	TEMPORARY SEEDING AC 0.		0.6	
AU 501120	RUBBLIZE PAVEMENT SY 20,97		20,975	
AU 800308	EXPLORATORY EXCAVATION	EA	2	
AU 800331	0331 PAVEMENT MILLING, 6" SY 20,975		20,975	
AU 901510	SEEDING	AC	6.2	
AU 908515	HEAVY-DUTY HYDRAULIC MULCH AC 6.2			



JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1




SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL


MARK	DATE	DESCRIPTION

AIP PROJ. NO: 3-17-	CA021	
IL. PROJ. NO: SPI-47		
CMT PROJECT NO:	180035-05	
CAD DWG FILE:	18003505-PH1-GI002.DWG	
DESIGNED BY:	HWI	
DRAWN BY:	DPA	
CHECKED BY:	MJD	
APPROVED BY:	RLV	
CODVDIGHT:		

INDEX TO SHEETS & SUMMARY OF QUANTITIES

GI002





GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2 (LATEST VERSION), AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SUBMIT TO THE AIRPORT FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2 (LATEST VERSION). NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING OSHA REQUIREMENTS.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SIGN THE SWPPP CERTIFICATION STATEMENT.
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT UNLESS A SPECIFIC PAY ITEM IS PROVIDED.

COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT, ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE
- ON OR BEFORE THE PRECONSTRUCTION CONFERENCE. THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS. ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT.
- DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH THE AIRPORT STAFF AND RESIDENT ENGINEER. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT.

PHASING

PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN (CAP) SHEETS

AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS ALLOWED IN THE PLANS.
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT
- ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING AIRCRAFT AT ALL TIMES.

PROTECTION OF NAVIGATION AIDS (NAVAIDS)

THE CONTRACTOR SHALL REMAIN CLEAR OF THE ILS CRITICAL AREAS AND OTHER NAVAIDS FACILITIES AT ALL TIMES.

CONTRACTOR ACCESS

- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN IN THE PLANS, ALL COSTS RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE GATES SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE ACCESS GATE(S) CLOSED DURING WORK HOURS OR THE CONTRACTOR SHALL POST A COMPETENT SECURITY GUARD TO CONTROL ACCESS AT THE GATE. THE CONTRACTOR SHALL REPLACE ANY UNSATISFACTORY SECURITY GUARDS AS DIRECTED
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND TEMPORARY EASEMENTS FOR THE PUBLIC ACCESS ROAD(S) SHOWN AND SHALL COMPLY WITH ALL REQUIREMENTS, LOAD RESTRICTIONS, & TRAFFIC CONTROL SIGNAGE REQUIRED BY THE CITY, COUNTY, TOWNSHIP, OR I.D.O.T.
- CONTRACTOR EMPLOYEES MAY BE REQUIRED TO OBTAIN AN AIRPORT IDENTIFICATION BADGE. THIS CONSISTS OF FILLING OUT ALL NECESSARY PAPERWORK, FINGERPRINTING, ATTENDING AND PASSING A TRAINING CLASS CONCERNING SAFETY AND SECURITY AT THE AIRPORT CONTRACTOR EMPLOYEES MUST MEET BACKGROUND CHECK CRITERIA AND THE CONTRACTOR MUST MAKE CERTIFICATION ABOUT EACH EMPLOYEE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FINGERPRINTING COSTS
- ALL CONTRACTOR EMPLOYEES WHO ARE DESIGNATED AS DRIVERS FOR THE CONTRACTOR WITHIN THE AIRFIELD OPERATIONS AREA (AOA) SHALL ALSO ATTEND AND PASS THE AIRPORT DRIVERS TRAINING PROGRAM, ONLY THOSE INDIVIDUALS WHO RECEIVE THIS DESIGNATION WILL BE PERMITTED TO OPERATE VEHICLES OR EQUIPMENT ON THE AIRPORT. ALL COSTS ASSOCIATED WITH THE DRIVER TRAINING PROGRAM SHALL BE BORNE BY THE CONTRACTOR.
- CONTRACTOR'S VEHICLES AND EQUIPMENT SHALL BE MARKED AND FLAGGED PER THE PLAN DETAILS AND SPECIFICATIONS. MAXIMUM HEIGHT OF CONTRACTOR'S EQUIPMENT WILL BE 25'.
- DRIVERS OF TRUCKS CONTAINING MATERIAL DELIVERIES (AGGREGATE, CONCRETE, ETC.) WILL NOT NEED TO OBTAIN AN AIRPORT ID BADGE BUT SHALL BE REQUIRED TO SUBMIT THEIR NAME, DRIVER'S LICENSE NUMBER, TRUCK LICENSE PLATE NUMBER AND NAME OF TRUCKING COMPANY TO THE PRIME CONTRACTOR PRIOR TO ENTERING THE JOBSITE. WHILE INSIDE THE AOA, THE TRUCK DRIVERS SHALL BE UNDER THE CONTROL OF AND SUPERVISED BY THE CONTRACTOR
- CONTRACTOR WORK CREWS MUST MAINTAIN RADIO CONTACT WITH AIR TRAFFIC AND THE AIR TRAFFIC CONTROL TOWER (ATCT) AT ALL TIMES WHEN WITHIN THE MOVEMENT AREA. CONTRACTOR SHALL SUPPLY ALL APPROPRIATE RADIOS NEEDED FOR COMMUNICATIONS AND ONLY HIS PERSONNEL WHO HAVE SUCCESSFULLY PASSED THE APPROVED AIRPORT TESTS MAY OPERATE THESE RADIOS.
- ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS, TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT IN RADIO CONTACT WITH THE ATCT. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMEN.
- 10. THE CONTRACTORS STORAGE AND STAGING AREAS WILL BE AS
- 11. THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR.
- WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE RETURNED TO & STORED AT THE STAGING AREA
- DURING ADVERSE WEATHER THE CONTRACTOR SHALL MAINTAIN ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF THE CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK SITE.
- THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE. EXISTING TURF AREAS DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE ENGINEER AND THE AIRPORT.
- THE CONTRACTOR SHALL THOROUGHLY CLEAN ALI CONSTRUCTION AREAS AND HAUL ROUTES WHICH ARE OR WILL BE OPENED TO AIR TRAFFIC TO THE SATISFACTION OF THE AIRPORT. A POWER BROOM AND OPERATOR SHALL BE ON SITE AT ALL TIMES WHEN ACTIVE PAVEMENTS ARE UTILIZED FOR CONSTRUCTION

CONTRACTOR ACCESS (CONTINUED)

- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS OR STORAGE AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION. NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR THIS WORK.
- ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE
- THE CONTRACTOR SHALL NOTIFY THE AIRCRAFT RESCUE AND FIRE FIGHTING (ARFF) FACILITY IF CONSTRUCTION ACTIVITY MAY REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE

WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY THE AIRPORT IF ANY WILDLIFF IS SEEN ON OR ENTERING THE AIRPORT
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING.
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED
- THE CONTRACTOR SHALL CONTROL GRASS HEIGHTS THROUGH MOWING TO ASSIST WITH WILDLIFE CONTROL.

FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS.
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.

8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOURS NOTICE TO THE AIRPORT PRIOR TO CLOSING ANY PAVEMENTS SO THAT PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- 4. IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL

10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2 (LATEST VERSION) MAY BE USED TO AID IN THE INSPECTIONS.
- THE CONTRACTOR SHALL REQUEST AND ATTEND AN INSPECTION OF EACH PHASE WORK AREA PRIOR THE AREA BEING REOPENED. THE AIRPORT WILL DETERMINE IF THE WORK AREA IS SUITABLE TO

11. UNDERGROUND UTILITIES

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROUND UTILITIES AT CRITICAL POINTS. LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS, NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. ANY UTILITY, INCLUDING AIRFIELD ELECTRICAL CABLE AND LIGHTS, DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY HIM AT HIS OWN EXPENSE IN A MANNER WHICH IS SATISFACTORY TO THE ENGINEER AND TO THE OWNER OF THE UTILITY. ANY REPAIRS THAT MUST BE MADE BY THE OWNER OF THE UTILITY SHALL HAVE THE COST REIMBURSED TO THE UTILITY BY THE CONTRACTOR. AIRFIELD LIGHTING CABLES DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY A QUALIFIED ELECTRICIAN WITH THE COSTS TO BE BORNE BY THE
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. THE AIRPORT, AND CONTACT THE LOCAL FAA OFFICE (847-294-7336) TO ARRANGE FOR UTILITY LOCATES.

12. PENALTIES

- NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT BULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP, THE CONTRACTOR'S APPROVED SPCD OR THE SECURITY PLAN MAY RESULT IN FINES AS ALLOWED BY LAW.
- FINES CAN BE LEVIED AGAINST THE CONTRACTOR BY THE TRANSPORTATION SECURITY ADMINISTRATION (TSA) FOR NEGLIGENCE IF THE AIRPORT SECURITY IS COMPROMISED AND THE AIRPORT PERIMETER FENCE LINE IS NOT MAINTAINED AS SPECIFIED ABOVE. FINES CAN ALSO BE LEVIED AGAINST THE CONTRACTOR FOR FAILURE TO COOPERATE WITH THE AIRPORT MANAGEMENT AS REQUIRED TO MAINTAIN AIRPORT SECURITY.

13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL

14. RUNWAY AND TAXIWAY VISUAL AIDS

- ALL BLINWAYS TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRPORT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED IN
- 2. IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOWING THE REQUIREMENTS OF THE PLANS & FAA AC 150/5370-2 (LATEST VERSION.)

15. MARKING AND SIGNS FOR ACCESS ROUTES

BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED IN THE PLANS.

16. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT.
- ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G AND 150/5210-5D (OR LATEST) AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN IN THE PLANS OR AS DIRECTED BY THE AIRPORT.
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT.

17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION

- THE CONTRACTOR SHALL PROVIDE ADEQUATE LIGHTING DURING NIGHTTIME CONSTRUCTION.
- ARTIFICIAL AREA LIGHTING SHALL CONSIST OF VEHICLE OR POLE MOUNTED FLOODLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL ONLY BE ALLOWED IN ADDITION TO THE AREA LIGHTING
- ARTIFICIAL AREA LIGHTING SHALL NOT INTERFERE WITH AIR TRAFFIC OR ATCT OPERATIONS.
- PLACEMENT & AIMING OF ARTIFICIAL LIGHTING SHALL BE APPROVED BY THE AIRPORT PRIOR TO START OF OPERATIONS

18. PROTECTION OF AREAS & SURFACES

- ALL WORK REQUIRED INSIDE OF THE RUNWAY 4-22, 13-31 OR 18/36 SAFETY AREAS, WHICH EXTENDS 250' FROM THE RUNWAY CENTERLINE, WILL REQUIRE THE BUNWAY TO BE CLOSED, THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT A MINIMUM OF 72 HOURS PRIOR TO THE REQUESTED CLOSURE TIME.
- ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA, WHICH EXTENDS 93' FROM THE TAXIWAY CENTERLINE, WILL REQUIRE THE TAXIWAY TO BE CLOSED. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT A MINIMUM OF 72 HOURS PRIOR TO THE REQUESTED
- ALL WORK REQUIRED ON AN ACTIVE TAXILANE OBJECT FREE AREA, WHICH EXTENDS 81' FROM THE TAXILANE/APRON CENTERLINE, WILL REQUIRE A PORTION OF THAT APRON TO BE CLOSED. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT A MINIMUM OF 72 HOURS PRIOR TO THE REQUESTED CLOSURE TIME.

(NOTES CONTINUE ON SHEET GC002)



JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL

MARK	DATE	DESCRIPTION	

CA021 .. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-GC000.DWG DESIGNED BY: HWI DPA CHECKED BY: MJD PPROVED BY: RLV

CONSTRUCTION **ACTIVITY PLAN** NOTES 1

GC001

95

(NOTES CONTINUED FROM SHEET GC001)

19. OTHER LIMITATIONS ON CONSTRUCTION

- IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.
- BROKEN CONCRETE, BROKEN ASPHALT, RUBBISH FROM DEMO, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY. UNI ESS OTHERWISE SPECIFIED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEGGAR TESTING ALL EXISTING CIRCUITS PRIOR TO CONSTRUCTION AND FOLLOWING CONSTRUCTION AS SPECIFIED IN THE SPECIFICATIONS.

20. AIRPORT SECURITY REQUIREMENTS

- MAINTAINING THE SECURITY REQUIREMENTS OF THE AIRPORT SHALL BE A PRIMARY CONCERN FOR THE CONTRACTOR.
- 2. A LIST OF PERSONNEL AUTHORIZED TO WORK ON THE AIRFIELD SHALL BE PROVIDED TO THE RESIDENT ENGINEER BY THE CONTRACTOR. THE SUPERINTENDENT AND FOREMAN THAT ARE ISSUED BADGES SHALL BE DIRECTLY RESPONSIBLE FOR THE IDENTITY AND LOCATION OF THOSE THEY ARE SUPERVISING WHILE ON THE AIRFIELD. BADGES SHALL BE RETURNED TO THE AIRPORT AT THE FINAL INSPECTION OR WHEN THE PERSON IS NO LONGER EMPLOYED BY THE CONTRACTOR. THE CONTRACTOR WILL PAY A FEE OF \$200.00 WITHIN 15 DAYS FOR EACH ACCESS BADGE THAT IS LOST, DESTROYED, STOLEN, OR NOT RETURNED AT THE FINAL INSPECTION.
- 3. THE CONTRACTOR WILL BE RESPONSIBLE FOR MAINTAINING AIRPORT SECURITY BY SUPERVISING OPENINGS OR MAINTAINING THE AIRPORT PERIMETER FENCE LINE AT ALL TIMES.
- 4. THE CONTRACTOR SHALL COMPLETE A SECURITY FORM FOR ALL PERSONNEL HE PROPOSES TO USE ON THE AIRPORT. THESE FORMS SHALL BE COMPLETED PRIOR TO THAT PERSON BEING ALLOWED ON THE AIRFIELD. A LIST OF PERSONNEL AUTHORIZED TO WORK ON THE AIRFIELD SHALL BE PROVIDED TO THE RESIDENT ENGINEER BY THE CONTRACTOR.
- 5. THE CONTRACTOR SHALL INSTALL AND USE TEMPORARY GATES FOR ACCESS TO THE AIRFIELD. THE CONTRACTOR SHALL INSTALL AND MAINTAIN A HEAVY-DUTY PADLOCK ON THE ACCESS GATE. HE SHALL PROVIDE KEYS FOR HIS PADLOCK TO THE RESIDENT ENGINEER, THE MAINTENANCE SUPERVISOR, AND THE SECURITY CHIEF. NO ADDITIONAL KEYS ARE TO BE DISTRIBUTED UNLESS AUTHORIZED BY THE RESIDENT ENGINEER. NO ADDITIONAL PAYMENT SHALL BE MADE FOR THE INSTALLATION AND REMOVAL OF TEMPORARY ACCESS GATES.
- 6. AS A MINIMUM, THE CONTRACTOR SHALL BE RESPONSIBLE FOR SECURITY DURING CONSTRUCTION AS FOLLOWS:
 - a. POSSESS A COPY OF THE AIRPORT'S PROJECT SECURITY PLAN.
 - b. VISIBLY DELINEATE HIS CONSTRUCTION ZONE BY PLACING A LINE OF BARRICADES OR FLAGGING AROUND THE ENTIRE WORK ZONE DURING EACH PHASE OF THE CONTRACT.
 - C. COMPLY WITH THE AIRPORT'S SECURITY PLAN ASSOCIATED WITH THE CONSTRUCTION PROJECT AND ENSURE THAT CONSTRUCTION PERSONNEL ARE FAMILIAR WITH SECURITY PROCEDURES AND REGULATIONS ON THE AIRPORT.
 - d. ENSURE THAT NO CONSTRUCTION EMPLOYEES, EMPLOYEES OF SUBCONTRACTORS OR SUPPLIERS, OR OTHER PERSONS ENTER ANY PART OF THE AIRCRAFT OPERATIONS AREA FROM CONSTRUCTION SITE UNLESS AUTHORIZED.
 - e. THE AIRPORT MAY REQUIRE THAT ALL SECURITY GUARDS UNDERGO ADDITIONAL TRAINING NECESSARY TO MEET THE AIRPORT'S SECURITY NEEDS.
 - f. THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN SECURITY ON THE AIRPORT AS SPECIFIED OR AS DIRECTED BY THE AIRPORT
 - g. THE CONTRACTOR'S SUPERINTENDENT, FOREMAN, SECURITY GUARDS, AND ANY SUPERVISORY PERSONNEL IN CHARGE OF OTHER WORKERS SHALL OBTAIN AN AIRPORT AUTHORITY SECURITY BADGE AND DISPLAY THIS BADGE WHILE ON SITE IN ACCORDANCE WITH FAA AND TSA REGULATIONS. CONTRACTOR PERSONNEL WITH BADGES SHALL BE DIRECTLY RESPONSIBLE FOR THE IDENTITY AND LOCATION OF THOSE THEY ARE SUPERVISING WHILE ON THE AIRFIELD.

20. AIRPORT SECURITY REQUIREMENTS (CONT'D)

- h. TO OBTAIN AIRPORT SECURITY BADGES, CONTRACTORS MUST COMPLETE A CRIMINAL HISTORY RECORDS CHECK TWO WEEKS PRIOR TO EMPLOYEES BEING ALLOWED ACCESS TO THE SITE. THE TWO-WEEK PERIOD IS NECESSARY FOR AN ADEQUATE TIME OF PROCESSING FINGERPRINTS FOR COMPLETING THE CRIMINAL HISTORY CHECK. THE CONTRACTOR IS REQUIRED TO DEPOSIT A \$200 FEE TO THE AIRPORT PER BADGE, WHICH IS 80% REFUNDABLE AFTER EACH BADGE IS RETURNED. THE AIRPORT MUST RECEIVE THIS FEE/DEPOSIT PRIOR TO CONDUCTING ANY OF THE SECURITY BADGE ISSUE PROCESS. THE CONTRACTOR IS REQUIRED TO CONTACT THE AIRPORT AT LEAST THREE CALENDAR DAYS PRIOR TO SCHEDULING FINGERPRINTING AND BADGE TRAINING. TRAINING LASTS APPROXIMATELY TWO HOURS AND CAN BE CONDUCTED INDIVIDUALLY OR WITH A GROUP
- i. THE UNITED STATES DEPARTMENT OF HOMELAND SECURITY HAS DESIGNATED THE SECURITY LEVEL AS HIGH RISK AT ABRAHAM LINCOLN CAPITAL AIRPORT. SUBSEQUENTLY, THE AIRPORT MUST HAVE ALL SECURITY ACTIVITY AND PROGRAMS APPROVED BY THE UNITED STATES DEPARTMENT OF HOMELAND SECURITY TRANSPORTATION SECURITY ADMINISTRATION, TO OBTAIN AIRPORT AUTHORITY ACCESS BADGES, THE CONTRACTOR SHALL PROVIDE COMPLETED ACCESS CONTROL FORMS PROVIDED BY THE AIRPORT FOR ALL PERSONNEL HE PROPOSES TO USE ON THE AIRPORT. THE CONTRACTORS WILL NEED TO PROVIDE THE AIRPORT AUTHORITY WITH DOCUMENTATION FROM THE LIST OF ACCEPTABLE DOCUMENTS, WHICH ESTABLISHES BOTH IDENTITY AND EMPLOYMENT AUTHORIZATION TWO WEEKS PRIOR TO EMPLOYEES BEING ALLOWED ACCESS TO THE SITE. THE TWO-WEEK PERIOD IS NECESSARY FOR AN ADEQUATE TIME OF PROCESSING OF A SECURITY THREAT ASSESSMENT (STA) FOR EACH EMPLOYEE REQUESTING ACCESS BY THE HOMELAND SECURITY TRANSPORTATION SECURITY ADMINISTRATION. THE CONTRACTOR IS REQUIRED TO CONTACT THE DIRECTOR OF OPERATIONS AND PUBLIC SAFETY AT 217-494-0787 FOR THE SCHEDULING OF ALL ACCESS BADGE APPLICATIONS.
- j. A MINIMUM OF SEVEN (7) DAYS PRIOR TO CONSTRUCTION, A MANDATORY SAFETY MEETING WILL BE CONDUCTED FOR ALL PARTIES INVOLVED. THIS SAFETY MEETING WILL INCLUDE A REVIEW OF A TRANSPORTATION SECURITY ADMINISTRATION (TSA) APPROVED ABRAHAM LINCOLN CAPITAL AIRPORT CHANGE OF CONDITION FOR THIS CONSTRUCTION PROJECT. THIS REVIEW WILL INCLUDE A SET OF SECURITY REQUIREMENTS AND PROCEDURES THAT THE CONTRACTOR WILL BE REQUIRED TO FOLLOW AT ALL TIMES WHILE OPERATING AT THE AIRPORT.
- k. THE CONTRACTOR WILL DESIGNATE A MINIMUM OF ONE INDIVIDUAL TO BE THE 24-HOUR POINT OF CONTACT AND ASSUME ALL ON-SITE SECURITY RESPONSIBILITIES FOR ALL EMPLOYEES DURING THE PROJECT. THIS INDIVIDUAL SHALL PROVIDE THE AIRPORT AUTHORITY A 24-HOUR CONTACT FOR EMERGENCY PURPOSES. THIS INDIVIDUAL WILL ALSO BE REQUIRED TO HAVE AVAILABLE AND PRESENT UPON REQUEST AT ANY TIME; A COPY OF THE TRANSPORTATION SECURITY ADMINISTRATION (TSA) APPROVED CHANGE OF CONDITION DURING THE PROJECT.
- I. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE ACCESS GATE CLOSED AND LOCKED DURING WORK HOURS. IF THE CONTRACTOR CHOOSES TO LEAVE THE GATE OPEN, THEN HE SHALL POST A COMPETENT, PROPERLY TRAINED SECURITY GUARD TO PREVENT UNAUTHORIZED ENTRIES. THE CONTRACTOR SHALL REPLACE ANY UNSATISFACTORY SECURITY GUARDS IF SO DIRECTED BY THE AIRPORT.
- m. THE CONTRACTOR SHALL INSTALL AND MAINTAIN A HEAVY-DUTY PADLOCK ON THE ACCESS GATE. HE SHALL PROVIDE KEYS FOR THIS PADLOCK TO THE RESIDENT ENGINEER AND AIRPORT. NO ADDITIONAL KEYS ARE TO BE DISTRIBUTED UNLESS AUTHORIZED BY THE AIRPORT.
- n. THE CONTRACTOR SHALL PROVIDE A SIGN AT ALL ACCESS GATES STATING " AUTHORIZED PERSONNEL ONLY." ALL COSTS RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR

20. AIRPORT SECURITY REQUIREMENTS (CONT'D)

- O. THE AIRPORT OPERATOR HAS A PROGRAM IN WHICH THE CONTRACTOR HAS THE ABILITY TO HAVE PERSONNEL APPROVED TO ACQUIRE ACCESS TO THE AIR OPERATIONS AREA (AOA) WITHOUT DRIVING PRIVILEGES FOR PURPOSES OF THIS CONTRACT. THOSE PERSON(S) HAVING ACCESS MUST SUCCESSFULLY COMPLETE SECURITY TRAINING AND PROVIDE PROPER DOCUMENTATION AS REQUIRED BY THE AIRPORT. PERSON(S) WITH ACCESS PRIVILEGES MUST SUCCESSFULLY COMPLETE THE NECESSARY SECURITY TRAINING IN ORDER THAT THEY CAN ESCORT ADDITIONAL WORKERS LIMITED TO HAVING ONLY CONTROLLED ACCESS PRIVILEGES
- p. THE TRANSPORTATION SECURITY ADMINISTRATION (TSA)
 REQUIRED A TEMPORARY MODIFICATION TO THE AIRPORT
 SECURITY PLAN, KNOWN AS A CHANGE OF CONDITION PLAN
 (CCP) AND THE CONTRACTOR AND MAJOR
 SUBCONTRACTORS WILL BE REQUIRED TO SIGN THE PLAN
 INDICATING THEIR COMPLIANCE WITH THE SECURITY
 REQUIREMENTS SPECIFIED IN THE CCP. A MANDATORY
 SAFETY BRIEFING WILL BE HELD AT THE PUBLIC SAFETY
 FACILITY PRIOR TO THE START OF THE PROJECT.



icense No. 184-000613

NSULTANTS

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL

ARK	DATE	DESCRIPTION

AIP PROJ. NO: 3-17-0096-XX IL. PROJ. NO: SPI-4755

CA021

CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-GC000.DWG

DESIGNED BY: HWI

RLV

DESIGNED BY: HWI
DRAWN BY: DPA
CHECKED BY: MJD


APPROVED BY:

SHEET TITLE

CONSTRUCTION ACTIVITY PLAN NOTES 2


GC002

6 оғ 95



BEAM BARRICADE NOTES


- BARRICADE SHALL BE WEIGHTED TO WITHSTAND DISPLACEMENT BY WIND, JET OR PROP BLAST.
- BARRICADE MUST BE OF LOW MASS AND EASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT.
- NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM. COSTS SHALL BE CONSIDERED INCIDENTAL TO THE
- 4. PLACE AS SHOWN IN PLANS AND AS DIRECTED BY THE
- 5. BARRICADES SHALL BE COMPLIANT WITH FAA AC 150/5370-2 (LATEST VERSION)




LIGHTED RUNWAY CLOSURE MARKER

LIGHTED RUNWAY CLOSURE MARKER NOTES

- TO BE PLACED ON PAVEMENT AT THE RUNWAY NUMERALS FOR NIGHTTIME CLOSURE.
- THE CONTRACTOR SHALL PROVIDE FOUR CLOSURE MARKERS (2 PAIR) AND MAINTAIN THEM (FUEL, OIL, LIGHT BULBS) WHEN USED DURING CONSTRUCTION CLOSURES.
- NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM. COSTS ASSOCIATED WITH PROVIDING AND MAINTAINING THIS ITEM SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.




CLOSED TAXIWAY/ACTIVE RUNWAY BARRICADE DETAIL 3



CLOSED TAXIWAY/ACTIVE TAXIWAY BARRICADE DETAIL 4

NIGHT WORK RUNWAY CLOSURE NOTES


- WORK WITHIN THE RUNWAY SAFETY AREA MAY NOT BEGIN UNTIL THE RUNWAY HAS BEEN CLOSED, NAVAIDS DISABLED, EDGE LIGHTING, CENTERLINE LIGHTING, AND TDZ LIGHTING DISABLED IN THE VALUET AND THE LIGHTED CLOSURE MARKERS ARE IN PLACE
- UPON COMPLETION OF WORK IN NIGHTTIME OFF-PEAK CLOSURE, NO EXCAVATIONS OR STOCKPILES SHALL EXIST IN EXCESS OF 3" AND ALL GRADES SHALL MEET FAA REQUIREMENTS, BARRICADES AND CLOSURE MARKERS SHALL BE REMOVED. AIRPORT OPERATIONS WILL INSPECT RUNWAY AT 4:30 AM.
- SEE SECTION 80 OF THE SPECIFICATIONS FOR INFORMATION REGARDING LIQUIDATED DAMAGES AND REOPENING THE
- PRIOR TO REOPENING THE RUNWAY. THE CONTRACTOR SHALL SWEEP THE PAVEMENT AND REMOVE DEBRIS WITHIN THE RUNWAY SAFETY AREA.



EQUIPMENT & VEHICLE SIGNAL FLAG

SIGNAL FLAG NOTES

- 1. ALL CONTRACTOR VEHICLES AND EQUIPMENT SHALL DISPLAY COMPANY LOGO PLACARDS AND FLAG.
- WHEN WORKING PRIOR TO DAWN OR AFTER DUSK, A 360 DEGREE ROTATING AMBER BEACON IS REQUIRED ON ALL EQUIPMENT AND TRUCKS.
- CONTRACTOR SHALL REPLACE FLAGS THAT ARE WORN AND INEFFECTIVE.



•			
DIMENSION SYMBOL TYPE	Α	В	С
CLOSED TAXIWAY	5'-0"	12'-6"	30'-0"
CLOSED RUNWAY	10'-0"	25'-0"	60'-0"

NON-LIGHTED CLOSURE MARKER

NOTES

6

- 1. CLOSURE MARKERS SHALL BE SOLID YELLOW.
- 2. MARKERS SHALL BE PLACED ON TAXIWAYS AT THE RUNWAY INTERSECTIONS INSIDE THE RUNWAY SAFETY
- 3. MARKERS SHALL BE PLACED ON RUNWAYS TO COVER THE NUMERALS ON BOTH ENDS.
- 4. MARKERS MAY BE CONSTRUCTED OF FABRIC, COLORED PLASTIC, PAINTED SHEETS OF PLYWOOD OR SIMILAR MATERIALS.
- MARKERS SHALL BE SECURED TO PREVENT MOVEMENT BY PROP WASH, JET BLAST OR OTHER WIND CURRENTS. METHODS OF SECURING THE MARKERS SHALL NOT PROTRUDE MORE THAN 3" ABOVE THE PAVEMENT.

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1


SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II


MARK DATE DESCRIPTION CA021 .. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-GC000.DWG DESIGNED BY: HWI RAWN BY: DPA MJD CHECKED BY: APPROVED BY: RLV


CONSTRUCTION **ACTIVITY PLAN DETAILS**


GC003

95









PAVEMENT STATUS TABLE

TAXIWAY CLOSURE MARKER

CONTRACTOR'S ACCESS ROUTE

PAVEMENT	PHASE 3
RUNWAY 18/36	CLOSED
RUNWAY 4/22	CLOSED
RUNWAY 13/31	CLOSED
TAXIWAY A	CLOSED SOUTH OF RWY 13/31
TAXIWAY B	CLOSED WEST OF RWY 4/22
TAXIWAY C	CLOSED SOUTH OF TXY H
TAXIWAY E	CLOSED NORTH OF TXY G
TAXIWAY G	OPEN
TAXIWAY H	CLOSED
TAXIWAYY	CLOSED WEST OF TXY C

- 4. PHASE 3 IS AN EXPEDITED WORK AREA AND SHALL RECEIVE PRIORITY OVER ALL OTHER WORK AREAS
- 5. THE CONTRACTOR SHALL CONTINUOUSLY CLEAN THIS PAVEMENT AREA DURING HAULING OPERATIONS AND AT THE END OF THE WORKDAY.
- 6. AIRCRAFT & AIRPORT VEHICLES SHALL HAVE THE RIGHT OF WAY AT ALL TIMES.
- 7. THE CONTRACTOR SHALL PROVIDE A FLAGMAN / RADIO OPERATOR FOR THIS PHASE TO MONITOR AND MAINTAIN RADIO CONTACT WITH AIR TRAFFIC AND THE AIR TRAFFIC CONTROL TOWER (ATCT) AND CONTROL CONTRACTOR OPERATIONS AT ALL TIMES.
- 8. IT IS ANTICIPATED THAT THE AIR TRAFFIC CONTROL TOWER (ATCT) WILL BE CLOSED AT NIGHT REQUIRING THE CONTRACTOR'S FLAGMAN / RADIO OPERATOR TO MONITOR THE COMMON TRAFFIC ADVISORY FREQUENCY (CTAF) FOR AIRCRAFT TRANSMISSIONS
- 9. THE IMPACTS OF THIS PHASE MERIT ADDITIONAL CONSIDERATION FROM THE CONTRACTOR WHEN SCHEDULING THIS WORK. AS A RESULT, THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE SUFFICIENT PERSONEL AND EQUIPMENT AND WORK SUFFICIENT HOURS THE COMPLETE THIS PHASE WITHIN THE REQUIRED PARAMETERS.
- 10. RUNWAY 13/31 SHALL BE CLOSED AT 11:00 PM AND REOPENED BY 5:00 AM ON A DAILY BASIS.
- 11. RUNWAY 4/22 SHALL REMAIN CLOSED THROUGHOUT THIS PHASE.
- 12. THE CONTRACTOR WILL BE ALLOWED TO CLOSE THE RUNWAY 4/22 AND RUNWAY 13/31 INTERSECTION FOR NO MORE THAN 30 NON-CONSECUTIVE NIGHTS TO PERFORM THE WORK WITHIN THIS
- 13. THE CONTRACTOR SHALL COORDINATE CLOSELY WITH THE AIRPORT TO SCHEDULE THE CLOSURE. VARIABLES SUCH AS THE EXTENDED WEATHER FORECAST, MATERIAL AVAILABILITY, EQUIPMENT AVAILABILITY & CONDITION AND WORKFORCE AVAILABILITY SHALL BE DISCUSSED PRIOR TO SCHEDULING EACH CRITICAL CLOSURE.

- THE FOLLOWING REQUIREMENTS WITHIN 250' OF THE RUNWAY 4/22 AND RUNWAY 13/31 CENTERLINES:
- A. CLEARED AND GRADED AND HAVE NO POTENTIALLY HAZARDOUS RUTS, HUMPS, DEPRESSIONS OR OTHER SURFACE VARIATIONS.
- B. DRAINED BY GRADING OR STORM SEWERS TO PREVENT WATER ACCUMULATION.
- C. CAPABLE, UNDER DRY CONDITIONS, OF SUPPORTING AIRPORT MAINTENANCE EQUIPMENT, AIRCRAFT RESCUE AND FIRE FIGHTING (ARFF) EQUIPMENT, AND THE OCCASIONAL PASSAGE OF AIRCRAFT WITHOUT CAUSING DAMAGE TO THE AIRCRAFT.
- D. FREE OF OBJECTS HIGHER THAN THREE INCHES ABOVE GRADE INCLUDING SOIL MOUNDS, SURFACE IRREGULARITIES OR CONSTRUCTION MATERIALS.
- E. OPEN TRENCHES OR EXCAVATIONS MUST BE BACKFILLED BEFORE THE RUNWAY IS REOPENED. IF BACKFILLING TRENCHES OR EXCAVATIONS IS IMPRACTICAL, THE EXCAVATIONS MUST BE COVERED TO ALLOW THE SAFE OPERATION OF THE HEAVIEST AIRCRAFT OPERATING ON THE RUNWAY ACROSS THE TRENCH WITHOUT DAMAGE
- F. GRADING PARALLEL TO THE RUNWAY 13/31 CENTERLINE (LONGITUDINAL) SHALL NOT EXCEED 1.50%.
- G. GRADING CHANGES PARALLEL TO THE RUNWAY 13/31 CENTERLINE (LONGITUDINAL) SHALL NOT BE STEEPER THAN 80 HORIZONTAL TO 1
- H. GRADING PERPENDICULAR TO THE RUNWAY 13/31 CENTERLINE (TRANSVERSE) SHALL BE SMOOTHLY GRADED AND NOT EXCEED 3%.
- 16. EQUIPMENT STORAGE OR MATERIAL STOCKPILES WILL NOT BE ALLOWED WITHIN 400' OF THE RUNWAY 13/31 CENTERLINE.

- RUNWAY 13/31 TO REOPEN EACH MORNING IN ACCORDANCE WITH THE GRADING CRITERIA ABOVE
- D. CONSTRUCT TURFING AND EROSION CONTROL.
- 18. THE SUGGESTED GENERAL SEQUENCE OF WORK FOR THIS PHASE IS:
- A. IMPLEMENT DAILY RUNWAY CLOSURES AS REQUIRED.
- B. PERFORM TOPSOIL STRIPPING THROUGHOUT THE WORK AREA.
- C. REMOVE THE RUNWAY 18/36 PAVEMENT WHILE SIMULTANEOUSLY DEGRADING THE EXCAVATED AREAS TO MAINTAIN REQUIRED CONSTRUCTION GRADING.
- D. PERFORM REMAINDER OF REQUIRED GRADING IN A MANNER WHICH WILL ALLOW THE DAILY OPENING OF RUNWAY 13/31. THE MANNER OF GRADING MAY REQUIRE THAT THE WORK BE PHASED VERTICALLY IN LIEU OF HORIZONTALLY (I.E. - THE MATERIAL IS EXCAVATED IN THINNER LAYERS OVER A LARGER WORK AREA INSTEAD OF MASS EXCAVATION IN A LIMITED AREA.).
- E. CONSTRUCT THE STORM SEWER IMPROVEMENTS AT THE
- F. COMPLETE THE SPECIFIED GRADING AND DRAINAGE.
- G. COMPLETE THE SPECIFIED TURFING AND EROSION CONTROL.



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II

MARK	DATE	DESCRIPTION		_
AIP P	ROJ. NO	: 3-17-0096-XX	CA	02
IL. PROJ. NO: SPI-4755				
CMT PROJECT NO: 180035-05				_


CAD DWG FILE: 18003505-PH1-GC100.DWG DESIGNED BY: HWI CHECKED BY:


CONSTRUCTION **ACTIVITY PLAN -**PHASE 3

GC104

95

11





PAVEMENT LEGEND

	ID	THICK	MATERIAL	ITEM
		5 "	НМА	401/201
	Α	8.5 "	CRACK AND SEAT PCC	501
		7 "	GRANULAR BLANKET	154
	В	5 "	HMA	401/201
		15 "	CRACK AND SEAT PCC	501
		6 "	AGG BASE	208
		7 "	GRANULAR BLANKET	154
	С	4 "	HMA	402/201
		8 "	CRACK AND SEAT PCC	501
		7 "	GRANULAR BLANKET	154
		11 "	PCC	501
	D	2.5 "	HMA	501
	ט	18.5 "	PCC	501
		7 "	GRANULAR BLANKET	154
		4 "	HMA	401
	E	8 "	CRACK AND SEAT PCC	501
		7 "	GRANULAR BLANKET	154
		5 "	HMA	401
	F	8 "	CRACK AND SEAT PCC	501
		7 "	GRANULAR BLANKET	154

ID	THICK	MATERIAL	ITEM
	8 "	PCC	501
	1 "	HMA	401
G	15 "	PCC	501
	6"	AGG BASE	208
	7 "	GRANULAR BLANKET	154
	5 "	HMA	401
н	8 "	CRACK AND SEAT PCC	501
	7 "	GRANULAR BLANKET	154
	8 "	HMA	401/201
1	8 "	PCC	501
	7 "	GRANULAR BLANKET	154
	11 "	HMA	401/201
J	8 "	CRACK AND SEAT PCC	501
	7 "	GRANULAR BLANKET	154
	8 "	HMA	401/201
K	8 "	PCC	501
	7 "	GRANULAR BLANKET	154
	5 "	HMA	401
L	8 "	CRACK AND SEAT PCC	501
	7 "	GRANULAR BLANKET	154

ID	THICK	MATERIAL	ITEM
	18 "	НМА	401/201
М	4 "	AGG BASE	209
	12 "	LIME MODIFIED SUBGRA	155
	5 "	HMA	401
N	8 "	CRACK AND SEAT PCC	501
	7 "	GRANULAR BLANKET	154
	6 "	PCC	501
0	1 "	HMA	201
١٠	9 "	CRACK AND SEAT PCC	501
	7 "	GRANULAR BLANKET	154
Р	18.5 "	PCC	501
	7 "	GRANULAR BLANKET	154
Q	18.5 "	PCC	501
<u> </u>	7 "	GRANULAR BLANKET	154
	16 "	PCC	501
R	4 "	AGG BASE	209
	8 "	LIME MODIFIED SUBGRA	155
	16 "	PCC	501
S	4 "	AGG BASE	209
	8 "	LIME MODIFIED SUBGRA	155

ID	THICK	MATERIAL	ITEM
Т	6 "	HMA	401/403
I	6 "	AGG BASE	209
U	7 "	HMA	401/201
	8 "	PCC	501
	7 "	GRANULAR BLANKET	154
	7 "	HMA	401/201
٧	10 "	PCC	501
W	10 "	PCC	501
Х	13 "	PCC	501
V	10 "	PCC	501
Υ	4 "	AGG BASE	209
Z	6 "	PCC	501
AA	10 "	PCC	501
A Β	13 "	PCC	501
	4 "	AGG BASE	209
AC	6"	HMA	401/403
AU	12 "	AGG BASE	209

PAVEMENT STRUCTURES SHOWN WERE TAKEN FROM RECORD DRAWINGS AND ARE CONSIDERED GENERALLY REPRESENTATIVE OF THE "AS CONSTRUCTED" PAVEMENT SECTION WITH SOME VARIABILITY FROM THE THICKNESS INDICATED TO BE EXPECTED. THERE WILL BE NO ADDITIONAL PAYMENT TO THE CONTRACTOR DUE TO VARIATIONS IN SIZE OR QUANTITY OF EXISTING FEATURES.

SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL

AIRPORT SPRINGFIELD, IL

JUNE 29, 2020


PHASE 1


MARK DATE DESCRIPTION


CAXXX IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CD003.DWG DESIGNED BY: HWI RAWN BY: DPA MJD CHECKED BY: APPROVED BY:


EXISTING PAVEMENT STRUCTURES


CD001 SHEET 13 95


































License No. 184-0006



THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL


MARK DATE DESCRIPTION


IP PROJ. NO: 3-17-	-0096-XX	CA021
. PROJ. NO: SPI-47	755	
MT PROJECT NO:	180035-05	
AD DWG FILE:	18003505-PH1-CP100.DWG	
ESIGNED BY:	HWI	
RAWN BY:	DPA	
HECKED BY:	MJD	
PPROVED BY:	RLV	


HEET TITLE


HORIZONTAL CONTROL


CP100 SHEET 25 OF 95
















License No. 184-0006

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNE



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL

MADE DATE DESCRIPTION

MARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755

CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-CP300.DWG

DESIGNED BY: HWI

DESIGNED BY: HWI
DRAWN BY: DPA
CHECKED BY: MJD

APPROVED BY: RLV
COPYRIGHT:

TYPICAL SECTION


CP301


_{SHEET} 31


OF


CA021


Path: K:\SpringlieldAp\18035-05_Hwy_18-36\Draw\Sheets\PHASE 1\18003505-PH1-CP3
Date: Thursday, June 25, 2020 6:49:51 PM























TYPE C DOWELED CONTRACTION SYMBOL

TYPE A THICKENED ISOLATION

TYPE B HINGED (TIED) CONTRACTION SYMBOL


TABLE 2 DOWEL BAR DETAILS TIE BAR DETAILS THICKNESS LENGTH SPACING BAR SIZE LENGTH SPACING DIA. T - INCHES 12" O.C 30" O.C. 3/4" 18" 12" O.C. 30" 30" O.C. 19" 12" O.C. 30" 30" O.C. #5 19" 12" O.C #5 30" 30" O.C. 12" O.C. 10 19" #5 30" 30" O.C. 19" 12" O.C. 30" O.C. 11 #5 30" 12 19" 12" O.C. 30" 30" O.C. 13 1 - 1/4" 20" 15" O.C. 30" 30" O.C. 14 20" 15" O.C. 30" O.C. 1 - 1/4" #5 30" 15 1 - 1/4" 20" 15" O.C. 30" 30" O.C. 16 1 - 1/4" 20" 15" O.C. 30" 30" O.C. #5 17 1 - 1/2" 20" 18" O.C. #5 30" 30" O.C.

18" O.C.


20"

1 - 1/2'


18



TYPE D DUMMY CONTRACTION SYMBOL - D




TYPE E DOWELED CONSTRUCTION



ODD SHAPED PANEL REINFORCEMENT SYMBOL R

NOTES:

ODD SHAPED PANELS INCLUDE ALL PANELS THAT



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II


MARK DATE DESCRIPTION


AIP PROJ. NO: 3-17-	AIP PROJ. NO: 3-17-0096-XX			
IL. PROJ. NO: SPI-47	755			
CMT PROJECT NO:	180035-05			
CAD DWG FILE:	18003505-PH1-CJ500.DWG			
DESIGNED BY:	HWI			
DRAWN BY:	DPA			
CHECKED BY:	MJD			
APPROVED BY:	RLV			
COPYRIGHT:				

PAVING DETAILS 2

CJ502

- 1.) ALL EDGES OF NEW SLABS, FREE STANDING OR CLOSURE, SHALL BE EDGED WITH AN APPROVED TOOL HAVING A RADIUS OF 1/8" TO 1/4" TO FACILITATE SAWING OF THE SEALANT RESERVOIR. A RADIUS > 1/4' WILL NOT BE ACCEPTABLE.
- 2.) THE INITIAL SAWCUT FOR ALL LONGITUDINAL & TRANSVERSE CONTRACTION JOINTS SHALL BE SAWED AS SOON AS POSSIBLE AFTER PLACEMENT OF THE PAVEMENT.
- 3.) ALL TIE BARS & MESH SHALL BE SECURELY HELD IN PLACE BY SUPPORT PINS OR OTHER APPROVED METHODS TO PREVENT SHIFTING DURING & AFTER CONCRETE PLACEMENT.
- 4.) TIE BARS SHALL BE DEFORMED BARS IN CONFORMANCE WITH THE SPECIFICATIONS.
- THE INITIAL SAWCUT SHALL BE MADE TO THE 1/8" WIDTH INDICATED. INITIAL SAWING TO THE DIMENSIONS OF THE SECOND SAWCUT WILL NOT BE





JOINT SEALING DETAILS

JOINT SEALING DIMENSIONS DETAIL 1 DETAIL 2 DETAIL: SEALANT 3/4 1/2 RESERVOIR D=DEPTH OF SEALANT 3/8 1/4 RESERVOIR B=BACKER ROD N/A 5/8 DIAMETER S=SECOND SAWCUT N/A 1-1/8 MINIMUM

1/2

1/4

5/8

1-1/8

SYMBOL

JOINT NOTES

30" O.C.


30"


DETAIL 3


37


EXCEED LENGTH TO WIDTH RATIO OF 1.25


95












N.T.S.

TYPICAL PAVEMENT REMOVAL SECTION



SUBGRADE REPAIR NOTES

- 1. THE REMOVAL AREA AND DEPTH SHALL BE DETERMINED AT THE TIME OF CONSTRUCTION BY THE RPR.
- 2. THE FOLLOWING SHALL BE THE STEPS TAKEN TO REPAIR THE SUBGRADE:
 - A. REMOVE SOIL SUBGRADE TO THE DEPTH SPECIFIED BY THE RPR.

 - B. COMPACT THE SUBGRADE TO THE SATISFACTION OF THE RPR.
 C. PLACE SEPARATION GEOTEXTILE FABRIC ON TOP OF THE
 COMPACTED SUBGRADE AND ALONG THE SIDES OF THE
 - D. PLACE AND CONSOLIDATE GRANULAR SUBBASE TO THE SATISFACTION OF THE RPR.
- 3. THE FOLLOWING SHALL BE CONSIDERED INCIDENTAL TO THE SUBGRADE REPAIR PAY ITEM:
 A. SUBGRADE REMOVAL
 B. SUBGRADE COMPACTION

 - C. SUBBASE GRANULAR
- 4. GEOTEXTILE FABRIC SHALL BE PAID UNDER ITEM AR209600.

NCMT

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS,

PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL

MARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-CG301.DWG DESIGNED BY: HWI


MJD CHECKED BY: APPROVED BY: COPYRIGHT:


GRADING DETAILS


CG301

SHEET 43

CA021







PIPE SCHEDULE STORM SEWER A							
PIPE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	INVERT	INVERT	LENGTH (FT)	SLOPE	TYPE
A-1	IN A-1	EIN 2-4	582.37	581.60	244	0.30%	CONCRETE PIPE - 12"
A-2	IN A-2	IN A-1	583.45	582.60	270	0.30%	CONCRETE PIPE - 12"

STRUCTURE TABLE STORM SEWER A						
STRUCTURE NAME AND TYPE	STRUCTURE DETAILS	HORIZONTAL CONTROL				
EIN 2-4 EXISTING INLET	RIM = 586.44 SUMP = 581.36 A-1 INV IN = 581.60	TAXIWAY A STA 36+06.50 OFFSET 115.22 R				
IN A-1 36" INLET	RIM = 587.50 SUMP = 581.37 A-2 INV IN = 582.60 A-1 INV OUT = 582.37	TAXIWAY A STA 33+51.00 OFFSET 105.52 R				
IN A-2 36" INLET	RIM = 587.00 SUMP = 582.45 A-2 INV OUT = 583.45	TAXIWAY A STA 30+68.56 OFFSET 105.50 R				

STRUCTURE TABLE STORM SEWER H						
STRUCTURE NAME AND TYPE	STRUCTURE DETAILS	HORIZONTAL CONTROL				
EIN 1-8 EXISTING INLET	RIM = 583.51 SUMP = 579.16 H-1 INV IN = 579.50	TAXIWAY H STA 16+42.54 OFFSET -284.97 L				
IN H-1 36" INLET	RIM = 586.14 SUMP = 579.60 H-2 INV IN = 580.80 H-1 INV OUT = 580.60	TAXIWAY H STA 19+38.84 OFFSET -71.37 L				
IN H-2 36" INLET	RIM = 585.52 SUMP = 580.24 H-2 INV OUT = 581.24	TAXIWAY H STA 19+78.65 OFFSET 68.48 R				

PIPE SCHEDULE STORM SEWER H							
PIPE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	INVERT	INVERT	LENGTH (FT)	SLOPE	TYPE
H-1	IN H-1	EIN 1-8	580.60	579.50	353	0.30%	CONCRETE PIPE - 12"
H-2	IN H-2	IN H-1	581.24	580.80	133	0.30%	CONCRETE PIPE - 12"

PIPE SCHEDULE STORM SEWER Y							
PIPE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	INVERT	INVERT	LENGTH (FT)	SLOPE	TYPE
Y-1	IN Y-2	MH Y-1	584.06	582.30	164	1.00%	CONCRETE PIPE - 12"
Y-2	IN Y-1	MH Y-1	582.67	582.30	25	1.00%	CONCRETE PIPE - 12"


STRUCTURE TABLE STORM SEWER Y					
STRUCTURE NAME AND TYPE	STRUCTURE DETAILS	HORIZONTAL CONTROL			
IN Y-1 36" INLET	RIM = 585.40 SUMP = 581.67 Y-2 INV OUT = 582.67	TAXIWAY Y STA 7+85.99 OFFSET 100.54 R			
IN Y-2 36" INLET	RIM = 586.94 SUMP = 583.06 Y-1 INV OUT = 584.06	TAXIWAY Y STA 8+01.51 OFFSET -94.99 L			
MH Y-1 48" MANHOLE	RIM = 588.20 SUMP = 581.30 Y-2 INV IN = 582.30 Y-1 INV IN = 582.30	TAXIWAY Y STA 8+17.31 OFFSET 80.00 R			

PIPE SCHEDULE STORM SEWER 422							
PIPE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	INVERT	INVERT	LENGTH (FT)	SLOPE	TYPE
422-3	IN 422-3	IN 422-1	584.18	583.70	149	0.30%	CONCRETE PIPE - 12"
422-1	IN 422-1	EIN 3-4	583.49	582.90	186	0.30%	CONCRETE PIPE - 24"
422-2	IN 422-2	IN 422-1	584.39	583.70	217	0.30%	CONCRETE PIPE - 15"

STRUCTURE TABLE STORM SEWER 422						
STRUCTURE NAME AND TYPE	STRUCTURE DETAILS	HORIZONTAL CONTROL				
EIN 3-4 EXISTING INLET	RIM = 588.40 SUMP = 581.90 422-1 INV IN = 582.90	RUNWAY 4-22 STA 148+43.58 OFFSET -138.13 L				
IN 422-1 36" INLET	RIM = 587.19 SUMP = 583.49 422-2 INV IN = 583.70 422-3 INV IN = 583.70 422-1 INV OUT = 583.49	RUNWAY 4-22 STA 146+99.46 OFFSET -274.32 L				
IN 422-2 36" INLET	RIM = 586.72 SUMP = 584.39 422-2 INV OUT = 584.39	RUNWAY 4-22 STA 144+71.04 OFFSET -264.56 L				
IN 422-3 36" INLET	RIM = 587.04 SUMP = 583.18 422-3 INV OUT = 584.18	RUNWAY 4-22 STA 146+92.63 OFFSET -435.55 L				

EIN = EXISTING INLET IN = INLET - NEW MH = MANHOLE - NEW





THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL


MARK DATE DESCRIPTION

CA021 AIP PROJ. NO: 3-17-0096-XX IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CU100.DWG DESIGNED BY: HWI DRAWN BY: CHECKED BY: APPROVED BY: RLV COPYRIGHT:

STORM SEWER SCHEDULES

CU103

SHEET 46 OF



	UNDERDRAIN SCHEDULE								
STRUCTURE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	UPSTREAM INVERT	DOWNSTREAM INVERT	LENGTH (FT)	SLOPE (%)	TYPE		
UD-1	CO1	CS1	591.50	588.42	306.59	1.00%	PERFORATED		
UD-2	CS1	IN Y-3	584.92	581.90	56.61	5.33%	NON-PERFORATED		
UD-3	CO2	CS1	585.31	584.92	159.84	0.24%	PERFORATED		
UD-4	CO3	CS2	588.09	585.88	287.11	0.77%	PERFORATED		
UD-5	CS2	IN Y-2	585.88	583.06	68.59	4.11%	NON-PERFORATED		
UD-6	CO4	CS2	586.29	585.88	165.21	0.25%	PERFORATED		
UD-42	CO26	CS13	584.68	584.15	249.17	0.21%	PERFORATED		
UD-43	CO27	CS14	584.98	584.31	249.17	0.27%	PERFORATED		
UD-46	CO28	CS15	587.01	585.66	217.50	0.62%	PERFORATED		
UD-47	CO28	CS16	587.01	585.50	217.50	0.69%	PERFORATED		
UD-49	CO29	CO2	586.06	585.31	209.90	0.36%	PERFORATED		
UD-50	CO30	CO29	588.10	586.06	217.50	0.94%	PERFORATED		
UD-51	CO30	CS17	588.10	585.20	217.50	1.33%	PERFOR A TED		



icense No. 184-000613

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL

MARK DATE DESCRIPTION

MARK DATE DESCRIPTION

AIP PROJ. NO: 3-17-0096-XX

IL. PROJ. NO: SPI-4755

CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-CU100.DWG

DESIGNED BY: HWI

DRAWN BY: DPA

CHECKED BY: MJD

CA021

APPROVED BY: RLV
COPYRIGHT:


SHEET TITLE


UNDERDRAIN SCHEDULES


CU104


SHEET 47 OF 95


CSX - COLLECTION STRUCTURE COX - CLEAN OUT











LEGEND PROPOSED GROUND SURFACE - - - EXISTING GROUND SURFACE

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1




SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL


MARK DATE DESCRIPTION AIP PROJ. NO: 3-17-0096-XX IL. PROJ. NO: SPI-4755


CA021 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CU200.DWG DESIGNED BY: HWI DPA MJD CHECKED BY: APPROVED BY: RLV COPYRIGHT:

STORM SEWER **PROFILES**

> CU201 95







UNDERDRAIN COLLECTION STRUCTURE

SIDE VIEW

UNDERDRAIN CLEAN-OUT TYPE 1




RUNWAY 18/36 REMOVAL AND

SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT**

CA021 L. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CU500.DWG DESIGNED BY: HWI DPA MJD CHECKED BY: APPROVED BY: RLV

UNDERDRAIN **DETAILS**

> CU501 49 95



UNDERDRAIN DIRECT CONNECTION TO STRUCTURE

1'-6" FINISHED GROUND (PAVEMENT OR TURF) 10" ITEM P-610 P.C.C. 4" NON-PERFORATED (2)-#4 BARS TOP & BOTTOM CONNECT TO 4" UNDERDRAIN

UNDERDRAIN CLEAN-OUT TYPE 2

ITEM P-610 P.C.C. AS REQUIRED

GROUT BASE TO PROVIDE SMOOTH FLOWLINE AND PROVIDE WATERTIGHT SEAL AT PIPE **PLAN** CONNECTIONS WITH WATER SEALING GROUT

FINISHED GROUND (PAVEMENT OR TURF) 10" ITEM P-610 P.C.C. (2)-#4 BARS **TOP & BOTTOM** CONNECT TO 4" UNDERDRAI 4" NON-PERFORATED PVC PIPE

SLOPE FROM PERIMETER
WITH WATER SEALING GROUT

NEW 4" UNDERDRAIN

UNDERDRAIN CLEAN-OUT TYPE 3

FINISHED GROUND

(PAVEMENT OR TURF)

ITEM P-610 P.C.C.

4" NON-PERFORATED

(2)-#4 BARS TOP & BOTTOM

PVC PIPE

PLAN UNDERDRAIN CLEAN-OUT 5

#4 BARS

TOP & BOTTOM

6 3/4"

CAST IRON FRAME & COVER (SIMILAR TO NEENAH R-6013 OR


FRAME & LID


CONNECT TO 4" UNDERDRAIN


JUNE 29, 2020


ASSOCIATED IMPROVEMENTS, PHASE 1

SPRINGFIELD, I











STORM SEWER


CU502

95


DETAILS 1








TOP REINFORCEMENT 3





DESIGN CRITERIA

2000 PSI LOADING WATER TABLE AT TOP OF INLET NET ALLOWABLE SOIL BEARING PRESSURE =

GENERAL NOTES

- 1. THE INLET GRATE SHALL BE SUPPORTED ON ALL FOUR SIDES.
- 2. ALL REINFORCEMENT BARS SHALL CONFORM TO ASTM A615 GRADE 60 AND SHALL BE CLEAN AND FREE OF GREASE, SCALING RUST AND OTHER FOREIGN MATERIALS.
- INLET MAY BE CONSTRUCTED BY CAST-IN-PLACE CONCRETE OR PRECAST CONCRETE. PRECAST CONCRETE INLETS SHALL BE CONSTRUCTED TO THE LINES, DIMENSIONS AND DETAILS SHOWN ON
- 4. CAST-IN-PLACE CONCRETE AND PRECAST CONCRETE FOR THE INLETS SHALL BE IN ACCORDANCE WITH P-610.
- 5. ALL FOOTING EXCAVATIONS SHALL BE CLEAN FREE OF DEBRIS. STANDING WATER AND LOOSE SOIL AND SHALL BE INSPECTED BY THE ENGINEER PRIOR TO THE PLACEMENT OF CONCRETE OR
- 6. CONCRETE SHALL NOT BE PLACED OVER FROZEN OR MUDDY SOIL.
- ADDITIONAL REINFORCEMENT FOR PIPE PENETRATIONS NOT REQUIRED FOR 4" DIA. PIPES OR LESS.



JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1


SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL


MARK DATE DESCRIPTION

CA021 .. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CU500.DWG DESIGNED BY: HWI DPA MJD CHECKED BY: APPROVED BY: RLV


STORM SEWER **DETAILS 2**


CU503 SHEET 51 95






MANHOLE DETAIL










EL103

CA021







LIGHT TABLE TAXIWAY H

I AXIWAY H						
FIXTURE #	FIXTURE TYPE	HORIZONTAL CONTROL				
TWY H - L1	MITL (LED)	TAXIWAY H STA 6+74.90 OFFSET -48.86 L				
TWY H - L2	MITL (LED)	TAXIWAY H STA 6+88.43 OFFSET -38.84 L				
TWY H - L3	MITL (LED)	TAXIWAY H STA 7+04.89 OFFSET -35.27 L				
TWY H - L4	MITL (LED)	TAXIWAY H STA 7+61.34 OFFSET -35.20 L				
TWY H - L5	MITL (LED)	TAXIWAY H STA 7+99.28 OFFSET -36.03 L				
TWY H - L6	MITL (LED)	TAXIWAY H STA 8+37.61 OFFSET -44.89 L				
TWY H - L7	MITL (LED)	TAXIWAY H STA 9+17.51 OFFSET -37.90 L				
TWY H - L8	MITL (LED)	TAXIWAY H STA 9+56.58 OFFSET -33.25 L				
TWY H - L9	MITL (LED)	TAXIWAY H STA 10+62.45 OFFSET -34.26 L				
TWY H - L10	MITL (LED)	TAXIWAY H STA 11+12.45 OFFSET -34.26 L				
TWY H - L11	MITL (LED)	TAXIWAY H STA 11+62.45 OFFSET -34.26 L				
TWY H - L12	MITL (LED)	TAXIWAY H STA 13+64.53 OFFSET -44.92 L				
TWY H - L13	MITL (LED)	TAXIWAY H STA 13+86.82 OFFSET -35.00 L				
TWY H - L14	MITL (LED)	TAXIWAY H STA 15+59.17 OFFSET -35.00 L				
TWY H - L15	MITL (LED)	TAXIWAY H STA 17+31.51 OFFSET -35.00 L				
TWY H - L16	MITL (LED)	TAXIWAY H STA 19+03.85 OFFSET -35.00 L				
TWY H - L17	MITL (LED)	TAXIWAY H STA 20+76.19 OFFSET -35.00 L				
TWY H - L18	MITL (LED)	TAXIWAY H STA 22+48.53 OFFSET -35.00 L				
TWY H - L19	MITL (LED)	TAXIWAY H STA 24+20.87 OFFSET -35.00 L				
TWY H - L20	MITL (LED)	TAXIWAY H STA 25+93.22 OFFSET -35.00 L				
TWY H - L21	MITL (LED)	TAXIWAY H STA 26+21.66 OFFSET -47.77 L				
TWY H - L22	MITL (LED)	TAXIWAY H STA 27+73.57 OFFSET 55.77 R				
TWY H - L23	MITL (LED)	TAXIWAY H STA 27+30.99 OFFSET 48.85 R				

LIGHT TABLE

TAXIWAY H							
FIXTURE TYPE	HORIZONTAL CONTROL						
MITL (LED)	TAXIWAY H STA 26+88.42 OFFSET 41.92 R						
MITL (LED)	TAXIWAY H STA 26+45.84 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 25+93.22 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 24+20.87 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 22+48.53 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 20+76.19 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 19+03.85 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 17+31.51 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 15+59.17 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 13+86.82 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 12+97.40 OFFSET 35.00 R						
MITL (LED)	TAXIWAY H STA 12+57.97 OFFSET 39.78 R						
MITL (LED)	TAXIWAY H STA 12+20.83 OFFSET 53.84 R						
MITL (LED)	TAXIWAY H STA 10+34.14 OFFSET 44.38 R						
MITL (LED)	TAXIWAY H STA 10+13.70 OFFSET 36.47 R						
MITL (LED)	TAXIWAY H STA 9+56.92 OFFSET 36.75 R						
MITL (LED)	TAXIWAY H STA 9+08.70 OFFSET 31.88 R						
MITL (LED)	TAXIWAY H STA 8+67.09 OFFSET 17.60 R						
MITL (LED)	TAXIWAY H STA 8+30.64 OFFSET 29.78 R						
MITL (LED)	TAXIWAY H STA 7+61.34 OFFSET 34.80 R						
MITL (LED)	TAXIWAY H STA 7+06.39 OFFSET 34.73 R						
MITL (LED)	TAXIWAY H STA 6+91.31 OFFSET 37.66 R						
MITL (LED)	TAXIWAY H STA 6+78.44 OFFSET 46.06 R						
	FIXTURE TYPE MITL (LED) MITL (LED)						

LIGHT TABLE TAXIWAY Y

FIXTURE #	FIXTURE TYPE	HORIZONTAL CONTROL
TWY Y - L1	MITL (LED)	TAXIWAY Y STA 4+68.9 OFFSET 57.03 R
TWY Y - L2	MITL (LED)	TAXIWAY Y STA 4+93.0 OFFSET 54.27 R
TWY Y - L3	MITL (LED)	TAXIWAY Y STA 5+17.19 OFFSET 51.51 R
TWY Y - L4	MITL (LED)	TAXIWAY Y STA 5+66.5 OFFSET 45.85 R
TWY Y - L5	MITL (LED)	TAXIWAY Y STA 6+15.9 OFFSET 40.19 R
TWY Y - L6	MITL (LED)	TAXIWAY Y STA 6+72.9 OFFSET 40.00 R
TWY Y - L7	MITL (LED)	TAXIWAY Y STA 7+18.4 OFFSET 46.36 R
TWY Y - L8	MITL (LED)	TAXIWAY Y STA 7+62.59 OFFSET 52.72 R
TWY Y - L9	MITL (LED)	TAXIWAY Y STA 7+96.89 OFFSET 57.65 R
TWY Y - L10	MITL (LED)	TAXIWAY Y STA 8+31.19 OFFSET 62.59 R
TWY Y - L11	MITL (LED)	TAXIWAY Y STA 8+34.99 OFFSET 97.07 R
TWY Y - L12	MITL (LED)	TAXIWAY Y STA 8+38.7 OFFSET 131.54 R

LIGHT TABLE TAXIWAY Y

FIXTURE #	FIXTURE TYPE	HORIZONTAL CONTROL
TWY Y - L13	MITL (LED)	TAXIWAY Y STA 4+79.26 OFFSET -56.73 L
TWY Y - L14	MITL (LED)	TAXIWAY Y STA 5+01.10 OFFSET -54.06 L
TWY Y - L15	MITL (LED)	TAXIWAY Y STA 5+22.94 OFFSET -51.38 L
TWY Y - L16	MITL (LED)	TAXIWAY Y STA 5+69.42 OFFSET -45.69 L
TWY Y - L17	MITL (LED)	TAXIWAY Y STA 6+15.90 OFFSET -40.00 L
TWY Y - L18	MITL (LED)	TAXIWAY Y STA 6+72.91 OFFSET -40.00 L
TWY Y - L19	MITL (LED)	TAXIWAY Y STA 7+20.65 OFFSET -46.45 L
TWY Y - L20	MITL (LED)	TAXIWAY Y STA 7+68.38 OFFSET -52.90 L
TWY Y - L21	MITL (LED)	TAXIWAY Y STA 8+05.20 OFFSET -57.87 L
TWY Y - L22	MITL (LED)	TAXIWAY Y STA 8+42.03 OFFSET -62.85 L
TWY Y - L23	MITL (LED)	TAXIWAY Y STA 8+51.69 OFFSET -94.72 L
TWY Y - L24	MITL (LED)	TAXIWAY Y STA 8+61.35 OFFSET -126.60 L

LIGHT TABLE **RUNWAY 4-22**

FIXTURE #	FIXTURE TYPE	HORIZONTAL CONTROL
RWY 4-22 - L1	FMRL	RUNWAY 4-22 STA 144+50.56 OFFSET -84.21 L
RWY 4-22 - L2	FMRL	RUNWAY 4-22 STA 142+50.64 OFFSET 85.59 R

LIGHT TABLE

RUNWAY 13-31			
FIXTURE #	FIXTURE TYPE	HORIZONTAL CONTROL	
RWY 13-31 - L1	FMRL	RUNWAY 13-31 STA 244+15.43 OFFSET -85.09 L	
RWY 13-31 - L2	FMRL	RUNWAY 13-31 STA 246+10.82 OFFSET 85.14 R	

LIGHT TABLE ΤΔΧΙΜΑΥ Δ

IANIWAYA		
FIXTURE #	FIXTURE TYPE	HORIZONTAL CONTROL
TWY A - L1	MITL (LED)	TAXIWAY A STA 32+13.99 OFFSET -48.03 L
TWY A - L2	MITL (LED)	TAXIWAY A STA 33+94.34 OFFSET -48.03 L
TWY A - L3	MITL (LED)	TAXIWAY A STA 32+13.99 OFFSET 47.00 R
TWY A - L4	MITL (LED)	TAXIWAY A STA 33+94.34 OFFSET 47.03 R



THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL

MARK DATE DESCRIPTION

CA021 AIP PROJ. NO: 3-17-0096-XX IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-EL400.DWG DESIGNED BY: HWI DRAWN BY: MJD CHECKED BY: APPROVED BY: RLV

COPYRIGHT:

LIGHTING SCHEDULE

EL 401

GUIDANCE SIGN SCHEDULE

NOT

CONTRACTOR SHALL CONFIRM OUTPUT OF EXISTING REGULATORS (6.6A OR 20A) PRIOR TO ORDERING EQUIPMENT.



icense No. 184-000613

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL

MARK	DATE	DESCRIPTION


AIP PROJ. NO: 3-17-	-0096-XX	CA02
IL. PROJ. NO: SPI-47	755	
CMT PROJECT NO:	180035-05	
CAD DWG FILE:	18003505-PH1-EL400.DWG	
DESIGNED BY:	HWI	
DRAWN BY:	DPA	
CHECKED BY:	MJD	
APPROVED BY:	RLV	
COPYRIGHT:		

SHEET TITLE

SHEET **59**

SIGNAGE SCHEDULE

EL402 _{OF} 95



CIRCUIT DESIGNATION (AIRPORT WILL PROVIDE CIRCUIT NUMBER) ď LIGHT DESIGNATION LIGHT IDENTIFICATION TAG

3/16" DIA

3/8" STEEL COVER WITH GASKET, BOLTED TO BASE L-867 BASE, (TYP.) CLASS I, 12" DIA., 30" MIN. DEPTH **GROUNDING LUG** ITEM P-610 P.C.C. CONCRETE #6 BARE COPPER CONDUCTOR TO GROUND LUG **EXOTHERMIC** SEAL END OF WFI D CONDUIT TO 1" WEEP HOLE MAKE WATER SAND BACKFILL TIGHT (TYP.) UNDISTURBED EARTH 2'-0" DIA. ROUND 3/4" x 10' COPPER CLAD GROUND ROD

SPLICE CAN

RUNWAY 18/36 REMOVAL AND

MIN. 18" BELOW GRADE

JUNE 29, 2020

ASSOCIATED IMPROVEMENTS, PHASE 1


SPRINGFIELD AIRPORT

AUTHORITY

ABRAHAM LINCOLN CAPITAL

AIRPORT

SPRINGFIELD, II



LOCATION OF COUNTERPOISE (DUCT BANK)

LAYER 3 BACKFILL RESTORATION PER SPEC. 108

6 0.049 CIT YD CONCRETE PER MARKER

MANHOLES.

MIN.

A MARKER CONFORMING TO THIS DETAIL

MARKED "SPLICE" SHALL BE INSTALLED AT ALL SPLICE LOCATIONS NOT IN LIGHT CANS OR

MOUND SLIGHTLY,


GRADE AND SEED

BACKFILL RESTORATION PER SPEC. 108 LAYER 2 LAYER 2 LAYER 1 LAYER 1 EARTH OR SAND BACKFILL PER FARTH OR SAND SPFC, 108 BACKFILL PER SPEC. 108

CABLE TRENCH DETAIL

LIGHT IDENTIFICATION NOTES

- INSTALL A NON-CORROSIVE DISC OF 2" MINIMUM DIAMETER WITH THE NUMBER PERMANENTLY STAMPED, CUT OUT, OR ENGRAVED UNDER THE HEAD OF THE BASE PLATE BOLT OR ATTACHED TO LIGHT FLANGE WITH SET SCREW.
- LEGENDS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. CONTRACTOR TO COORDINATE LEGEND WITH
- THE CONTRACTOR SHALL NUMBER THE EXISTING/ PROPOSED LIGHTS AND SIGNS IN EACH CIRCUIT STARTING AT THE HOMERUN CONTINUING AROUND THE ENTIRE CIRCUIT BACK TO THE HOMERUN.
- 4. AIRFIELD SIGNS SHALL BE TAGGED & NUMBERED.



COUNTERPOISE LOCATION DETAIL

CABLE TRENCH NOTES

CABLES SHALL NOT BE PLACED LESS THAN 24" DEEP IN ANY ONE TRENCH JNLESS PERMITTED BY ENGINEER.

DIRECT BURY CABLE OR

CABLE IN UNIT DUCT

DUCT MARKERS SHALL BE INSTALLED AT BOTH

EDGES OF PAVEMENT WHERE PROPOSED

FXISTING PAVEMENTS

1/4" RADIUS TOOL.

MOUND SLIGHTLY,

GRADE AND SEED

3. ITEM 610 CONCRETE SHALL BE USED.

ELECTRICAL DUCTS CROSS BOTH NEW AND

CABLE MARKERS SHALL BE INSTALLED AT ALL

4. ALL EXPOSED EDGES SHALL BE EDGED WITH A

THE COST OF FURNISHING AND INSTALLING

NEW MARKERS SHALL BE INCIDENTAL TO THE ASSOCIATED ITEMS.

MIN.

LAYER 3

GRADE

BENDS AND EVERY 200' ALONG THE HOMERUN.

WHERE PERMITTED, CONTRACTOR MAY INSTALL CABLE IN UNIT DUCT BY PLOWING METHOD.

CABLE TRENCH NOTES

#6 BARE COUNTERPOISE WITH 3/4" x 10' GROUND BOD INSTALLED AT MAX 500' SPACING ALSO LISE GROUND ROD TO TERMINATE THE COUNTERPOISE AT BOTH ENDS OF DUCT. GROUND RODS SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS.

COUNTERPOISE NOTES

- THE HEIGHT ABOVE THE CABLE AND/OR CONDUIT IS CALCULATED TO ENSURE THE CABLES AND/OR CONDUITS TO BE PROTECTED ARE WITHIN THE 459 ZONE OF PROTECTION BELOW THE COUNTERPOISE
- COUNTERPOISE WIRES MUST BE INSTALLED ABOVE MULTIPLE CONDUITS/DUCT BANKS FOR AIREFIELD LIGHTING CABLES, WITH THE INTENT BEING TO PROVIDE A COMPLETE CONE OF PROTECTION OVER THE AIRFIELD LIGHTING CABLES. WHEN MULTIPLE CONDUITS AND/OR DUCT BANKS FOR AIRFIELD CABLE ARE INSTALLED IN THE SAME TRENCH, THE NIMBER AND LOCATION OF THE COLINTERPOISE WIRES ABOVE THE CONDUITS SHALL BE ADEQUATE TO PROVIDE A COMPLETE ZONE OF PROTECTION MEASURED 22-1 /2°EACH SIDE OF VERTICAL.
- REFER TO THE CURRENT VERSIONS OF FAA AC 150/5340-30 AND AC 150/5370-10 FOR MORE DETAILS ON COUNTERPOISE INSTALLATION.


MARK DATE DESCRIPTION			
AIP PROJ. NO: 3-17-	-0096-XX	CA021	
IL. PROJ. NO: SPI-4755			
CMT PROJECT NO:	180035-05		
CAD DWG FILE:	18003505-PH1-EL500.DWG		
DESIGNED BY:	HWI		
DRAWN BY:	DPA		
CHECKED BY:	MJD		
APPROVED BY:	RLV		
COPYRIGHT:			


MARK DATE DESCRIPTION

ELECTRICAL DETAILS

EL501 60

95






ELEVATED RETRO-REFLECTIVE MARKER

RETRO-REFLECTIVE MARKER NOTES

RETROREFLECTIVE MARKER SHALL MET FAA AC 150/5345-39D AIRFIELD LIGHTING EQUIPMENT CERTIFICATION PROGRAM



IN-PAVEMENT EDGE LIGHT DETAIL

- IN-PAVEMENT LIGHT DETAIL NOTES:

 1. LIGHT BASES SHALL BE INSTALLED WITH CARE TO ASSURE VERTICAL & AZIMUTH ALIGNMENT OF FIXTURE. SEE PAVEMENT OR CAN DETAIL FOR CONCRETE
- 2. PROVIDE 3' CABLE SLACK WITHIN LIGHT BASE TO ALLOW TRANSFORMER
- BOLTS AND WASHERS USED DURING INSTALLATION OF BASE, CABLE AND TRANSFORMERS SHALL BE REPLACED WITH NEW FOR FINAL BASE IS 0.5".
- 4. AS REQUIRED TO MAINTAIN +0/-1/16" BELOW GRADE FAA INSTALLATION TOLERANCE. A MAXIMUM OF THREE SPACER RINGS MAY BE STACKED TOGETHER.

IN-PAVEMENT EDGE LIGHT NOTES

- 1. THE LIGHT FIXTURE SHALL BE BONDED TO THE LIGHT BASE INTERNAL GROUND LUG VIA A #6 AWG STRANDED COPPER WIRE. RATED FOR 600 VOLTS WITH GREEN XHHW INSULATION. THE GROUND WIRE LENGTH SHALL BE SUFFICIENT TO ALLOW THE REMOVAL OF THE LIGHT FIXTURE FROM THE LIGHT BASE FOR BOUTINE MAINTENANCE SEE THE LIGHT FIXTURE MANUFACTURER'S INSTRUCTIONS FOR PROPER METHODS OF ATTACHING THIS BONDING WIRE.
- 2. LIGHT FIXTURES SHALL BE L-861, L-861E, AS INDICATED ON THE PLANS AND SPECIFICATIONS. ALL NEW LIGHTS SHALL BE LED.
- 3. L-830 ISOLATION TRANSFORMERS FOR LED EDGE LIGHTS WITH ARCTIC KITS SHALL BE L-830-1 30/45 WATT.
- 4. THE TOLERANCE FOR THE HEIGHT OF RUNWAY/TAXIWAY EDGE LIGHTS MUST BE ± 1 INCH. THE TOLERANCE FOR THE LATERAL SPACING (LIGHT LANE TO RUNWAY/TAXIWAY CENTERLINE) OF RUNWAY/TAXIWAY EDGE LIGHTS MUST BE ± 1 INCH.

- DIRECTION OF PRIMARY CABLES MUST BE IDENTIFIED BY COLOR CODING AS FOLLOWS: WHEN FACING LIGHT WITH BACK FACING PAVEMENT, CABLE TO THE LEFT IS CODED RED AND CABLE TO THE RIGHT IS CODED BLUE.
- 6. APPLY A CORROSION INHIBITING, ANTI-SEIZE COMPOUND TO ALL SCREWS, NUTS AND FRANGIBLE COUPLING THREADS. IF COATED BOLTS ARE USED PER ENGINEERING BRIEF #83, DO NOT APPLY ANTI-SEIZE COMPOUND.
- 7. ELECTRICAL INSULATING GREASE MUST BE APPLIED WITHIN THE L-830 ISOLATION TRANSFORMER SECONDARY TWO CONDUCTOR CONNECTORS TO PREVENT WATER ENTRANCE. THE CONNECTORS MUST NOT BE TAPED.
- 8. ENTRANCES IN L-867 BASES MUST BE PLUGGED FROM THE INSIDE WITH DUCT SEAL TO MAKE WATERTIGHT.
- 9. EDGE LIGHTS SHALL BE LOCATED NO MORE THAN 10' AND NO LESS THAN 2' FROM THE EXISTING PAVEMENT EDGE, IN A STRAIGHT LINE.



JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II


MARK DATE DESCRIPTION

CA021 .. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-EL500.DWG DESIGNED BY: HWI DPA MJD CHECKED BY: APPROVED BY: COPYRIGHT

ELECTRICAL DETAILS

EL502 95


61




DUCT BANK NOTES

- 1. DIMENSIONS SHOWN ARE MINIMUM.
- 2. TOP OF CONCRETE ENCASEMENT SHALL BE NOT LESS THAN 24" BELOW FINISHED SUBGRADE BELOW PAVEMENTS AND NOT LESS THAN 24" BELOW FINISHED GRADE IN UNPAVED AREAS, EXCEPT WHERE DIRECTED OTHERWISE BY ENGINEER. AVOID ALL CONFLICTS WITH OTHER UTILITIES (UNDERDRAINS, WATER LINES, SEWER LINES, TELEPHONE, ELECTRICAL) OR OTHER OBSTACLES, ADJUSTING DEPTH AS NECESSARY.
- 3. CONCRETE SHALL BE ITEM P-610.
- 4. CONDUIT FOR CONCRETE ENCASEMENT SHALL BE SCHEDULE 40 PVC, 4" NOMINAL DIAMETER, OR AS INDICATED ON THE PLANS.
- 5. CONCRETE ENCASEMENT SHALL EXTEND A MINIMUM OF 5'-0" BEYOND EDGES OF PAVEMENT, OR AS SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER
- 6. #4 REBAR SHALL BE INSTALLED CONTINUOUS THE LENGTH OF THE CONCRETE ENCASEMENT

- 7. DUCT BANK SHALL BE STACKED NO MORE THAN THREE CONDUITS HIGH UNLESS DIRECTED OTHERWISE BY THE
- 8. AT ENDS OF DUCT BANKS, INSTALL A PVC COUPLING FLUSH WITH END OF CONCRETE FOR CONNECTING FUTURE CONDUIT, INSTALL POLYETHELENE PULL STRING. GREENLEE, OR EQUIVALENT. PLUG THE ENDS OF UNUSED
- 9. HIGH VOI TAGE WIRING, BUNWAY & TAXIWAY SERIES CIRCUIT WIRING, ETC., AND POWER WIRING OVER 480V SHALL BE INSTALLED IN SEPARATE CONDUITS FROM LOW VOLTAGE WIRING, 480V OR LESS.
- 10.IF POSSIBLE, INSTALL FIBER OPTIC CABLES AND COMMUNICATION CABLES (FAA, ETC.) IN THEIR OWN CONDUITS; OTHERWISE, INSTALL THEM IN THE CONDUITS WITH LOW VOLTAGE WIRING.
- 11. DEPTH AS REQUIRED TO NOT IMPACT EDGE DRAIN.





JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II

MARK DATE DESCRIPTION

CA021 .. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-EL500.DWG DESIGNED BY: HWI DPA MJD CHECKED BY: APPROVED BY:

COPYRIGHT


ELECTRICAL DETAILS


95

EL503 62

MATCH THE OUTSIDE DIAMETER OF CABLE INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY


WRAP WITH AT LEAST ONE LAYER OF RUBBER OR TAPE, ONE-HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF JOINT.







- 2. SIGN LEGEND SHALL BE AS SHOWN IN THE PLANS. SIGN SCHEDULE IS SUBJECT TO FAA APPROVAL OF THE SIGNAGE PLAN. CHANGES TO NEW LEGENDS MAY OCCUR
- 3. SIGN ANCHOR TETHERS AND GROUND WIRES ARE REQUIRED, SEE SPECIFICATIONS.
- 5. LIGHT I.D. TAG FOR SIGN SHALL INCLUDE SIGN DESIGNATOR SHOWN IN THE PLAN
- 6. DIRECTION OF PRIMARY CABLES MUST BE IDENTIFIED BY COLOR CODING AS



- STANDARDS AND MAY NOT REFLECT THE ACTUAL GRADES IN THE FIELD
- 2. ESTIMATED 1 C.Y. OF EMBANKMENT MAY BE REQUIRED TO CONSTRUCT SIGN BASE FOUNDATION. COSTS TO CONSTRUCT SHALL BE INCIDENTAL TO SIGN PAY ITEM.
- 3. ACTUAL LOCATION OF THE SIGN WITHIN THE TAXIWAY SAFETY AREA WILL VARY DUE TO PAVEMENT WIDTHS AND VARIANCES IN SIGN FOUNDATION LENGTHS.
- 4. 4" OF KNITTED STRAW MAT SHALL BE PLACED AROUND THE PROTECTION APRON. COST FOR MAT SHALL BE INCIDENTAL TO SIGN PAY ITEM.

#6 BARE COPPER

1/4" BOLT


GROUND WIRE

GROUND WIRE CLAMP

GROUND STAMP

VEGA 0919

5/16" BOLT



ELEVATION VIEW

MOUNTED SIGN BASE DETAIL

L-823 PLUG FLANGIBLE FURNISHED WITH SIGN COUPLING FLOOR FLANGE CABLE CLAMP TOP OF 2" CONDUIT TO BE FLUSH WITH TOP SURFACE OF JUMPER CABLE

CONCRETE MOUNTING PAD

STYLE 7, TYPE 2, CLASS A

L-823 CONNECTOR

FACTORY GROUND LUG DETAIL

SIDE OF L-867

OR L-860 BASE CAN

ELECTRICAL CONNECTION 5

FIGURE 1

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II

MARK DATE DESCRIPTION CA021 .. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-EL500.DWG DESIGNED BY: HWI DPA MJD CHECKED BY: APPROVED BY: RLV


COPYRIGHT


ELECTRICAL DETAILS


EL504 HEET 63 95




- TRANSFORMER WATTAGE SHALL BE AS REQUIRED BY SIGN MANUFACTURER. SIGNS ON RUNWAY CIRCUITS SHALL BE STYLE 2 OR 3 DEPENDING ON REGULATOR.
- 4. SIGNS SHALL BE SIZE 2, STYLE 2 OR 3, CLASS 2, AND MODE 2. SEE SIGN SCHEDULE
- FOLLOWS: WHEN FACING SIGN IN BACK FACING THE RELATED RUNWAY OR TAXIWAY PAVEMENT, THE CABLE FOR THE CIRCUIT TO THE LEFT IS CODED RED AND CABLE FOR THE CIRCUIT TO THE RIGHT IS CODED BLUE.










OBSCURE RUNWAY DESIGNATION

NUMERALS SHALL BE COMPLETELY COVERED AND INVISIBLE

NOTE:

NEW 6" YELLOW LINE TAXIWAY EDGE MARKING



NCMT


JUNE 29, 2020


RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

> SPRINGFIELD AIRPORT **AUTHORITY**

ABRAHAM LINCOLN CAPITAL

AIRPORT SPRINGFIELD, IL





EDGE OF PAVEMENT FRANGIBLE BASE INSTALL IN CONCRETE PER MANUFACTURER'S INSTRUCTIONS

ROADWAY SIGN PLACEMENT

MARK DATE DESCRIPTION L. PROJ. NO: SPI-4755

CA021 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CM500.DWG DESIGNED BY: DPA MJD CHECKED BY: APPROVED BY:


PAVEMENT MARKING **& SIGNAGE DETAILS**


CM502


1. NEW L-858 UNLIGHTED NO ENTRY SIGN SHALL BE SIZE 2 AND DIMENSIONED PER FAA AC 150/5345-44 (CURRENT.)


TAXI GUIDANCE SIGN, UNLIT DETAIL


PLAN VIEW















PERSPECTIVE VIEW




SILT FENCE NOTES

- 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES
- 2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 2'-0" AT TOP AND MID SECTION.
- 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY 6" MINIMUM AND FOLDED.
- 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE. MAINTENANCE, WHICH INCLUDES THE REPLACEMENT OF DAMAGED FENCE SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE EROSION CONTROL FENCE.



INLET PROTECTION WITH FABRIC



INLET PROTECTION WITH STRAW BALES



JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL

MARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-LG501.DWG DESIGNED BY: HWI

DPA MJD CHECKED BY:

APPROVED BY: COPYRIGHT:


EROSION CONTROL DETAILS

LG501

SHEET **72**

CA021








RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

JUNE 29, 2020



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL




CA021 L. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY: CHECKED BY:


SHEET **74**


COPYRIGHT


CROSS SECTIONS -RWY 18-36 REMOVALS


CG701

























RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL



MARK DATE DESCRIPTION


IL. PROJ. NO: SPI-4755			
CMT PROJECT NO:	180035-05		
CAD DWG FILE:	18003505-PH1-CG700 RWY XSEC.DWG		
DESIGNED BY:	HWI		
DRAWN BY:	DPA		
CHECKED BY:	MJD		


CA021


COPYRIGHT:


CROSS SECTIONS -RWY 18-36 REMOVALS


CG702 знеет **75**

























CONSULTANTS


JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL



AIP PROJ. NO: 3-17-0096-XX

IL. PROJ. NO: SPI-4755

CMT PROJECT NO: 180035-05

CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG

DESIGNED BY: HWI

DRAWN BY: DPA

CHECKED BY: MJD


CA021


COPYRIGHT:


CROSS SECTIONS -RWY 18-36 REMOVALS


CG703


SHEET 76 OF





























RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL

CA021

MARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755


CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY: CHECKED BY:

COPYRIGHT

CROSS SECTIONS -RWY 18-36 REMOVALS

CG704







RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL



CA021 IL. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY:


CHECKED BY:


COPYRIGHT:


CROSS SECTIONS -RWY 18-36 REMOVALS


CG705


SHEET 78













RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

JUNE 29, 2020



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II

MARK DATE DESCRIPTION


IL. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY: CHECKED BY:


CA021


COPYRIGHT


CROSS SECTIONS -RWY 18-36 REMOVALS


CG706 SHEET 79






















JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL

MARK DATE DESCRIPTION

ARK DATE DESCRIPTION


AIP PROJ. NO: 3-17-0096-XX


APPROVED BY COPYRIGHT:

CROSS SECTIONS -RWY 18-36 REMOVALS

CG707
SHEET 80 OF

Path: Ki:SpringfieldApi18035-05_Rwy.18-36/Draw/Sheets/IPHASE 1/18003505-PH1-CG700 FWY XSEC.dwg Date: Thursday, June 25, 2020 7/03:41 PM








RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II





CA021 L. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY: CHECKED BY:


CROSS SECTIONS -RWY 18-36 REMOVALS


> CG708 81


CUT = 218 SF FILL = 10 SF

























NSULTANTS

JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL

MARK DATE DESCRIPTION

IARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755

CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG

DESIGNED BY: HWI

CA021

DRAWN BY: DPA
CHECKED BY: MJD
APPROVED BY: RLV

COPYRIGHT:

SHEET TITLE

CROSS SECTIONS -RWY 18-36 REMOVALS


CG709


Path: K:SpringfieldApt18035-05_RWv_18-36\Draw!Sheets\PHASE 1118003505-PH1-CG700 RWY XSEC.dwg


9


OF


SHEET **82**













RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL

CA021

MARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755


CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY:

CHECKED BY:

COPYRIGHT

CROSS SECTIONS -RWY 18-36 REMOVALS

CG710 SHEET 83






RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL




MARK DATE DESCRIPTION


CA021 IL. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY: CHECKED BY:

COPYRIGHT

CROSS SECTIONS -RWY 18-36 REMOVALS

CG711





140 120 100 80 60 40 20 **0** 20 40 60 80 100 120 140

PAVEMENT

REMOVAL

591

590

589

588

EXISTING 1

GROUND

PROPOSED GROUND

UT = 11 SF


 \perp FILL = 120 SF

591

590

589

587




590


589


587


359


50













RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II

CA021

MARK DATE DESCRIPTION

L. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG


DESIGNED BY:


CHECKED BY:


COPYRIGHT


CROSS SECTIONS -RWY 18-36 REMOVALS


CG712 SHEET 85




























RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL


IARK	DATE	DES	CRIPTION			
AIP PROJ. NO: 3-17-0096-XX CA021						
L. PROJ. NO: SPI-4755						
CMT PROJECT NO: 1			180035-05			
CAD DWG FILE:			18003505-PH1-CG700 RWY XSEC.DWG			
DESIGNED BY:			HWI			

MJD

CHECKED BY: COPYRIGHT

CROSS SECTIONS -RWY 18-36 REMOVALS

CG713 SHEET 86






RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1




SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, IL





CA021 L. PROJ. NO: SPI-4755 CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG DESIGNED BY: CHECKED BY:


CROSS SECTIONS -TXY E REMOVALS 1


CG714 SHEET 87













JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL

CA021

MARK DATE DESCRIPTION

MARK DATE DESCRIPTION

III. PROJ. NO: SPI-4755

CMT PROJECT NO: 180035-05

CAD DWG FILE: 18003505-PH1-CG700 RWY XSEC.DWG

DESIGNED BY: HWI


CHECKED BY: MJI


COPYRIGHT:


SHEET TITLE

CROSS SECTIONS -TXY E REMOVALS 2


CG715 SHEET 88 OF 9












3\$0 360 340 320 300 280 260 240 220 200 180 160 140 120 100 80 60 40 20 0 20 40 60





CROSS SECTIONS -

TXY E REMOVALS 3

SHEET 89

CG716


CA021


JUNE 29, 2020


RUNWAY 18/36 REMOVAL AND

ASSOCIATED IMPROVEMENTS,

PHASE 1









CONSULTANTS


JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1

OWNER



SPRINGFIELD AIRPORT
AUTHORITY
ABRAHAM LINCOLN CAPITAL
AIRPORT
SPRINGFIELD, IL




MARK DATE DESCRIPTION


AIP PROJ. NO: 3-17-	0096-XX CA021		
IL. PROJ. NO: SPI-4755			
CMT PROJECT NO:	180035-05		
CAD DWG FILE:	18003505-PH1-CG700 RWY XSEC.DWG		
DESIGNED BY:	HWI		
DRAWN BY:	DPA		
CHECKED BY:	MJD		


APPROVED BY: COPYRIGHT:


CROSS SECTIONS - TXY E REMOVALS 4


CG717 SHEET 90 OF 9




















RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT **AUTHORITY** ABRAHAM LINCOLN CAPITAL **AIRPORT** SPRINGFIELD, II


MARK DATE DESCRIPTION

CA021 L. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CG800 TXYXSEC.DWG DESIGNED BY: CHECKED BY:

COPYRIGHT

CROSS SECTIONS -TAXIWAY A 1

CG801





RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL

MARK DATE DESCRIPTION

AIP PROJ. NO: 3-17-0096-XX

IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CG800 TXYXSEC.DWG DESIGNED BY: HWI DRAWN BY:


CA021


CHECKED BY: APPROVED BY: RLV

COPYRIGHT:

CROSS SECTIONS -TAXIWAY A 2

CG802 SHEET **93**








589 589 588 588 587 587 586


120 100 80 60 40 20 **0** 20 40 60 80 100 120

CUT = 171 SF FILL = 275 SF 50


585




CUT = 171 SF FILL = 275 SF 00



CUT = 171 SF FILL = 275 SF





CUT = 171 SF FILL = 275 SF JUNE 29, 2020

RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1




SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL

MARK DATE DESCRIPTION

CA021 IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CG800 TXYXSEC.DWG DESIGNED BY: HWI CHECKED BY: APPROVED BY: COPYRIGHT:

CROSS SECTIONS -TAXIWAY H

CG803 SHEET 94





RUNWAY 18/36 REMOVAL AND ASSOCIATED IMPROVEMENTS, PHASE 1



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, IL

CA021

MARK DATE DESCRIPTION

IL. PROJ. NO: SPI-4755 CMT PROJECT NO: 180035-05 CAD DWG FILE: 18003505-PH1-CG800 TXYXSEC.DWG


DESIGNED BY: HWI

CHECKED BY: APPROVED BY:

COPYRIGHT:

CROSS SECTIONS -TAXIWAY Y

CG804 SHEET **95**



CUT = 171 SF FILL = 275 SF

