LETTING ITEM NUMBER

03A

LETTING DATE

JULY 31, 2020


WILLIAMSON COUNTY AIRPORT AUTHORITY **VETERANS AIRPORT OF SOUTHERN ILLINOIS**

INDEX OF SHEETS


- COVER 1.
- SCOPE OF WORK 2.
- SAFETY AND PHASING PLAN PH 1 3.
- SAFETY AND PHASING PLAN PH 1A 4.
- SAFETY AND PHASING PLAN PH 2 5.
- CONCRETE SLAB REPLACEMENT PLAN 6.
- SPOT ELEVATION SHEET 7.
- JOINT REHABILITATION AND PAVEMENT 8.


MARKINGS PLAN

CONSTRUCTION PLANS TERMINAL RAMP REHABILITATION



DATE: JUNE 5, 2020 A.I.P. NO.: 3-17-0065-XXXX ILLINOIS PROJECT NO.: MWA-4829





PLANS PREPARED

15

BOARD MEMBERS

CHAIRMAN: BENARD A. PAUL

MEMBERS: JAVIER MUNIZ MICHAEL TROOP RANDY YOUNGBLOOD JOHN O'KEEFE

SECRETARY: **ROBERT MEES**

AIRPORT DIRECTOR: DOUGLAS KIMMEL



EXPIRES : NOVEMBER 30, 2021



PROJECT 19203

LETTING CONTRACT NUMBER

WI058

TOTAL SHEETS: 8


| FEDERAL | FUNDS |
|---------|-------|
| ITEM | |


| TEM NO. | DESCRIPTION | UNIT | EST. QYT. | AS BUILT QTY. |
|------------|-----------------------------|------|-----------|------------------|
| 150510 | ENGINEER'S FIELD OFFICE | L.S. | 1 | |
| 50520 | MOBILIZATION | L.S. | 1 | |
| 150530 | TRAFFIC MAINTENANCE | L.S. | 1 | |
| 501509 | 9" PCC PAVEMENT | S.Y. | 96 | |
| 501515 | 15" PCC PAVEMENT | S.Y. | 402 | |
| 501909 | 9" PCC PAVEMENT REMOVAL | S.Y. | 96 | |
| 501915 | 15" PCC PAVEMENT REMOVAL | S.Y. | 402 | |
| 605540 | CLEAN & SEAL JOINTS | L.F. | 28,500 | |
| 605541 | CLEAN & SEAL CRACKS | L.F. | 225 | |
| 620520 | PAVEMENT MARKING-WATERBORNE | S.F. | 770 | |
| 801358 | SPALL REPAIR | S.F. | 360 | |

| EM O. | DESCRIPTION | UNIT | EST. QYT. | AS BUILT QTY. |
|----------|---------------------|------|-----------|------------------|
| 05540 | CLEAN & SEAL JOINTS | L.F. | 800 | |
| 01358 | SPALL REPAIR | S.F | 1 | |


DUE TO THE ANTICIPATED TIMING OF CONTRACT AWARD AND POTENTIAL FOR INCLEMENT WEATHER, IT IS NOT EXPECTED THAT CONSTRUCTION WILL BEGIN BEFORE APRIL 2021.

| REPARED BY : | |
|--|--|
| CLARIDA & ZIEGLER ENGINEERING COMPANY P.O. Box 937, 410 North Court Street Marion, Illinois 62959 | WILLIAMSON COUNTY AIRPORT AUTHORITY |
| REGISTERED PROFESSIONAL ENGINEER OF ILLINOIS NO. 053881 | APPROVED |
| ITED ENGINEER W. BRIAN ZIEGLER | APPROVED Called FMEEN SECRETARY |
| 06/05/2020 | DATE :06/05/2020 |






| AIRFIELD OPERATIONAL LIMITATIONS | | |
|----------------------------------|----------------------------------|--|
| FACILITY | PHASE 1 | |
| TAXIWAY B | NONE | |
| TAXIWAY B3 | NONE | |
| TAXIWAY D | CLOSED | |
| TERMINAL RAMP | CLOSED EAST OF TERMINAL BUILDING | |



| AIRFIELD OPERATIONAL LIMITATIONS | | |
|----------------------------------|---------------------------------|--|
| FACILITY PHASE 1 | | |
| TAXIWAY B | NONE | |
| TAXIWAY B3 | CLOSED SOUTH OF TAXIWAY B | |
| TAXIWAY D | CLOSED | |
| TERMINAL RAMP | CLOSED (9:00 PM - 6:00 AM, M-F) | |

| PHASE 1 LIMITS |
|--------------------------|
| PHASE 1A LIMITS |
| TAXIWAY PAVEMENT CLOSURE |
| CONTRACTOR STAGING AREA |
| HAUL ROUTE |
| RUNWAY SAFETY AREA |
| TAXIWAY SAFETY AREA |
| RUNWAY OBJECT FREE AREA |
| LOW PROFILE BARRICADE |
| |



- PHASING PLAN.
- AIRCRAFT AND EMERGENCY VEHICLES SHALL HAVE THE RIGHT OF WAY AT ALL TIMES.
- APPROPRIATE NOTAMS (NOTICE TO AIRMEN) WILL BE ISSUED BY THE AIRPORT DIRECTOR. THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 72 HOURS NOTICE PRIOR TO NAVAID OR PAVEMENT CLOSURES.
- THE CONTRACTOR SHALL NOT ALLOW HIS/HER EMPLOYEES, INCLUDING SUBCONTRACTORS AND SUPPLIERS, TO CROSS OR PROCEED ON AN ACTIVE RUNWAY, TAXIWAY, OR CRITICAL/SAFETY AREA WITHOUT PRIOR AUTHORIZATION BY AIRPORT PERSONNEL.
- STOCKPILED MATERIALS AND EQUIPMENT STORAGE ARE NOT PERMITTED WITHIN THE OBJECT FREE AREA (OFA) OF AN ACTIVE RUNWAY OR TAXIWAY.
- THE CONTRACTOR SHALL WORK ONLY WITHIN THE LIMITS SHOWN ON THE PLANS. ALL EQUIPMENT AND PERSONNEL SHALL BE LIMITED TO THE STAGING AREA, DESIGNATED HAUL ROUTES, OR WITHIN THE CONSTRUCTION LIMITS. ALL PERSONAL VEHICLES SHALL BE PARKED OUTSIDE THE PERIMETER FENCE.
- THE CONTRACTOR SHALL REPAIR OR REPLACE ANY DAMAGE TO AIRPORT PROPERTY, TO THE SATISFACTION OF THE AIRPORT, CAUSED BY CONSTRUCTION PERSONNEL OR ACTIVITIES AT HIS/HER OWN EXPENSE.
- THE CONTRACTOR SHALL THOROUGHLY CLEAN ALL CONSTRUCTION AREAS AND PAVEMENTS BEFORE THE COMPLETION OF EACH PHASE TO THE SATISFACTION OF AIRPORT PERSONNEL.
- EXISTING TURF AREAS DISTURBED BY THE CONTRACTORS OPERATIONS SHALL BE RESTORED AT HIS/HER EXPENSE TO THE SATISFACTION OF THE AIRPORT.
- 10. HEIGHT OF CONSTRUCTION EQUIPMENT MAXIMUM IS ANTICIPATED TO BE 25', WHICH IS A RAISED TRUCK BED.

- BARRICADES AS DIRECTED BY THE ENGINEER. THE BARRICADES WILL BE EQUIPPED WITH RED FLASHING LIGHTS. THE BARRICADES, THEIR MAINTENANCE, PLACEMENT AND REMOVAL WILL BE CONSIDERED AS INCIDENTAL TO MAINTENANCE OF TRAFFIC AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 13. IDENTIFICATION WHEN THE CONTRACTOR'S VEHICLES AND EQUIPMENT ARE ON THE AIRPORT THEY SHALL BE PROPERLY MARKED WITH THREE FOOT (3') SQUARE CHECKERED AVIATION FLAGS (INTERNATIONAL ORANGE AND WHITE) OR FLASHING DOME TYPE AMBER COLORED BEACONS VISIBLE FROM THE CONTROL TOWER.
- 14. THE CONTRACTOR SHALL FURNISH AIRPORT RADIOS FOR HIS/HER USE. RADIOS SHALL BE CAPABLE OF MONITORING AND TRANSMITTING OVER THE AIRPORT'S GROUND CONTROL FREQUENCY (121.7 MHZ). THE CONTRACTOR SHALL MONITOR THE GROUND CONTROL FREQUENCY CONTINUOUSLY WHEN THE ATCT IS OPERATIONAL, 7:00 AM TO 7:00 PM. WHEN THE ATCT IS CLOSED THE CONTRACTOR SHALL MONITOR FREQUENCY (128.40).
- 15. CONTRACTOR PERSONNEL OPERATING VEHICLES ON THE AIRFIELD SHALL ATTEND AIRPORT DRIVERS TRAINING CLASS OR BE ESCORTED BY PERSONNEL WHO HAVE COMPLETED TRAINING PRIOR TO BEGINNING OF CONSTRUCTION.
- 16. THE CONTRACTOR SHALL BE ASSIGNED A LIMITED NUMBER OF GATE ACCESS KEYS. THE KEYS SHALL ONLY BE ASSIGNED TO PERSONNEL WHO HAVE COMPLETED THE DRIVERS TRAINING CLASS. KEYS SHALL BE RETURNED TO THE AIRPORT AT THE COMPLETION OF THE PROJECT.
- 17. TAXIWAY LIGHTS WITHIN CLOSED PORTIONS OF PROJECT SHALL BE COVERED. COST TO COVER LIGHTS SHALL BE CONSIDERED AS INCIDENTAL TO MAINTENANCE OF TRAFFIC AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 18. THE CONTRACTOR SHALL PREPARE AND SUBMIT TO THE ENGINEER A SAFETY PLAN COMPLIANCE DOCUMENT (SPCP) PRIOR TO BEGINNING WORK. THE INTENT OF THE SPCD IS TO DOCUMENT HOW THE CONTRACTOR WILL COMPLY WITH CONSTRUCTION SAFETY AND PHASING PLAN (CSPP). SEE CURRENT VERSION OF FAA ADVISORY CIRCULAR (AC) 150/5370-2 FOR ADDITIONAL INFORMATION.


- PHASE 2 CLOSURE DOES NOT NEED TO BE CONTINUOUS AND MAY BE BROKEN UP INTO TWO 2. SEPARATE CLOSURES. THE CONTRACTOR SHALL PROVIDE 72 HOURS NOTICE BEFORE ANY PHASE CLOSURE.
- TAXIWAY B3 AND TERMINAL RAMP LIGHTS AND DIRECTIONAL SIGNS SHALL BE COVERED IN THE CLOSED PORTIONS. COVERS SHALL NOT ALLOW LIGHT TO BE VISIBLE DURING OPERATION. A TOTAL OF 21 LIGHTS AND 4 SIGNS SHALL BE COVERED THIS PHASE.
- THE CONTRACTOR SHALL ENSURE A CLEAR PATH IS AVAILABLE AT ALL TIMES FOR FUEL 4. TRUCKS CROSSING PHASE 2 CONSTRUCTION LIMITS FROM THE GA RAMP TO THE TERMINAL RAMP.
- THE CONTRACTOR SHALL ENSURE A CLEAR PATH FREE FROM FOREIGN OBJECT DEBRIS (FOD) IS AVAILABLE BETWEEN THE TERMINAL AND THE CORPORATE HANGAR AT THE END OF EACH DAYS WORK FOR PLANE STORAGE IN THE CORPORATE HANGAR. COORDINATE LOCATION WITH THE ENGINEER EACH DAY.
- THE CONTRACTOR SHALL ENSURE THE TAXILANE BETWEEN T HANGARS AND CORPORATE HANGAR REMAINS CLEAN, CLEAR, AND FREE OF FOD AT ALL TIMES. AIRCRAFT SHALL HAVE THE RIGHT OF WAY AT ALL TIMES.


LEGEND PHASE 1 LIMITS TAXIWAY PAVEMENT CLOSURE CONTRACTOR STAGING AREA

HAUL ROUTE **RUNWAY SAFETY AREA** TAXIWAY SAFETY AREA RUNWAY OBJECT FREE AREA

LOW PROFILE BARRICADE


| AIRFIELD OPERATIONAL LIMITATIONS | | |
|----------------------------------|--|--|
| FACILITY | PHASE 2 | |
| TAXIWAY B | NONE | |
| TAXIWAY B3 | CLOSED | |
| TAXIWAY D | NONE | |
| TERMINAL RAMP | NORTHWEST CORNER SOUTH OF TAXIWAY B3 CLOSED | |






| SLAB REPLACEMENT TABLE | | | |
|------------------------|-----------------|--------------|------------------------|
| SLAB | L X W | SQUARE YARDS | TYPICAL SECTION |
| 1 | 10' X 3' | 3.33 SYD'S | 9" PCC ON 4" AGGREGATE |
| 2 | 12.5' X 2' X 8' | 6.94 SYD'S | 9" PCC ON 4" AGGREGATE |
| 3 | 30' X 6' | 20.00 SYD'S | 9" PCC ON 4" AGGREGATE |
| 4 | 12.5' X 12.5' | 17.36 SYD'S | 15" PCC ON 9" HMA |
| 5 | 78' X 7.5' | 65.00 SYD'S | 9" PCC ON 4" AGGREGATE |
| 6 | 25' X 2' | 5.56 SYD'S | 15" PCC ON 9" HMA |
| 7 | 12.5' X 2' | 2.78 SYD'S | 15" PCC ON 9" HMA |
| 8 | 12.5' X 2' | 2.78 SYD'S | 15" PCC ON 9" HMA |
| 9 | 20' X 4' | 8.89 SYD'S | 15" PCC ON 9" HMA |
| 10 | 125' X 25' | 347.22 SYD'S | 15" PCC ON 9" HMA |
| 11 | 12.5' X 2' | 2.78 SYD'S | 15" PCC ON 9" HMA |
| 12 | 12.5' X 2' | 2.78 SYD'S | 15" PCC ON 9" HMA |
| 13 | 25' X 2' | 5.56 SYD'S | 15" PCC ON 9" HMA |
| 14 | 25' X 2' | 5.56 SYD'S | 15" PCC ON 9" HMA |

| | STATE OF II | LLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-004515 |
|----------------|-------------|--|
| | REVISIONS | © 2018 ALL RIGHTS RESERVED |
| | DATE NO. | CLARIDA & ZIEGLER |
| | | ENGINEERING CO. |
| | | 410 North Court St, P.O. Box 937 |
| | | Marion, Illinois 62959 |
| | | Phone - (618)993-6411, Fax - (618)993-6750 |
| | | TERMINAL RAMP REHABILITATION |
| ONTRACT NUMBER | | |
| ONTRACT NOMBER | | CONCRETE SLAB REPLACEMENT PLAN |
| WI058 | | Date <u>6/5/20</u> DR. By <u>MKW</u> CK'D By <u>WBZ</u> |
| WIUJO | | Scale <u>1" = 100'</u> Job No. <u>19203</u> Sheet No. <u>6</u> of <u>8</u> |
| | | |



Airport\19203 Terminal Ramp Rehab\Drawings - Plans\06-07 PCC Rehab.dwg 6-05-20 01:44:14 PM



LETTING C

DETAILED NOTES

1. THE ENGINEER SHALL STAKE A CONTROL POINT ELEVATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SETTING PROPOSED SPOT ELEVATION.

| | STATE OF IL | LINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-004515 | |
|-----------------|-------------|---|--|
| | REVISIONS | © 2018 ALL RIGHTS RESERVED | |
| | DATE NO. | CLARIDA & ZIEGLER | |
| | | ENGINEERING CO. | |
| | | | |
| | | 410 North Court St, P.O. Box 937 Marion, Illinois 62959 | |
| | | Phone - (618)993-6411, Fax - (618)993-6750 | |
| | | TERMINAL RAMP REHABILITATION | |
| CONTRACT NUMBER | | | |
| CONTRACT NOMBER | | SPOT ELEVATION SHEET | |
| WI058 | | Date <u>6/5/20</u> DR. By <u>MKW</u> CK'D By <u>WBZ</u> | |
| ¥¥1030 | | Scale <u>1" = 10'</u> Job No. <u>19203</u> Sheet No. <u>7</u> of <u>8</u> | |

