



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 24, 2026

SUBJECT: FAP 360 (Kirk Road)
Section 12-00192-04-BR
Kane County
Contract No. 61M13
Item 019
July 31, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. **Revised the Schedule of Prices**
2. **Revised Plan Sheets 4, 8, 21, 31, 34, 40, 110, 124, 254, 261, 288, 289, 306, 330, 344-350, 364-367, 369, 370, 371, 379, 383-385, 387-389, 405, 406, & 408-411**
3. **Revised Special Provision Index**
4. **Added page 319A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

BARRIER WALL REMOVAL	294
TEMPORARY STORM SEWER (SIZE SPECIFIED).....	295
TEMPORARY END SECTION	296
RECESSED REFLECTIVE PAVEMENT MARKERS (KDOT)	297
RECESSED REFLECTIVE PAVEMENT MARKER REMOVAL (KDOT).....	299
EXPLORATION TRENCH (SPECIAL)	300
GUARDRAIL REFLECTORS, TYPE 1 (GUARDRAIL DELINEATION).....	301
BICYCLE RAILING (SPECIAL)	302
STAINING CONCRETE STRUCTURES	304
FENCE REMOVAL AND REINSTALLATION	306
STAMPED COLORED PORTLAND CEMENT MEDIAN SURFACE 4 INCH (SPECIAL)	307
PAINT CURB	309
HOT-MIX ASPHALT DRIVEWAY, 10"	310
DRAINAGE SCUPPERS DS-11.....	311
ROAD WEATHER INFORMATION SYSTEM, COMPLETE	312
AGGREGATE COLUMN GROUND IMPROVEMENT.....	313
CONTRACTOR RIGHT OF ENTRY AGREEMENT	318
SLEEPER SLAB.....	319
TEMPORARY DRAINAGE SYSTEM NO. 1	319A
UNION PACIFIC RAILROAD RIGHT OF ENTRY AGREEMENT AND INSTRUCTIONS.....	320
IDOT TRAINING PROGRAM GRADUATE ON THE JOB TRAINING	367
LR107-4	369
LR1030-2	370
STORMWATER POLLUTION PREVENTION PLAN (BDE 2342)	372
CONTRACTOR CERTIFICATION STATEMENT (BDE 2342A)	385
NOTICE OF INTENT (ILR10).....	386
KANE DUPAGE SOIL WATER CONSERVATION DISTRICT PERMIT	389
LPC 663	390
FAA COORDINATION	392
UNITED STATES ARMY CORPS PERMIT	397

TEMPORARY DRAINAGE SYSTEM NO. 1

Description. This work shall consist of furnishing all formwork, material, pipe, structures, equipment and labor to install and remove a temporary drainage system as shown in the plans. The contractor is responsible to provide positive drainage and maintain all existing drainage outlets. Any connection from the temporary drainage system necessary for the construction of the temporary MSE, permanent MSE or structures to the existing, temporary or proposed drainage system is included. This design is to be performed by the Contractor. This work shall also include any necessary diversions to ensure the system does not interfere with Contractor operations.

The temporary drainage system shall remain in place and operate until the no longer necessary as determined by the Engineer.

This work shall include the contractor maintaining conveyance of all flows during construction of the project. When existing drainage facilities are disturbed, the contractor shall provide and maintain temporary outlets and connections for public drains, sewers, culverts, and other drainage facilities. The contractor shall provide and maintain temporary outlets and be prepared at all times to dispose of the water received from these temporary connections until such time that the permanent connections with sewers or culverts are built and in service.

Design. The temporary drainage system shall be designed by the Contractor and approved by the Engineer. The design may include temporary connections, pipe, fasteners, connections, mounting brackets, temporary connections, temporary structures and pumps.

Construction Requirements: The Contractor shall submit, for approval by the Engineer, details of the temporary drainage system that is proposed to use, prior to ordering of material and implementation. All dewatering, pumping, formwork, labor, equipment and materials required for this work is included in the price for TEMPORARY DRAINAGE SYSTEM NO. 1.

Method of Measurement: This work shall be measured by the contract lump sum for TEMPORARY DRAINAGE SYSTEM NO. 1 as indicated on the Plans and specified herein.

Basis of Payment. This work will be paid for at the contract lump sum price for TEMPORARY DRAINAGE SYSTEM NO. 1.