



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 22, 2026

SUBJECT: TR Route 246 (Old Dad Joe Trail)  
Section (ORCB)BRR-1  
Bureau County  
Contract No. 66P22  
Item No. 31, July 31, 2026 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 10 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## **CLOSED-CIRCUIT TELEVISION DOME CAMERA, HD**

Description. This work shall consist of furnishing and installing an integrated Closed-Circuit Television (CCTV) Dome Camera Assembly, camera bracket, CAT 5 Ethernet cable and all other items required for installation and operation. This assembly shall contain all components identified in the Materials Section and shall be configured as indicated on the plan sheets.

### Materials.

The CCTV camera shall be **an Axis Model Q6086-E** Dome Camera Assembly for integration into the existing District 3 ITS system. The Illinois Department of Transportation shall be responsible for obtaining the cell phone modem. An antenna shall be provided by the Illinois Department of Transportation, on the mechanical building fascia for the camera system cellular modem.

The Contractor shall provide all materials required to install the proposed camera on the proposed wood pole on the north side of the Red Covered Bridge and to the existing light pole south, as shown on the plans.

The camera shall have great visibility for all 4 directions, the Red Covered Bridge, and the mechanical building.

The Contractor shall submit catalog cut sheets to the Department for all items (mounting brackets, hardware, etc.) that will be utilized for review prior to commencing work.

There will be proposed fiber optic cable used with the proposed CCTV cameras unless otherwise noted on the plan sheets.

The Contractor shall furnish and install new camera brackets at all locations. The proposed CAT 5 ethernet cable shall be terminated in the bracket terminal block (use IDC connector and pre-formed RJ-45 connector that is furnished with the camera bracket) in accordance with the manufacturer's instructions.

The Department will program the cameras prior to installation.

The camera shall meet or exceed the following specifications:

### CAMERA

|                |                                                                                                                                 |
|----------------|---------------------------------------------------------------------------------------------------------------------------------|
| VIDEO:         | 60 Hz (NTSC), 50 Hz (PAL)                                                                                                       |
| IMAGE SENSOR:  | 1/2.8" progressive scan CMOS                                                                                                    |
| LENS:          | 4.44–142.6 mm, F1.6–4.41<br>Horizontal angle of view: 62.8°–2.23°<br>Vertical angle of view: 36.8°–1.3°<br>Autofocus, auto-iris |
| DAY AND NIGHT: | Automatically removable infrared-cut filter                                                                                     |

Revised July 22, 2026