

I:\Projects\2023\22-1003 Ghent Road - Phase 1\20 Design\CADD\Sheets\Phase 2\22-1003-2_SQO.dwg, Plotted on: 7/13/2026 2:38 PM

SUMMARY OF QUANTITIES			
PAY ITEM NO.	PAY ITEM NAME	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	2168
20800150	TRENCH BACKFILL	CU YD	208
25000100	SEEDING CLASS 1	ACRE	0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54
25100115	MULCH METHOD 2	ACRE	0.6
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	54
28000400	PERIMETER EROSION BARRIER	FOOT	469
28000500	INLET AND PIPE PROTECTION	EACH	21
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2960
31101191	SUBBASE GRANULAR MATERIAL, TYPE B 3"	SQ YD	354
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1372
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	335
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	45
35400100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	SQ YD	708
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	43
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	750
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	6391
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	2200
40600990	TEMPORARY RAMP	SQ YD	44
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	821
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	526

SUMMARY OF QUANTITIES			
PAY ITEM NO.	PAY ITEM NAME	UNIT	QUANTITY
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	335
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5975
42400800	DETECTABLE WARNINGS	SQ FT	20
44000100	PAVEMENT REMOVAL	SQ YD	1201
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	345
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10
44000600	SIDEWALK REMOVAL	SQ FT	129
44004250	PAVED SHOULDER REMOVAL	SQ YD	174
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	28
50105220	PIPE CULVERT REMOVAL	FOOT	131
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	986
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	236
60100935	PIPE DRAINS 10"	FOOT	19
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	6
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	8
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2623
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	130

* SPECIALTY ITEM

I:\Projects\2022\22-1003 Ghent Road - Phase 1\20 Design\CADD\Sheet\Phase 2\22-1003-2_SCHEDULES.dwg, Plotted on: 7/13/2026 2:39 PM

STORM SEWER SCHEDULE				
PIPE NO.	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 - 12"	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 - 15"	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	PIPE DRAINS 10"
	FOOT	FOOT	FOOT	FOOT
P-1		190		
P-2	172			
P-3	139			
P-4	215			
P-5	31			
P-6	31			
P-7	31			
P-8	15			
P-9	31			
P-10	117			
P-11	121			
P-12			39	
P-13		18		
P-14		28		
P-15			47	
P-16	21			
P-17	31			
P-18	31			
P-19				19
TOTAL	986	236	86	19

DRAINAGE STRUCTURE SCHEDULE							
PT	MANHOLES, TYPE A, 4'-DIA., WITH TYPE 1 FRAME, OPEN LID	MANHOLES, TYPE A, 4'-DIA., WITH TYPE 3 FRAME AND GRATE (OPEN BACK)	INLETS, TYPE B, WITH TYPE 3 FRAME AND GRATE (OPEN BACK)	INLETS, TYPE A, WITH TYPE 3 FRAME AND GRATE (OPEN BACK)	INLETS, TYPE A, WITH TYPE 8 GRATE	PRECASE REINFORCED CONCRETE FLARED END SECTIONS 15"	INLETS, SPECIAL NO. 1
S-1			1				
S-2		1					
S-3			1				
S-4			1				
S-5				1			
S-6				1			
S-7				1			
S-8					1		
S-9				1			
S-10			1				
S-11			1				
S-12			1				
S-13	1						
S-14			1				
S-15						1	
S-16			1				
S-17							1
S-18				1			
S-19				1			
TOTAL	1	1	8	6	1	1	1