

SUMMARY OF QUANTITIES - CONT

SUMMARY OF QUANTITIES - CONT			COUNTY:	Jefferson				
			ROUTE:	FAS 2826, IL 37				
			FUNDING:	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
			LOCATION:	RURAL				
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	HSIP	041-2022	041-0097	041-0105
				0005	0021	0010	0059	0059
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	4,729	4,729				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	349		349			
42000060	WELDED WIRE REINFORCEMENT	SQ YD	176			176		
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	176			176		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	33		33			
44000100	PAVEMENT REMOVAL	SQ YD	1272	1096		176		
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	620	144			476	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	53,485	53,485				
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	2,363	2,363				
44004250	PAVED SHOULDER REMOVAL	SQ YD	66		66			
44200050	WELDED WIRE REINFORCEMENT	SQ YD	224	224				
44201373	CLASS C PATCHES, TYPE I, 12 INCH	SQ YD	4	4				
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	919	919				

△ REVISED 7-20-2026

REV - MS

MODEL: SQQ-3 [Sheet]
FILE NAME: c:\paw\work\paw\doc\colennm\110354\0978520-SumC-SQQ.dgn

	USER NAME = melissa.cole	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					2826	(41-8,1,2)RS-5,1B-1	Jefferson	408	10
		CHECKED -	REVISED -		CONTRACT NO. 78520							
	PLOT DATE = 5/29/2026	DATE -	REVISED -		SCALE:	SHEET 4	OF 15	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

SUMMARY OF QUANTITIES - CONT

SUMMARY OF QUANTITIES - CONT

			COUNTY:	Jefferson				
			ROUTE:	FAS 2826, IL 37				
			FUNDING:	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
			LOCATION:	RURAL				
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	HSIP	041-2022	041-0097	041-0105
				0005	0021	0010	0059	0059
44201381	CLASS C PATCHES, TYPE III, 12 INCH	SQ YD	777	777				
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	808	808				
44213204	TIE BARS, 3/4"	EACH	158	158	△			
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	234		234			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	38,851		38,851			
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	655		655			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	16		16			
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	184		184			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1			
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1			
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1			
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1		1			

△ REVISED 7-20-2026

REV - MS

MODEL: SQQ-4 [Sheet]
FILE NAME: c:\paw_work\paw\dot\colummd110354\0978520-SumC-SQQ.dgn

	USER NAME = melissa.cole	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					2826	(41-8,1,2)RS-5;1B-1	Jefferson	408	11
		CHECKED -	REVISED -		CONTRACT NO. 78520							
	PLOT DATE = 5/29/2026	DATE -	REVISED -		SCALE:	SHEET 5	OF 15	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

PATCHING SCHEDULE

LOCATION				CLASS C PATCHES, TYPE I	CLASS C PATCHES, TYPE II	CLASS C PATCHES, TYPE III	CLASS C PATCHES, TYPE IV	TIE BARS	COMMENTS
SB IL 37									
MP	FEET	FEET	SQ FT	SQ YD	SQ YD	SQ YD	SQ YD	EACH	
0.00	15	16	240	0.00	0.00	0.00	26.67	0	
0.07	10	12	120	0.00	13.33	0.00	0.00	0	
0.25	15	11	165	0.00	0.00	18.33	0.00	0	
0.35	5	11	55	0.00	6.11	0.00	0.00	0	
0.38	5	11	55	0.00	6.11	0.00	0.00	0	
0.41	5	11	55	0.00	6.11	0.00	0.00	0	
0.60	5	11	55	0.00	6.11	0.00	0.00	0	
0.68	8	11	88	0.00	9.78	0.00	0.00	0	
0.70	8	11	88	0.00	9.78	0.00	0.00	0	
0.75	15	11	165	0.00	0.00	18.33	0.00	0	
0.79	5	11	55	0.00	6.11	0.00	0.00	0	
0.80	10	11	110	0.00	12.22	0.00	0.00	0	
1.08	30	11	330	0.00	0.00	0.00	36.67	10	
1.20	8	11	88	0.00	9.78	0.00	0.00	0	
1.30	5	11	55	0.00	6.11	0.00	0.00	0	
1.40	10	11	110	0.00	12.22	0.00	0.00	0	
1.50	5	11	55	0.00	6.11	0.00	0.00	0	
1.80	5	11	55	0.00	6.11	0.00	0.00	0	
1.82	5	11	55	0.00	6.11	0.00	0.00	0	
1.84	5	11	55	0.00	6.11	0.00	0.00	0	
1.85	15	11	165	0.00	0.00	18.33	0.00	0	
1.90	10	11	110	0.00	12.22	0.00	0.00	0	
1.95	5	11	55	0.00	6.11	0.00	0.00	0	
1.99	5	11	55	0.00	6.11	0.00	0.00	0	
2.01	5	11	55	0.00	6.11	0.00	0.00	0	
2.05	8	11	88	0.00	9.78	0.00	0.00	0	
2.09	8	11	88	0.00	9.78	0.00	0.00	0	
2.10	5	11	55	0.00	6.11	0.00	0.00	0	
2.10	5	11	55	0.00	6.11	0.00	0.00	0	
2.18	5	11	55	0.00	6.11	0.00	0.00	0	
2.20	5	11	55	0.00	6.11	0.00	0.00	0	
2.39	50	11	550	0.00	0.00	0.00	61.11	17	
2.50	15	11	165	0.00	0.00	18.33	0.00	0	Edge gone
2.59	5	11	55	0.00	6.11	0.00	0.00	0	
2.70	50	11	550	0.00	0.00	0.00	61.11	17	
2.89	10	11	110	0.00	12.22	0.00	0.00	0	
2.90	15	11	165	0.00	0.00	18.33	0.00	0	
2.91	5	11	55	0.00	6.11	0.00	0.00	0	
2.98	5	11	55	0.00	6.11	0.00	0.00	0	
3.00	5	11	55	0.00	6.11	0.00	0.00	0	
3.15	12	11	132	0.00	14.67	0.00	0.00	0	
SB SUBTOTAL SHEET 1:				0.00	254.11	91.67	185.56	44	

PATCHING SCHEDULE

LOCATION				CLASS C PATCHES, TYPE I	CLASS C PATCHES, TYPE II	CLASS C PATCHES, TYPE III	CLASS C PATCHES, TYPE IV	TIE BARS	COMMENTS
SB IL 37									
MP	FEET	FEET	SQ FT	SQ YD	SQ YD	SQ YD	SQ YD	EACH	
3.16	8	11	88	0.00	9.78	0.00	0.00	0	
3.20	10	11	110	0.00	12.22	0.00	0.00	0	
3.28	5	11	55	0.00	6.11	0.00	0.00	0	
3.30	10	11	110	0.00	12.22	0.00	0.00	0	
3.45	5	11	55	0.00	6.11	0.00	0.00	0	
3.47	8	11	88	0.00	9.78	0.00	0.00	0	
3.50	5	11	55	0.00	6.11	0.00	0.00	0	
3.51	5	11	55	0.00	6.11	0.00	0.00	0	
3.60	5	11	55	0.00	6.11	0.00	0.00	0	
3.78	15	11	165	0.00	0.00	18.33	0.00	0	
3.80	8	11	88	0.00	9.78	0.00	0.00	0	
3.90	10	11	110	0.00	12.22	0.00	0.00	0	
4.00	5	11	55	0.00	6.11	0.00	0.00	0	
4.10	5	11	55	0.00	6.11	0.00	0.00	0	
4.20	5	11	55	0.00	6.11	0.00	0.00	0	
4.30	5	11	55	0.00	6.11	0.00	0.00	0	
4.40	5	11	55	0.00	6.11	0.00	0.00	0	
4.50	8	11	88	0.00	9.78	0.00	0.00	0	
4.62	5	11	55	0.00	6.11	0.00	0.00	0	
4.65	5	11	55	0.00	6.11	0.00	0.00	0	
4.70	5	11	55	0.00	6.11	0.00	0.00	0	
4.75	5	11	55	0.00	6.11	0.00	0.00	0	
4.78	5	6	30	3.33	0.00	0.00	0.00	0	
4.80	10	11	110	0.00	12.22	0.00	0.00	0	
4.82	5	11	55	0.00	6.11	0.00	0.00	0	
4.86	10	11	110	0.00	12.22	0.00	0.00	0	
4.90	10	11	110	0.00	12.22	0.00	0.00	0	
4.95	10	11	110	0.00	12.22	0.00	0.00	0	
5.05	20	8	160	0.00	0.00	17.78	0.00	0	
5.09	5	11	55	0.00	6.11	0.00	0.00	0	
5.10	5	11	55	0.00	6.11	0.00	0.00	0	
5.15	40	11	440	0.00	0.00	0.00	48.89	14	
5.18	30	11	330	0.00	0.00	0.00	36.67	10	
5.20	8	11	88	0.00	9.78	0.00	0.00	0	
5.21	15	11	165	0.00	0.00	18.33	0.00	0	
5.26	15	11	165	0.00	0.00	18.33	0.00	0	
5.50	5	11	55	0.00	6.11	0.00	0.00	0	
5.60	5	11	55	0.00	6.11	0.00	0.00	0	
SB SUBTOTAL SHEET 2:				3.33	250.56	72.78	85.56	24.00	
SB TOTAL:				3.33	504.67	164.44	271.11	68.00	
TOTAL				8	919	414	584	169	

MM 0.0 Start at Bunny farm Road

△ REVISED 7-20-2026

MODEL: Schedule-4 [Sheet]
FILE NAME: c:\pwworking\dwg\codermmd1110354\0978520-SHE-Schedules.dgn

	USER NAME = melissa.cole	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE			F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					2826	(41-8,1,2)RS-5;1B-1	Jefferson	408	35
		CHECKED -	REVISED -					CONTRACT NO. 78520				
	PLOT DATE = 7/16/2026	DATE -	REVISED -		SCALE:	SHEET 10	OF 19 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		