



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 22, 2026

SUBJECT FAS Route 2826 (IL 37)
Project HSIP-STP-8GMK(127)
Section (41-8,1,2) RS-5; 1B-1
Jefferson County
Contract No. 78520

Item No. 072, July 31st, 2026, Letting
Addendum C

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page 32 of the Special Provisions.
3. Revised sheets 20 and 134 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

DETOUR SIGNING

Description: This work shall consist of furnishing, installing, maintaining, relocating, and removing temporary detour signs as shown on the plans, as directed by the Engineer, in accordance with Section 701 of the Standard Specifications, and as herein specified.

Detour signs required under this item are those which are required to implement temporary detours during the roadway closures. The Contractor shall coordinate the roadway closure with the Engineer, local emergency services, and IDOT. Detour signs required under this item include barricades/drums, type III barricades, and all other temporary signs necessary to mark the detours as shown on the plan detour sheets. This work will also include covering existing signs that conflict with any of the detour signs and shall also include covering/removing the detour signs when the detour is not in effect as directed by the Engineer.

The Contractor shall coordinate the items of work to keep hazards and traffic inconveniences to a minimum. All detour signs shall be in new or like new condition at the start of the project. If a sign is damaged or becomes unreadable, the sign shall be replaced by a new or like new sign.

Road closure signs and barricades used and placed on IL 37 near the work zone shall be as shown on BLR 21-9.

Basis of Payment: This work will be paid for at the contract unit price per LUMP SUM for DETOUR SIGNING.

HOT-MIX ASPHALT SURFACE REMOVAL

Areas of PCC pavement or shoulders encountered during HMA surface removal operations shall be removed to the same depth as the adjacent HMA surface removal. This work shall be included in the cost of the hot-mix asphalt surface removal pay items