

MODEL: Unnamed Plan - Plan 3 [Sheet]
FILE NAME: S:\2025\25IL\037 - PTB 215-055 D9 - QEI - Var Ph I\IWO-1 IL-142 Culv Replace PH2\CADD\CADD Sheets\0978935-sht-SQO.dgn

CODE NO.	ITEM	UNIT	QUANTITY	CONSTRUCTION TYPE CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY	BOX CULVERT
				0010	0010
				RURAL	RURAL
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	95		95
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	168		168
50300300	PROTECTIVE COAT	SQ YD	18		18
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	40,560		40,560
50800515	BAR SPLICERS	EACH	172		172
50900207	STEEL RAILING, TYPE CO-10	FOOT	66		66
51500100	NAME PLATES	EACH	1		1
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	517		517
54003000	CONCRETE BOX CULVERTS	CU YD	208.6		208.6
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	152		152
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	87.5	87.5	
* 63000007	STEEL PLATE BEAM GUARDRAIL, TYPE B, 6 FOOT POSTS	FOOT	87.5	87.5	
* 63100119	TRAFFIC BARRIER TERMINAL, TYPE 14	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	

* SPECIALTY ITEM

△ REVISED 7-13-2026

REV - MS



QUIGG ENGINEERING INC

USER NAME = TOverton	DESIGNED - TAO	REVISED -
	DRAWN - TAO	REVISED -
	CHECKED - SDM	REVISED -
PLOT DATE = 6/4/2026	DATE - 05/08/2026	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES IL 142			
SCALE: NONE	SHEET 3	OF 5 SHEETS	STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
849	113B-2	JEFFERSON	67	6
		CONTRACT NO. 78935		
		ILLINOIS	FED. AID PROJECT	