F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2005-071 LS	COOK	39	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A77

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN 100% STATE QUANTITY	ROADWAY IDOT J000	ROADWAY CDOT J000	LANDSCAPING Y003
25000210	SEEDING, CLASS 2A	ACRE	0.52	0.52		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	116	47		69
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	89	47		42
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	75	47		28
25100630	EROSION CONTROL BLANKET	SQ YD	22,678	22678		
28000510	INLET FILTERS	EACH	24	24		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	5		5	
42001300	PROTECTIVE COAT	SQ YD	128		128	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	5		5	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	273		273	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5		5	
44000300	CURB REMOVAL	FOOT	18		18	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	35		35	
44000600	SIDEWALK REMOVAL	SQ FT	273		273	
44003100	MEDIAN REMOVAL	SQ FT	152		152	
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	66		66	
56104600	WATER VALVES 2"	EACH	4		4	
60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	18		18	
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	20		20	
67100100	MOBILIZATION	LSUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		
~~67000500~~	~~ENGINEER'S FIELD OFFICE, TYPE B~~	~~CAL MO~~	~~16~~	~~16~~		
B2006120	TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	25			25
K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	28.57			28.57
K0030470	PERENNIAL PLANTS, ORNAMENTAL GRASS TYPE	UNIT	41.38			41.38
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	49.06			49.06
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52		
X0325604	WEED CONTROL, PRE-EMERGENT HERBICIDE	GALLON	1			1
X0325103	WATER METER IN VAULT, 2 INCH	EACH	4		4	
X0325104	WATER TAP, 2 INCH	EACH	4		4	

CODE NO.	ITEM	UNIT	URBAN 100% STATE QUANTITY	ROADWAY IDOT J000	ROADWAY CDOT J000	LANDSCAPING Y003
X0325105	IRRIGATION SYSTEM	SQ YD	1,732		1,732	
X0325106	IRRIGATION SYSTEM FALL SHUT-DOWN	EACH	4		4	
X0325107	IRRIGATION SYSTEM SPRING START-UP	EACH	4		4	
X0325108	BACKFLOW PREVENTER (RPZ), 2 INCH	EACH	4		4	
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	152		152	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	LSUM	1	1		
XX006326	TYPE K COPPER PIPE 2"	FOOT	200		200	
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	15		15	
XX152400	SAND CUSHION, 3 INCH	CU YD	2.6		2.6	
Z0013798	CONSTRUCTION LAYOUT	LSUM	1	1		
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~				
A2002012	TREE, AESCULUS FLAVA (YELLOW SWEET BUCKEYE), 3" CALIPER, BALLED AND BURLAPPED	EACH	24			24
X0326146	SOIL CONDITIONER	SQ YD	3705			3,705
K1003460	LANDSCAPE MAINTENANCE	CAL MO	12			12
C2C06026	SHRUB, RHUS TYPHINA 'TIGER EYES',(TIGER EYES CUTLEAF STAGHORN SUMAC), 24" HEIGHT, CONTAINER	EACH	788			788

* DENOTES SPECIALTY ITEMS

CTE | AECOM

Rev.

S00-1

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET GATEWAY LANDSCAPING AND IRRIGATION

SUMMARY OF QUANTITIES

SCALE: NONE | DRAWN BY: RMG
DATE: MAY 02, 2008 | CHECKED BY: JAL

p:\p40468\chi\h29-gateway_irrigation\sht\221 (6.3rd)\s0221(012).sht 05/01/2008 12:54:22 PM