

EARTHWORK SCHEDULE							
STATION			20200100		20201200		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	
LINE "IL 120 NORTH FRONTAGE ROAD"			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
100+10.00	TO	101+00.00	1	1	11	4	-4
101+00.00	TO	102+00.00	0	0	7	10	-10
102+00.00	TO	103+00.00	0	0	17	14	-14
103+00.00	TO	104+00.00	0	0	14	10	-10
104+00.00	TO	105+00.00	12	11	13	2	9
105+00.00	TO	106+00.00	15	13	17	0	13
106+00.00	TO	107+00.00	11	10	15	0	9
107+00.00	TO	108+00.00	22	18	19	0	18
108+00.00	TO	109+00.00	26	22	20	0	21
109+00.00	TO	110+00.00	15	12	23	4	9
110+00.00	TO	111+00.00	3	2	22	6	-4
111+00.00	TO	112+00.00	0	0	10	2	-2
112+00.00	TO	113+00.00	0	0	3	1	-1
113+00.00	TO	114+00.00	0	0	5	2	-2
114+00.00	TO	115+00.00	0	0	3	0	0
115+00.00	TO	115+98.19	0	0	0	0	0
TOTALS			105	89	199	56	33

SUMMARY	
20201200	20200100
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION
(CU YD)	(CU YD)
199	105

FILE NAME = c:\p\pro\32291\32291\_32\design\p\32291\_32\_044-Schedule\_E.K.dgn



**Ciorba Group, Inc.**  
 CONSULTING ENGINEERS  
 5607 North Cumberland Avenue, Suite 402  
 Chicago, Illinois 60656  
 Tel: 773.775.4009 Fax: 773.775.4014

USER NAME = jcolemm  
 PLOT SCALE = 1:8000' / IN.  
 PLOT DATE = 6/3/2008

DESIGNED - NT  
 DRAWN - NT  
 CHECKED - WBL  
 DATE - MAY 2008

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 120 NORTH FRONTAGE ROAD  
 WILL AVENUE TO KNIGHT AVENUE  
 EARTHWORK SCHEDULE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
880	12 RS-3	LAKE	21	4A
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 60B45	