

STATE STANDARDS

SHEET NO. TITLE


1	TITLE SHEET
2	GENERAL NOTES, INDEX OF SHEETS
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	TRAFFIC CONTROL CONSTRUCTION STAGING PLAN
6	DETOUR PLAN
7	PLAN AND PROFILE
8	PAVEMENT MARKING PLAN
9	EROSION CONTROL PLAN
10-15	STRUCTURAL SHEETS FOR STRUCTURE NO. 045-2036
16	GUARDRAIL PLACEMENT PLAN / TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
17	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)  HIGHWAY STANDARDS

SHEET NO. TITLE

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-01	AREAS OF REINFORCEMENT REBARS
280001-04	TEMPORARY EROSION CONTROL SYSTEMS
442201-03	CLASS C AND CLASS D PATCHES
515001-02	NAME PLATE FOR BRIDGE
630001-07	STEEL PLATE BEAM GUARDRAIL
630101-07	GUARDRAIL MOUNTED ON EXISTING CULVERTS
630201-05	PCC/BITUMINOUS STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
630301-04	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
635006-02	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-01	REFLECTOR MARKER AND MOUNTING DETAILS
701201-02	LANE CLOSURE, 2L, 2W DAY ONLY FOR SPEEDS >.45 MPH
701301-02	LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS
701901	TRAFFIC CONTROL DEVICES
704001-04	TEMPORARY CONCRETE BARRIER
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
720011	METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS
729001	APPLICATION OF TYPES A & B METAL POSTS (FOR SIGN & MARKERS)
780001-01	TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

1. ALL ELEVATIONS ARE BASED ON UNITED STATES COAST AND GEODETIC SURVEY DATUM.
2. DIMENSIONS ARE IN ENGLISH UNITS UNLESS OTHERWISE NOTED.
3. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED).
4. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
5. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
6. ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT LISTED IN THE PLANS WITH THE LATEST NUMBERS.
7. DURING CONSTRUCTION OPERATIONS, LOOSE MATERIAL DEPOSITS THAT OBSTRUCT THE FLOW OF WATER IN DRAINING THE AREA SHALL BE REMOVED BEFORE THE END OF EACH WORK DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES (NEW AND EXISTING) SHALL BE FREE FROM ALL DIRT AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
8. THE REMOVAL OF GUARDRAIL TERMINAL SECTIONS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER LINEAL FOOT OF STEEL PLATE BEAM GUARDRAIL REMOVAL.
9. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING PROPERTIES.
10. THE CONTRACTOR SHALL NOTIFY THE AREA TRAFFIC FIELD ENGINEER, DON CHIARUGI AT (847) 741-9857 AT LEAST 72 HOURS PRIOR TO FINAL PAVEMENT MARKING INSTALLATION.
11. THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
12. ALL UNBLASTED TYPE I AND TYPE II BARRICADES SHALL HAVE TWO (2) SANDBAGS ON THE BOTTOM RAIL.
13. ALL WORK IS TO BE COMPLETED WITHIN FIVE WEEKENDS. NO WORK WILL BE ALLOWED DURING SPECIAL EVENTS HELD FOR EAST AND WEST DUNDEE, AND FOR THE THE VILLAGE OF ALGONQUIN. THE COMPLETION DATE FOR THIS CONTRACT IS NOVEMBER 17, 2008.



USER NAME = #USER*	DESIGNED - MJY	REVISED -
PLOT SCALE = #SCALE*	DRAWN - ZDA	REVISED -
PLOT DATE = #DATE*	CHECKED - MJY	REVISED -
	DATE - 05/27/2008	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>GENERAL NOTES, INDEX OF SHEETS IL ROUTE 31</b>		
SCALE: NONE	SHEET NO. 2 OF 17 SHEETS	STA. 37+24 TO STA. 37+60

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-T-1	KANE	17	2
D-91-076-08			CONTRACT NO. 60E50	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				