CONTRACT NO. 64939

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	*	43	8
STA. _____	TO STA._____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* WHITESIDE & ROCK ISLAND

BRIDGE APPROACH PAVEMENT SCHEDULE

LOCATION (STA TO STA)	42001165 BRIDGE APPROACH PAVEMENT	50300300 PROTECTIVE COAT
	SQ YD	SQ YD
STA 427+40.43 TO STA 427+70.43	111	111
STA 428+71.17 TO STA 429+01.17	111	111
TOTAL	222	222

44000700

APPROACH SLAB REMOVAL

LOCATION	SQ YD
STA 427+77.50 TO STA 427+97.40	57
STA 428+44.40 TO STA 428+64.30	57
TOTAL	114

542D0220

PIPE CULVERTS,CLASS D, TY 1, 15"

LOCATION	FOOT
LT. STA. 435+00 (FIELD ENTRANCE)	76
LT. STA. 429+11 (FIELD ENTRANCE) *	68
TOTAL	144

54213450

END SECTIONS, 15"

LOCATION	EACH
LT. STA. 435+00 (FIELD ENTRANCE)	2
LT. STA. 429+11 (FIELD ENTRANCE) *	1
TOTAL	3

60801015

FLAP GATE, 15" *

LOCATION	EACH
STA 428+82, LT	1
TOTAL	1

* PROVISIONAL PAY ITEM SHOULD THE ENGINEER DETERMINE THE CULVERT AT THIS LOCATION DOES NOT OPERATE PROPERLY.

63000000

STEEL PLATE BEAM GUARD RAIL, TYPE A

LOCATION	FOOT
STA 425+55.30 TO STA 427+17.80, RT.	162.5
STA 429+04.80 TO STA 429+79.80, RT.	75.0
STA 429+23.80 TO STA 430+61.30, LT.	137.5
TOTAL	375

63000130

STEEL PLATE BEAM GUARD RAIL, TYPE A, (SPECIAL)

LOCATION	FOOT
STA 427+29.13, LT	25
TOTAL	25

63100045

TRAFFIC BARRIER TERMINAL, TYPE 2

LOCATION	EACH
STA 427+29.13, LT.	1
TOTAL	1

63100085

TRAFFIC BARRIER TERMINAL, TYPE 6

LOCATION	EACH
STA 427+17.80 TO STA 427+60.95, RT.	1
STA 427+36.80 TO STA 427+79.91, LT.	1
STA 428+61.69 TO STA 429+04.80, RT.	1
STA 428+80.65 TO STA 429+23.80, LT.	1
TOTAL	4

63100167

TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)

LOCATION	EACH
STA 425+55.30, RT.	1
STA 429+79.80, RT.	1
TOTAL	2

63100169

TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (FLARED)

LOCATION	EACH
STA 430+61.3	1
TOTAL	1

63200310

GUARDRAIL REMOVAL

LOCATION	FOOT
STA 426+70 TO STA 427+60, RT.	90
STA 427+68 TO STA 427+89, LT.	37
STA 428+62 TO STA 429+52, RT.	90
STA 428+83 TO STA 428+95, LT.	24
TOTAL	241

63500105

DELINEATORS

LOCATION	EACH
STA 425+05.35, RT.	1
STA 430+29.8, RT.	1
STA 431+11.3, LT.	1
TOTAL	3

PAINT PAVEMENT MARKING

	78001110	
	4" YELLOW	4" WHITE
LOCATION	FOOT	FOOT
STA 423+75 TO STA 432+25	420	3400
(2 APPLICATIONS)		
TOTAL	3820	

78200410

GUARDRAIL MARKERS, TYPE A

LOCATION	EACH
STA 425+05.3 TO STA 430+29.8, RT	5
STA 427+29.13 TO STA 431+11.26, LT	3
TOTAL	8

78200520

BARRIER WALL MARKERS, TYPE B *

LOCATION	EACH
BRIDGE	4
TOTAL	4

* MARKERS SHALL BE BIDIRECTIONAL SILVER/ SILVER

78201000

TERMINAL MARKER – DIRECT APPLIED

LOCATION	EACH
AT EACH TYPE 1 TERMINAL	3
TOTAL	3

TREE REPLACEMENT SCHEDULE

CODE NO.	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY
A2007814	TILIA AMERICANA	AMERICAN LINDEN/BRASSWOOD	1–3/4"	EACH	6

(SEE GENERAL NOTE 33 ON SHEET 2)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTTITES
FAS 203 (MOLINE ROAD)
SECTION 11BR-1
WHITESIDE & ROCK ISLAND COUNTIES

SCALE: VERT. HORIZ.
DATE: 12/05
DRAWN BY ARR
CHECKED BY JKC

PLOT DATE = 10/07
FILE NAME = ZPR003SCHED
PLOT SCALE = NONE
USER NAME = CHAHS