

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				URBAN ROADWAY 100% STATE 0005
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5302	5302
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1656	1656
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	120739	120739
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4338	4338
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	320	320
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2802	2802
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1028	1028
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1656	1656
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	120839	120839
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4338	4338
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	320	320
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2802	2802
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1092	1092

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				URBAN ROADWAY 100% STATE 0005
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1411	1411
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1411	1411
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2998	2998
X0327611	REMOVE AND REINSTALL BRICK PAVER	SQ FT	424	424
X2020110	GRADING AND SHAPING SHOULDERS	UNITS	100	100
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	90888	90888
X5537800	STORM SEWERS TO BE CLEANED, 12"	FOOT	300	300
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	619	619
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0076600	TRAINEES	HOUR		
70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1

* - SPECIALTY ITEM

FILE NAME : I:\6710\6710.05 - 3P Resurfacing Project	USER NAME : mrompfa	DESIGNED - RC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 134 (MAIN STREET) SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	Plana\60N58\CADD\C400 Sheets\60N58_500.dwg	DRAWN - RC	REVISED -			D186	36-RS-5	LAKE	31	4	
	PLOT SCALE = 100.0000' / in.	CHECKED - MGR	REVISED -			CONTRACT NO. 60N58					
	PLOT DATE = 5/27/2014	DATE - 5/27/2014	REVISED -			ILLINOIS FED. AID PROJECT					