SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17	17					
25200110	SODDING, SALT TOLERANT	SQ YD	17	17					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	74	74					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2015	2015					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	137	137					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4115	4115					
42001300	PROTECTIVE COAT	SQ YD	34	34					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	48986	48986					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	740	740					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	120	120					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	120	120					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	626	626					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	28636	28636					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37587	37587					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	58	58					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12645	12645					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37587	37587					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	58	58					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	252	252					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	245	245					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	278	278					
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	33250	33250					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	206	206					

* Specialty Items

FILE NAME = c:\pw_work\pwidot\razagam\d0313240\D752712-sht-plan.dgn	USER NAME = razagam	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 303	SECTION 131RS-5	COUNTY MCHENRY	TOTAL SHEETS 21	SHEET NO. 3
		DRAWN -	REVISED -					CONTRACT NO. 60V20		
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		
	PLOT DATE = 5/20/2014	DATE -	REVISED -							

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT