

SUMMARY OF QUANTITIES				URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	0005										
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	583	583									
25200110	SODDING, SALT TOLERANT	SQ YD	583	583									
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	30	30									
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19	19									
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	704	704									
40600895	CONSTRUCTING TEST STRIP	EACH	1	1									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	220	220									
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1438	1438									
42001300	PROTECTIVE COAT	SQ YD	860	860									
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	30	30									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	700	700									
42400800	DETECTABLE WARNINGS	SQ FT	224	224									

SUMMARY OF QUANTITIES				URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	0005										
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	12800	12800									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	60	60									
44000600	SIDEWALK REMOVAL	SQ FT	700	700									
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	50	50									
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	100									
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	65	65									
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3									
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2									
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5									
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	16	16									
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	30	30									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4									
67100100	MOBILIZATION	L SUM	1	1									
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1									