

SEEDING SCHEDULE	
LOCATION	FURNISHED EXCAVATION*
	CU YD
CREGO RD NORTH 1100E	4
CREGO RD SOUTH 1100E	4
HOWISON RD NORTH 1200E	4
HOWISON RD SOUTH 1200E	4
GOV BEVERIDGE RD NORTH 1400E	4
GOV BEVERIDGE RD SOUTH 1400E	4
STAFAER LANE NORTH	4
TOTALS	28

*THESE AREAS TO BE SEEDED, FERTILIZED AND MULCHED-
INLCUDED IN THE COST OF FURNISHED EXCAVATION

FOLDER 30-3			CONTRACT NO. 66B12		
US RTE. 30		W OF PINE ST IN WATERMAN TO W OF SOMONAUK RD. IN HINCKLEY		DEKALB CO.	
GPS POINT NUMBER OR INDEX NUMBER	DESCRIPTION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
237700	E OTR COR SEC 15-38-4E WILL BE REPLACED EITHER ON RTE 23, OR RTE 30 RESURFACING JOB	BRONZE DISK	TYPE 1	YES	1
30800	W OTR COR SEC 18-38-5E	PK NAIL	TYPE 1	YES	1
<p>THIS NOTE TO BE INCLUDED IN PLANS: LISTED MONUMENT LOCATIONS HAVE BEEN RECORDED BY GPS. PRE CONSTRUCTION TIES BY THE R.E. ARE NOT REQUIRED. IF AN UNLISTED MONUMENT IS FOUND, IT MUST BE TIED BY THE R.E. AND BROUGHT TO THE ATTENTION OF THE PLATS AND PLANS MANAGER. AFTER RESURFACING, THE R.E. IS TO CONTACT THE PLATS AND PLANS MANAGER TO ESTABLISH LOCATIONS FOR PERMANENT SURVEY MARKER CORING.</p> <p>RESPONSIBILITY: 1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1) 2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT</p>					

DRAINAGE SCHEDULE				
LOCATION		FRAMES & LIDS TO BE ADJUSTED SPECIAL	WATER VALVES TO BE ADJUSTED SPECIAL	DESCRIPTION
STATION	OFFSET	EACH	EACH	
458+54	11.8' RT		1	WATER VALVE
463+95	13.6' LT	1		STORM MANHOLE
466+25	33.8' RT	1		STORM MANHOLE
469+92	24.5' LT	1		SANITARY MANHOLE
470+39	8.0' LT	1		STORM MANHOLE
TOTAL		4	1	

ELECTRICAL US 30 / ELM ST.		
LOCATION	DETECTOR LOOP TYPE 1	LEAD-IN NO. 14 1 PAIR
	FOOT	FOOT
US 30 EB LEFT TURN	248	336
US 30 EB THRU	121	336
US 30 WB LEFT TURN	260	91
US 30 WB THRU	137	91
ELM ST. NB THRU	129	184
ELM ST. SB THRU	121	115
TOTAL	1016	1153