

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE
				100% STATE FAS 379 KNOX RURAL 0005
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	80	80
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	265	265
28100125	STONE RIPRAP, CLASS B3	SQ YD	108	108
28200200	FILTER FABRIC	SQ YD	108	108
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	240	240
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3
40600285	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POUND	6000	6000
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	565	565
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1721	1721
44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3510	3510
44000156	HOT - MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	8482	8482
44000400	GUTTER REMOVAL	FOOT	280	280
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	229	229
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	881	881
48101200	AGGREGATE SHOULDERS, TYPE B	TON	92	92

* SPECIALTY ITEMS

△ REVISED 7-21-14

FILE NAME : 0468898-typical.dgn	USER NAME : aubreyga	DESIGNED -	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE. 379	SECTION (101, 111)RS-3	COUNTY KNOX	TOTAL SHEETS 33	SHEET NO. 3
PLOT SCALE : 100.0000 / in	CHECKED -	REVISD -	CONTRACT NO. 68898							
PLOT DATE : 5/16/2014	DATE -	REVISD -	ILLINOIS FED. AID PROJECT							