

## SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HENDERSON COUNTY ROADWAY 0005 100% STATE	WARREN COUNTY ROADWAY 0005 100% STATE
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	30,007	14,413	15,594
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	33	11	22
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	7	3	4
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,283	616	667
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	LSUM	1	0.5	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	5	5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	101,562	49,248	52,314
X0327301	RELOCATE EXISTING MAILBOX	EACH	6	3	3
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	30,007	14,413	15,594

\* SPECIALTY ITEM

FILE NAME : 68C07 - IL 116 Henderson and Warren.dgn	USER NAME : soubrygg	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>					F.A.P. RTE. 665	SECTION 137W-1; 138, 139W-2	COUNTY HENDERSON/ WARREN	TOTAL SHEETS 15	SHEET NO. 3
Default	PLOT SCALE * 100.0000' / 1"	CHECKED -	REVISED -		NOT TO SCALE	SHEET 1	OF 1	SHEETS	STA.	TO STA.	CONTRACT NO. 68C07			
	PLOT DATE * 5/21/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT									