

SCHEDULE OF HMA WIDENING QUANTITIES											
				OMISSION NOTES	LENGTH	AREA	AGGREGATE WEDGE SHOULDER, TY B	HMA BASE CSE WIDENING, 9"	PAVEMENT REMOVAL (SPECIAL)	POLYMERIZED BIT. MAT. (PRIME COAT)	
											FEET
HENDERSON COUNTY											
LT.	STA.	224+95.30	TO	230+18.15		522.85	174.28	7.45	174.28	174.28	0.04
LT.	STA.	230+18.15	TO	230+22.15	4'X6' BOX						
LT.	STA.	230+22.15	TO	243+78.87		1,356.72	452.24	19.33	452.24	452.24	0.10
LT.	STA.	243+78.87	TO	243+80.87	2'X2' BOX						
LT.	STA.	243+80.87	TO	286+04.40		4,223.53	1,407.84	60.19	1,407.84	1,407.84	0.31
LT.	STA.	286+04.40	TO	286+66.24	850 N						
LT.	STA.	286+66.24	TO	308+40.16		2,173.92	724.64	30.98	724.64	724.64	0.16
LT.	STA.	308+40.16	TO	308+43.16	3'X3' BOX						
LT.	STA.	308+43.16	TO	319+80.36		1,137.20	379.07	16.21	379.07	379.07	0.08
LT.	STA.	319+80.36	TO	319+82.36	24" PIPE						
LT.	STA.	319+82.36	TO	334+98.44		1,516.08	505.36	21.60	505.36	505.36	0.11
LT.	STA.	334+98.44	TO	334+99.94	18" PIPE						
LT.	STA.	334+99.94	TO	339+11.51		411.57	137.19	5.86	137.19	137.19	0.03
LT.	STA.	339+11.51	TO	339+63.36	750 N						
LT.	STA.	339+63.36	TO	358+64.63		1,901.27	633.76	27.09	633.76	633.76	0.14
LT.	STA.	358+64.63	TO	370+00.00	WYE						
LT.	STA.	370+00.00	TO	390+12.11		2,012.11	670.70	28.67	670.70	670.70	0.15
LT.	STA.	390+12.11	TO	390+14.11	2'X2' BOX						
LT.	STA.	390+14.11	TO	416+00.15		2,586.04	862.01	36.85	862.01	862.01	0.19
LT.	STA.	416+00.15	TO	416+53.00	2000 E						
LT.	STA.	416+53.00	TO	452+86.98		3,633.98	1,211.33	51.78	1,211.33	1,211.33	0.27
LT.	STA.	452+86.98	TO	469+79.52	GUTTER						
SUB-TOTAL:								306.02	7,158.42	7,158.42	1.57

FILE NAME =	USER NAME = aubreygs	DESIGNED -	REVISED -
68C07 - IL 116 Henderson and Warren.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/21/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	137W-1r (138, 139)W-2	HENDERSON/ WARREN	15	6
CONTRACT NO. 68C07				
ILLINOIS FED. AID PROJECT				